

US ROCKIES REGION
Operation Summary Report

Well: DEEPE CARL R #2		Spud date: 11/16/1982	
Project: COLORADO-WELD-NAD83-UTM13		Site: DEEPE CARL R #2	Rig name no.: CONCORD 6/6
Event: CONST- CAP WELL WORK		Start date: 12/4/2013	End date:
Active datum: RKB @5,018.99usft (above Mean Sea Level)		UWI: 0/2/N/67/W/22/0/NWNE/6/PM/N/1,320.00/W/0/1,320.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
12/16/2013	6:00 - 6:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO LOC
	6:30 - 7:00	0.50	WO/REP	30		P		SAFETY MEETING, START EQUIPMENT
	7:00 - 8:30	1.50	MIRU	30	A	P		MOVE FROM FREUND L 07-06, MIRU, SPOT EQUIPMENT, RIG UP
	8:30 - 9:30	1.00	WO/REP	46	F	Z		WAIT FOR AUTOMATION TO BE REMOVED
	9:30 - 11:00	1.50	WO/REP	30	F	P		CONTROL WELL, NDWH, NUBOP.
	11:00 - 14:30	3.50	WO/REP	31	I	P		EMI TBG, TOOH SB, TALLY, 21 YEL, 148 BLUE, 80 RED
	14:30 - 16:00	1.50	WO/REP	31	I	P		TIH W/ RBP,RET HEAD, XN & 226 JTS
	16:00 - 16:30	0.50	WO/REP	31	G	P		SET RBP @ 7310'
	16:30 - 17:00	0.50	WO/REP	30		P		DRAIN EQUIP, SECURE WELL, INSTALL TIW, SDFN
	17:00 - 17:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO YARD
12/17/2013	6:00 - 6:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO LOC
	6:30 - 7:00	0.50	WO/REP	30		P		SAFETY MEETING, START EQUIP
	7:00 - 9:00	2.00	WO/REP	31	H	P		CIRC WELL
	9:00 - 9:30	0.50	WO/REP	52	G	P		2000# CSG TEST (GOOD TEST)
	9:30 - 10:00	0.50	WO/REP	30	F	P		NDBOP, ND CSG HEAD
	10:00 - 11:30	1.50	WO/REP	30		P		WELD SURFACE PLATE AND BELL NIPPLE
	11:30 - 12:30	1.00	WO/REP	30		P		ALLOW WELDS TO COOL
	12:30 - 13:00	0.50	WO/REP	30	F	P		SPIN ON NEW 5K WELLHEAD, NUBOP
	13:00 - 14:30	1.50	WO/REP	31	I	P		LD RED BAND TBG.
	14:30 - 16:00	1.50	WO/REP	31	I	P		PU YELLOW BAND TBG TIH TAG RBP W/ 228 JTS. LD 3 JTS.
16:00 - 16:30	0.50	WO/REP	30		P		225 JTS, XN, RET 4 1/2 RBP RET HEAD IN HOLE NDBOP, NUWH	
16:30 - 17:00	0.50	WO/REP	30		P		DRAIN EQUIP, SDFN	
17:00 - 17:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO YARD4800	
12/18/2013	6:00 - 6:30	0.50	WO/REP	30	G	P		CREW TRAVEL TO LOC
	6:30 - 7:00	0.50	WO/REP	30		P		SAFETY MEETING, START EQUIP
	7:00 - 7:30	0.50	WO/REP	30		P		DUMP 2 SX SND, PUMP DOWN & LOAD HOLE
	7:30 - 8:00	0.50	WO/REP	52	G	P		5K CSG / WELLHEAD TEST 15 MIN, GOOD TEST
	8:00 - 9:00	1.00	RDMO	30	C	P		RDMO