

US ROCKIES REGION  
**Operation Summary Report**

Well: <b>RADEMACHER 16-25A</b>		Spud date: 12/31/2001	
Project: COLORADO-WELD-NAD83-UTM13		Site: RADEMACHER 16-25A	
Event: CONST- CAP WELL WORK		Start date: 9/22/2014	End date:
Active datum: RKB @4,864.99usft (above Mean Sea Level)		UWI: 0/3/N/68/W/25/0/SESE/6/0/S/-470/E/0/850/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
9/22/2014	10:00 - 12:00	2.00	WO/REP	35		P		fish, tag
	12:00 - 16:00	4.00	WO/REP					level up for base beam, moved concrete barriers
	16:00 - 18:00	2.00	WO/REP	30	A	P		MIRU Concord 9
9/23/2014	6:00 - 7:00	1.00	WO/REP	30		P		crew travel
	7:00 - 9:00	2.00	WO/REP	30		P		control well
	9:00 - 10:00	1.00	WO/REP	30		P		ND WH, NU BOP
	10:00 - 12:30	2.50	WO/REP	31	I	P		TOOH, EMI tbg. 2 scanned bad, 2 crimped
	12:30 - 14:30	2.00	WO/REP	31	I	P		TIH w scraper to 7380'
	14:30 - 16:30	2.00	WO/REP	31	I	P		TOOH, LD scraper
	16:30 - 17:30	1.00	WO/REP	30		P		SDFN
9/24/2014	6:00 - 7:00	1.00	WO/REP	30	G	P		crew travel
	7:00 - 8:00	1.00	WO/REP	30		P		control well
	8:00 - 10:00	2.00	WO/REP	31	I	P		TIH w rbp
	10:00 - 12:00	2.00	WO/REP	30		P		test RBP. NU new WH, test to 1000#, good
	12:00 - 14:00	2.00	WO/REP	31	I	P		Release RBP, TOOH, LD RBP
	14:00 - 16:00	2.00	WO/REP	31	I	P		TIH w bit, sub, 232 jts
	16:00 - 17:00	1.00	WO/REP	30	G	P		SDFN
9/25/2014	6:00 - 7:00	1.00	WO/REP	30	G	P		crew travel
	7:00 - 8:00	1.00	WO/REP	30		P		control well
	8:00 - 12:00	4.00	WO/REP	31	H	P		<b>Drill CIBP @ 7550, pushed to PB, rolled hole clean</b>
	12:00 - 13:00	1.00	WO/REP	30		P		LD swivel
	13:00 - 15:00	2.00	WO/REP	31	I	P		TOOH
	15:00 - 17:00	2.00	WO/REP	31	I	P		TIH, land @ 7637' w 241 jts
	17:00 - 18:00	1.00	WO/REP	30		P		broach
	18:00 - 19:00	1.00	WO/REP	30		P		ND, NU
19:00 - 20:00	1.00	WO/REP	30		P		RDMO	