

US ROCKIES REGION
Operation Summary Report

Well: BROTEMARKLE 13-24				Spud date: 4/20/2004					
Project: COLORADO-WELD-NAD83-UTM13			Site: BROTEMARKLE 13-24				Rig name no.: BASIC 1557/1557, CONCORD 4/4		
Event: CONST- CAP WELL WORK			Start date: 11/19/2014					End date:	
Active datum: RKB @5,021.99usft (above Mean Sea Level)				UWI: 0/3/N/66/W/24/0/SWSW/6/0/0/0/0/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation	
9/3/2014	16:00 - 18:00	2.00	WO/REP	30	A	P		MIRU CONCORD 4.	
	18:00 - 19:00	1.00	WO/REP	30	G	P		CT TO YARD.	
9/4/2014	6:00 - 7:00	1.00	WO/REP	30	G	P		CT to location.	
	7:00 - 9:00	2.00	WO/REP	30	E	P		CP-TP=700, BD-KW w/ 50 bbls.	
	9:00 - 9:30	0.50	WO/REP	30	F	P		ND TH, NU BOP-WF.	
	9:30 - 12:00	2.50	WO/REP	45	A	P		RU Pick testers, POOH,EMI,SB,Tally tbq.	
	12:00 - 14:00	2.00	WO/REP	34	I	P		RU WL,RIH w/ G-ring,j-basket to 7150,RIH set RBP @ 7080.RD Wireline.	
9/5/2014	14:00 - 15:00	1.00	WO/REP	31	I	P		TIH w/ 104 jts.fan belts broke,SWI-SDFN.	
	15:00 - 16:00	1.00	WO/REP	30	G	P		CT to yard.	
	6:00 - 7:00	1.00	WO/REP	30	G	P		CT to location.	
	7:00 - 8:00	1.00	WO/REP	31	I	P		Finish TIH w/ 224 jts.	
	8:00 - 9:00	1.00	WO/REP	31	H	P		Circ.gas out.	
	9:00 - 9:30	0.50	WO/REP	52	F	P		PT csg. to 2K, held.	
	9:30 - 11:00	1.50	WO/REP	31	I	P		POOH,SB tbq.	
	11:00 - 13:00	2.00	WO/REP	31	I	P		TIH w/ RBP, set @ 6960. Spot 2 sx.sand.	
	13:00 - 17:00	4.00	WO/REP	31	I	P		TOOH,LD tbq.on trailer.	
	17:00 - 17:30	0.50	WO/REP	30	F	P		ND BOP, WH. NU 5K Frac valve,SWI.	
11/19/2014	17:30 - 18:30	1.00	WO/REP	30	C	P		RDMO Concord 4.	
	6:00 - 10:00	4.00		30	A	P		MIRU BASIC 1557	
	10:00 - 11:00	1.00		53	B	P		DIG OUT WELL WH	
	11:00 - 11:30	0.50		30	F	P		ND FRAC VALVE, UNLAND CSG, ND SURFACE HEAD	
	11:30 - 12:30	1.00		53	C	P		CUT SURFACE PIPE, WELD 8.625" SLIP COLLAR	
	12:30 - 13:00	0.50		30	F	P		NU SURFACE HEAD, LAND CSG	
	13:00 - 14:00	1.00		53	C	P		CUT CSG & WELD 4.5" BELL NIPPLE	
	14:00 - 14:30	0.50		30	F	P		NU TA VALVE	
2/11/2015	14:30 - 17:00	2.50		30	C	P		RDMO	
	-	-							