

# WELLBORE DIAGRAM

CURRENT WBD

600' FNL 660' FEL

Operator: Blue Chip Oil  
Well Name: Sloan #1  
Lease Number:  
Location: NENE Sec 25 6N 67W  
Field: LaPoudre South  
County, State: Weld Co., CO  
API Number: 05-123-13536  
Diagram Date: 1/28/2016  
Lat/Long: 40.46372/-104.83489

KB ' 4754

GL ' 4745

Spud Date: 9/24/1987  
Completion Date: 10/10/1987

## Surface Casing

9-5/8" Surf CSG set @ 319' (12-1/4" Hole)  
Cmt'd w/ 200 sks to surf.

Base of Fox Hills or Deepest Offset Water Well: 480 ft

Base Upper Pierre: 1190 ft

TOC = 6380 ft (need to confirm with CBL)

## Notes:

- re-frac/test to 5000 psi 12/28/2010
- Tag 6448 ft w/ 3.634" RBP (pull over 12,000 lbs)
- Ran 3.562" gauge ring no tag
- Ran 3.59" gauge ring to 7000 ft no tag

## Niobrara Perfs:

6920-6942

## Codell Perfs:

7083-7103

CIBP w/ 2 sx: 7400'

## J Sand Perfs:

7564-7588

## Production Casing

4-1/2" 15.1# CSG set @ 7669' (7-7/8" Hole)  
Cm'd w/ 275 sks

Niobrara = 6860'

Codell = 7084'

J Sand = 7562'

## Production Tubing:

218 jnts 2 3/8" set at 6923 ft

PBTD = 7643'  
TD = 7672'