

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400988389

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: Jennifer Thomas

Name of Operator: KERR MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6808

Address: P O BOX 173779

Fax:

City: DENVER

State: CO

Zip: 80217-

API Number 05-123-42205-00

County: WELD

Well Name: ALVIN

Well Number: 2C-29HZ

Location: QtrQtr: SESE Section: 29 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 294 feet Direction: FSL Distance: 364 feet Direction: FEL

As Drilled Latitude: 40.103042 As Drilled Longitude: -104.679628

## GPS Data:

Date of Measurement: 11/18/2015 PDOP Reading: 3.0 GPS Instrument Operator's Name: Sergio Del Carmen

\*\* If directional footage at Top of Prod. Zone Dist.: 135 feet. Direction: FSL Dist.: 1558 feet. Direction: FEL

Sec: 29 Twp: 2N Rng: 65W

\*\* If directional footage at Bottom Hole Dist.: 78 feet. Direction: FNL Dist.: 1594 feet. Direction: FEL

Sec: 29 Twp: 2N Rng: 65W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 11/12/2015 Date TD: 12/14/2015 Date Casing Set or D&amp;A: 12/15/2015

Rig Release Date: 01/03/2016 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 13010 TVD\*\* 7269 Plug Back Total Depth MD 12902 TVD\*\* 7269

Elevations GR 4908 KB 4924 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

CBL, GR, OHL

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	76	52	0	76	VISU
SURF	13+1/2	9+5/8	36	0	1,921	773	0	1,921	VISU
1ST	8+1/2	5+1/2	17	0	12,996	1,860	18	12,996	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,590				
SHARON SPRINGS	7,257				
NIOBRARA	7,298				
FORT HAYS	7,725				
CODELL	7,803				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.  
Per Rule 371.p Exception, open hole resistivity logs have been run on the Alvin 2C-29HZ well (API 05-123-42205).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Jennifer Thomas

Title: Regulatory Specialist

Date: \_\_\_\_\_

Email: rscdjpostdrill@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400988425	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400988424	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400988407	PDF-RESISTIVITY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400988412	LAS-RESISTIVITY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400988416	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400988417	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400988421	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400996788	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400996791	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)