

Noble Energy, INC
UPRR-WELLS 01
05-123-07136

Proposed Wellbore Schematic

Re-enter and re-plug

KB elev - 4897'

GL elev - 4886'

Weld cap on 8.625" sur csg

8.625" surf csg set @ 143'
130sxs cement to surface

Deepest Water well: 196'

Base Fox Hills 362'

Balanced cement plug: 0'/475'
200sxs cement

Balanced cement plug: 3750'/4000'
95sxs cement

7.865" Open Hole to TD

TD = 7206'