



WELLBORE DIAGRAM

CURRENT WBD

660' FSL 1980' FEL

Operator: Great Western Oil & Gas Company
 Well Name: UPRR-Meyer 1
 Lease Number:
 Location: SWSE, 9 2S 63W
 Field: Wattenberg
 County, State: Adams Co., CO
 API Number: 05-001-06793
 Diagram Date: 2/16/2016
 Lat/Long: 39.884892/-104.438772

KB ' 5205

GL ' 5194

Spud Date: 3/8/1974

Completion Date: 10/22/1974

Producing Formation: J-Sand

Surface Casing

12 1/4" hole size, 8 5/8" 24# CSG Set @ 212' KB (5 jts.)
 Cmt w/ 200 sks reg cmt. And 3% CaCl

Base Fox Hills: 1243'

TOC = 6408' (calculated)

Top Nio: 6681'

Tubing

2-3/8" set @ 7520'

J Sand Perfs:

7531 - 7543

7573 - 7590 (abandoned 3-30-74)

12' cmt above CIBP
 4-1/2" CIBP set @ 7568'
 on 3-30-74

TVD = 7671
 MD = 7671

PBTVD = 7556
 PBMD = 7556
 PBTD below CIBP = 7606'

Production Casing

4-1/2" 9.5, 10.5, 11.6#, N-80 CSG set @ 7664' (7-7/8" Hole) 249 jts.
 Cm'd w/ 250 sks 50-50 pozmix