



March 14, 2016  
Matt Lepore  
Director, Colorado Oil and Gas Conservation Commission  
Department of Natural Resources, The Chancery Building  
1120 Lincoln Street, Suite 801  
Denver, Colorado 80203

RE: Request for Exception to Rule 317.p  
Proposed DC-29 Lot 3, Section 10, 40N18W  
Form 2 Document Number 400937121

Dear Mr. Lepore,

Kinder Morgan CO2 Company respectfully requests approval for an exception to COGCC Rule 317.p and run a Cased Hole Pulse Neutron Log for the well listed above. Rule 317.p of the Colorado Oil and Gas Commissions Rules and Regulations requires wells to be logged with a minimum of resistivity log and gamma ray. The above named well is requested to be exempt from this requirement due to problems with drilling operations through the Paradox Formation salt.

The DC-29 listed above will be logged and those logs will be submitted with the form 5 completion report as follows:

- Mud logged from surface to TD.
- A measure while drilling (MWD) tool with gamma ray (GR) capability will be run from about 8175' TVD/MD to casing point.
- The 6" pilot hole will be open-hole logged with 2 runs as follows:
  - 1st run dual laterolog, GR
  - 2nd run neutron and density porosities, monopole sonic, GR
- The vertical wellbore will be logged from TD to the surface casing shoe through casing as follows (COGCC Rule 317.p):
  - 1st run GR, pulsed neutron as the alternative log to be run in lieu of the open-hole resistivity and gamma log
  - Cement Bond log

Thank you for your considerations in this matter. Should you have any questions please contact our office.

Sincerely,  
Kinder Morgan CO2 Company

A handwritten signature in black ink, appearing to read 'Phil Kennedy', is written over a light blue horizontal line.

Phil Kennedy  
Regulatory Manager Cortez, Colorado