

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400924629

Date Received:

12/08/2015

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Benelli Federal

Well Number: LC22-765

Name of Operator: NOBLE ENERGY INC

COGCC Operator Number: 100322

Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

Contact Name: Justin Garrett

Phone: (303)228 4449

Fax: (303)228 4286

Email: justin.garrett@nblenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 22 Twp: 9N Rng: 59W Meridian: 6

Latitude: 40.742340

Longitude: -103.967820

Footage at Surface: 400 feet FNL/FSL FNL 1612 feet FEL/FWL FWL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 4916

County: WELD

GPS Data:

Date of Measurement: 07/29/2015 PDOP Reading: 1.5 Instrument Operator's Name: Ben Milius

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
900 FNL 1917 FWL 330 FSL 1920 FWL
Sec: 22 Twp: 9N Rng: 59W Sec: 22 Twp: 9N Rng: 59W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Please see attached.

Total Acres in Described Lease: 3920 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 330 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2980 Feet

Building Unit: 2980 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 387 Feet

Above Ground Utility: 429 Feet

Railroad: 5280 Feet

Property Line: 400 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 438 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 330 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Unit configuration = 9N-59W Sec 10, 11, 14, 15, 22, & 23: All
Spacing unit also contains Federal minerals: Leases COC71623, COC70899

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-681	3840	S:10,11,14,15,22,23

DRILLING PROGRAM

Proposed Total Measured Depth: 10482 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

4680 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: 2614238

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42	0	80	6	80	0
SURF	13+1/2	9+5/8	36	0	1700	688	1700	0
1ST	8+3/4	7	26	0	6424	525	6424	
1ST LINER	6+1/8	4+1/2	11.6	6274	10482			

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments 1st string top of cement is 200' above Niobrara. The production liner will be hung off inside 7" casing. Well is part of a thirteen-well pad consisting of the existing Castor Federal LC22-78HN (API: 123-33080) and its production facilities and the proposed Benelli Federal LC22-755 (Doc #400924627), Benelli Federal LC22-760 (Doc #400924628), Benelli Federal LC22-765 (Doc #400924629), Diamondback Federal LC22-770 (Doc #400924630), Diamondback Federal LC22-775 (Doc #400924631), Magpul Federal LC21-670 (Doc #400924632), Magpul Federal LC21-675 (Doc #400924633), Magpul Federal LC21-680 (Doc #400924635), Mossberg Federal LC10-760 (Doc #400924636), Mossberg Federal LC10-765 (Doc #400924640), Rattlesnake Federal LC10-770 (Doc #400924644), and Rattlesnake Federal LC10-785 (Doc #400924646). The production facility will be at this location with the pad disturbance wrapped around it. Nearest well is the proposed Diamondback Federal LC22-770. Nearest non-op is the Wildhorse 16-42H (API: 123-34749). Noble Energy shall isolate the Upper Pierre Aquifer from the Fox Hills Aquifer with surface casing and cement and utilize intermediate casing and cement to ensure isolation from below.

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: 421847

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Garrett

Title: Regulatory Analyst Date: 12/8/2015 Email: RegulatoryNotification@nblene

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 3/29/2016

Expiration Date: 03/28/2018

API NUMBER

05 123 42975 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Note changes to submitted form. 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Set 1700' of surface casing. (U.Ppre.Aq. WW) 3) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
	Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.: 1) Within 60 days of rig release, prior to stimulation. 2) 6 months after rig release, prior to stimulation. 3) Within 30 days of first production, as reported on Form 5A.

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
2	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place and maintained until the pad reaches final reclamation.
3	Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	When Running an Open Hole Log on the Pad: One of the first wells drilled on the pad will be logged with open hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open hole logs were run.
5	Drilling/Completion Operations	If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations. If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.

Total: 5 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400924629	FORM 2 SUBMITTED
400949531	OffsetWellEvaluations Data
400949532	DIRECTIONAL DATA
400949533	DEVIATED DRILLING PLAN
400949534	LEGAL/LEASE DESCRIPTION
400949535	WELL LOCATION PLAT
400949538	SURFACE AGRMT/SURETY

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	3/22/16 - Requested operator confirm method (stage cement or surface casing) to protect U.Prre.Aq. developed in WWs within 2 miles in Sec 9,10,11-T9N-R59W). Operator opted to set 1700' surface casing, with 688 sxs cement.	3/28/2016 1:47:45 PM
Permit	Final Review Completed.	3/18/2016 2:04:09 PM
Permit	Per operator corrected distance to the nearest lease from 0' to 330'. Corrected spacing unit configuration. Permitting Review Complete.	3/18/2016 9:10:05 AM
Permit	Open Hole Logging BMP submitted by operator.	3/18/2016 9:10:04 AM
Engineer	Requested Wt/ft on conductor. Operator states 42 lb/ft.	2/18/2016 11:55:08 AM
Permit	Passed completeness.	12/16/2015 1:15:03 PM

Total: 6 comment(s)