

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400959886

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

01/29/2016

Well Name: HOPPER STATE

Well Number: 24N-34SLHZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Ronett Powers

Phone: (720)929-6759

Fax: (720)929-7759

Email: ronett.powers@anadarko.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NESE Sec: 15 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.137952

Longitude: -104.983336

Footage at Surface: 2361 feet FNL/FSL FSL 1000 feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4891

County: WELD

GPS Data:

Date of Measurement: 08/21/2015 PDOP Reading: 1.9 Instrument Operator's Name: MONTY WALLACE

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
2319 FNL 1488 FEL 1135 FSL 1549 FEL
Sec: 15 Twp: 2N Rng: 68W Sec: 34 Twp: 2N Rng: 68W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 2 North, Range 68 West, 6th P.M.

Section 15: Land situated in the NE/4 of Section 15-2N-68W described as follows: BEGINNING at a point on the South line of said NE/4 Section 15 from which the East 1/4 thereof bears N 89°52' E 1320.0 feet; THENCE S 89°52'W 300.0 feet along the South line of the NE/4 Section 15: THENCE N 00°31'W 726.0 feet; THENCE N 89°52' E 300.0 feet parallel to the south line of said NE/4; THENCE S 00°31'E along an old fence line used as the dividing line between the South East 1/4 and the South West 1/4 of the North East 1/4 of said Section 15 a distance of 726.0 feet to the point of beginning, being the same land described in Deed dated October 11, 1972, recorded in Book 678, Reception No. 1600226 of the records of Weld County, Colorado

Weld County, Colorado

See Mineral Lease map.

Total Acres in Described Lease: 5 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 478 Feet

Building Unit: 571 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 280 Feet

Above Ground Utility: 263 Feet

Railroad: 5280 Feet

Property Line: 269 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☒ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: 11/19/2015

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 11/19/2015

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 62 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 1162 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

UNIT CONFIGURATION:

3N68W SEC 34: SE
2N68W SEC 3: E2
2N68W SEC 10: E2
2N68W SEC 15: NE, N2SE

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		1040	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 21649 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

793 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	17+1/4	13+3/8	54.5	0	850	440	850	0
1ST	12+1/4	9+5/8	43.5	0	6672	760	6672	
1ST LINER	8+1/2	5+1/2	20	0	21639	2580	21639	

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒

Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

OTHER DISPOSAL DESCRIPTION:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: If the surface owner authorizes, and if it is feasible for this location at the time of drilling, water-based cuttings will be disposed of onsite using bioremediation/solidification product. If the surface owner does not authorize onsite disposal and/or it is not feasible for this location at the time of drilling, water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

This proposed well will have a treated interval less than one hundred fifty (150) feet from the treated interval of another well and is subject to COGCC Rule 317.r.

The following well(s) belong to Kerr-McGee and will have treated intervals within one hundred fifty (150) feet of this proposed well:

CAMENISCH 34-10

CAMENISCH DAVID E GU 1

Please note the following wells are not within 150' of Kerr-McGee's proposed well, but may appear so in 2-D viewing:

REESE 8-15 (3500' vertical separation)

CAMENISCH 1-15 (4200' vertical separation)

EVERIST 15-10 (4200' vertical separation)

EVERIST 23-10 (5100' vertical separation)

EVERIST 10-10 (4000' vertical separation)

EVERIST 25-10 (5000' vertical separation)

WATERFRONT 7-3 (2200' vertical separation)

WATERFRONT 2-3 (2300' vertical separation)

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ronett Powers

Title: Regulatory Analyst II Date: 1/29/2016 Email: djregulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Matthew Lee

Director of COGCC

Date: 3/31/2016

Expiration Date: 03/30/2018

API NUMBER

05 123 43024 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Permitting Review Complete.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
	1) Bradenhead test shall be performed within 60 days of rig release and prior to stimulation. Test results shall be submitted on Form 17 within 10 days of test. 2) Bradenhead test shall be performed between 6 and 7 months after rig release and shall be submitted on Form 17 within 10 days of test. 3) Bradenhead test shall be performed within 30 days of First Production as reported on Form 5A and shall be submitted on Form 17 within 10 days of test.
	Operator acknowledges the proximity of the listed non-operated well. Operator assures that this offset well will be remediated per the DJ Basin Horizontal Offset Policy (option 3). Operator will submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. Anderson Family trst GU B 1 (API 05-123-08359)

Best Management Practices

No BMP/COA Type

Description

1	Planning	604c.(2).E. Multi-Well Pads: In order to reduce surface impact, this application is for a six-well pad.
2	Planning	604c.(2).Q. Guy Line Anchors: Should guy line anchors be left buried for future use, they shall be identified by a bright marker greater than four (4) feet high and no more than one (1) foot east of the guy line anchor.
3	Planning	604c.(2).R. Tank Specifications: Two 500 barrel skid-mounted frac tanks will be temporarily placed on-site for use of the pre-spud rig only. One tank will store water and the other will store water based mud.
4	Planning	604c.(2).S. Access Roads: KMG will utilize a lease access road from the I-25 Frontage Road for drilling, completions, and production operations, including maintenance equipment. The road will be properly constructed and maintained to accommodate for local emergency vehicle access.
5	Planning	604c.(2).V. Development From Existing Well Pads: Drilling from an existing well pad was not feasible for the development of the wells on this proposed oil and gas location; however, this well pad will be considered for future well locations.

6	Community Outreach and Notification	<p>305.a.(2) A Notice of Intent to Conduct Operations was sent to each building unit owner within the Exception Zone or Buffer Zone Setback. Recipients did not contact KMG.</p> <p>As a part of planning this proposed location, Kerr-McGee held multi-disciplinary Surface Impact Planning Meetings regarding the impacts and mitigations associated with this proposed location. The toll-free hotline number and email for the Anadarko Colorado Response Line will be posted at the entrance to the lease access road for stakeholders during drilling and completion operations at this proposed location. Courtesy Notifications will be sent to impacted stakeholders prior to drilling operations and again prior to completions operations, providing contact information for the Anadarko Colorado Response Line and online resources. Additionally, Kerr-McGee representatives from a variety of disciplines will be available to meet with stakeholders at a community meeting, to be scheduled prior to drilling operations commencing. Impacted stakeholders will be able to get detailed information, including timing, at this meeting.</p>
7	Traffic control	604c.(2).D. Traffic Plan: If required by the local government, a traffic plan will be coordinated with the local jurisdiction prior to commencement of operations.
8	General Housekeeping	604c.(2).O. Loadlines: All loadlines shall be bullplugged or capped.
9	General Housekeeping	604c.(2).P. Removal of Surface Trash: A commercial size trash bin for removing debris will be located on site. This bin will be for use by all parties affiliated with the operation.
10	Storm Water/Erosion Control	604c.(2).W. Site-Specific Measures: KMG maintains a Storm Water Management Plan that assesses erosion control for every KMG operated location. This location will be added to this plan once construction begins. This site will be inspected every fourteen (14) days during construction activities, every twenty-eight (28) days after construction is completed, and after any major weather event.
11	Material Handling and Spill Prevention	604c.(2).N. Control of Fire Hazards: KMG and its contractors will employ best management practices during the drilling and production of its wells and facilities and will comply with appropriate COGCC rules concerning safety and fire. KMG will ensure that any material that might be deemed a fire hazard will remain no less than twenty-five (25) feet from the wellhead(s), tanks and separator(s).
12	Dust control	805.c. Dust: Water will be placed on dirt access roads to mitigate dust as needed. If feasible, magnesium chloride will also be used as needed on access roads to further abate dust. The I-25 Frontage Road is paved and will not require dust mitigation.
13	Construction	604c.(2).M. Fencing Requirements: The completed wellsites will be surrounded with a fence and gate with adequate lock to restrict access to authorized personnel only. KMG personnel will monitor the wellsites regularly upon completion of the wells. Authorized representatives and/or KMG personnel shall be on-site during drilling and completion operations.
14	Noise mitigation	<p>604c.(2).A. Noise: At a minimum, and pending a safety review after construction of the location, sound mitigation barriers (straw bales) will be placed around the perimeter of the pad location (excluding access points) to dampen noise and minimize impact to nearby residences during drilling and completions. An ambient noise survey will be conducted prior to operations. The commercial building units on the other side of the Interstate highway are not expected to be impacted by noise from drilling and completions operations.</p> <p>Sound surveys have been conducted on each rig type and are utilized to anticipate any additional effective noise mitigation once a drilling rig is determined. Pending any operational constraints, every effort will be made to orient the rig in such a way that noise from the shakers will be directed away from the homes to the north.</p> <p>Should technological advancements allow for better noise mitigation at the time of drilling and completion operations on this location, Kerr-McGee will re-evaluate the most effective method at that time.</p>
15	Drilling/Completion Operations	604c.(2).B. Closed Loop Drilling System: KMG will use a closed loop or "pitless" system for drilling and fluid management and will not construct a reserve pit.

16	Drilling/Completion Operations	604c.(2).C. Green Completions: Temporary above ground polyethylene water pipelines will deliver water to location operations from larger trunk lines to reduce truck traffic and minimize air pollution. Pipeline infrastructure is in place prior to completions operations to ensure saleable gas, once hydrocarbons are cut, is sent directly to sales without flaring during flowback.
17	Drilling/Completion Operations	604c.(2).H. BOPE: Our rigs at a minimum will have a double ram with blind and pipe ram and annular preventer.
18	Drilling/Completion Operations	604c.(2).I. BOPE Testing for Drilling Operations: Upon initial rig-up, BOPEs will be tested at a minimum of every 30 days.
19	Drilling/Completion Operations	604c.(2).J. BOPE for Well Servicing Operations: Blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves will be used during any future servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using low-pressure air and high-pressure fluid.
20	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All storage tanks used for active drilling operations (used in lieu of pits) contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gauges are used on tanks utilized for the surface rig.
21	Drilling/Completion Operations	604c.(2).L. Drill Stem Tests: No drill stem tests are planned and none will be performed without prior approval from the Director.
22	Drilling/Completion Operations	803. Lighting: To the extent practicable, site lighting shall be shielded and directed downward and inward toward operations to avoid glare on public roads and nearby Building Units. LED lights will be utilized during completion operations on this location to minimize light impacts. Straw bales placed on location will also help to mitigate light from operations.
23	Drilling/Completion Operations	A flare enclosure will be utilized during drilling operations. Straw bales will also assist in providing visual mitigation during drilling and completions operations.
24	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
25	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
26	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Cased-hole Pulsed Neutron Log with Gamma Ray Log from kick-off point to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.
27	Final Reclamation	604c.(2).T. Well Site Cleared: The wellsite will be cleared of all non-essential equipment within ninety (90) days after all wells associated with the pad have been plugged and abandoned.
28	Final Reclamation	604c.(2).U. Identification of Plugged and Abandoned Wells: Pursuant to rule 319.a.(5)., once the well has been plugged and abandoned, KMG will identify the location of the wellbore with a permanent monument that will detail the well name and date of plugging.

Total: 28 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf
Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area. http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400959886	FORM 2 SUBMITTED
400978682	OffsetWellEvaluations Data
400978711	DIRECTIONAL DATA
400978712	OPEN HOLE LOGGING EXCEPTION
400978713	OTHER
400978715	EXCEPTION LOC REQUEST
400978716	EXCEPTION LOC WAIVERS
400978717	DEVIATED DRILLING PLAN
400978718	LEASE MAP
400978719	WELL LOCATION PLAT
400978720	PROPOSED SPACING UNIT
400978721	SURFACE AGRMT/SURETY

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	3/31/2016 12:49:59 PM
Permit	Operator requested Exception to Open Hole Logging Rule 317.p. See attached.	3/31/2016 11:17:48 AM
Permit	Passed completeness.	2/3/2016 1:38:18 PM

Total: 3 comment(s)