

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400961992

Date Received:

01/08/2016

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Horsetail

Well Number: 30G-3143

Name of Operator: WHITING OIL & GAS CORPORATION

COGCC Operator Number: 96155

Address: 1700 BROADWAY STE 2300

City: DENVER

State: CO

Zip: 80290

Contact Name: Michael Brown

Phone: (307)237-9310

Fax: ()

Email: ml_brown@bresnan.net

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030110

WELL LOCATION INFORMATION

QtrQtr: SWNE Sec: 30 Twp: 10N Rng: 57W Meridian: 6

Latitude: 40.810528

Longitude: -103.791692

Footage at Surface: 2375 feet FNL/FSL FNL 1980 feet FEL/FWL FEL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 4743

County: WELD

GPS Data:

Date of Measurement: 04/24/2015 PDOP Reading: 1.7 Instrument Operator's Name: Jared Christopher

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
2562 FSL 1744 FEL 100 FSL 2018 FEL
Sec: 30 Twp: 10N Rng: 57W Sec: 31 Twp: 10N Rng: 57W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T10N R57W, 6TH P.M.
SECTION 5: SW/4NW/4, W/2SW/4
SECTION 6: LOTS 4(36.53),5(35.80),6(35.86),7(35.93),S/2NE/4,SE/4NW/4,
E/2SW/4,SE/4
SECTION 31: L1 (37.16), L2 (37.21), E2NW, NE (A/K/A N2)

Total Acres in Described Lease: 938 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4625 Feet
Building Unit: 4625 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 5280 Feet
Above Ground Utility: 560 Feet
Railroad: 5280 Feet
Property Line: 284 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 267 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 100 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-508	960	S/2 30, All 31

DRILLING PROGRAM

Proposed Total Measured Depth: 13903 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator: _____

3981 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Bio-remediation

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	80	179	80	0
SURF	13+1/2	9+5/8	36	0	1520	645	1520	0
1ST	8+3/4	5+1/2	17	0	13903	2028	13903	0

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

The well will be drilled to a KOP at 5302' TVD. A curve will be built to landed in the Niobrara at 5823' TVD. The lateral will be drilled with a 7-7/8" bit to TD at 13903 MD. A 5-1/2" casing string will be run with a marker joint to isolate the legal productive interval and cemented to surface. If hole issues occur during the drilling operation we will revert to the outlined contingency drilling program.

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation has been determined in a 3D distance.

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Michael Brown

Title: Agent Date: 1/8/2016 Email: ml_brown@bresnan.net

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/1/2016

Expiration Date: 03/31/2018

API NUMBER

05 123 43039 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.:</p> <ol style="list-style-type: none"> 1) Within 30 days of rig release prior to stimulation. 2) Between 6 and 7 months after rig release. 3) Within 30 days of first production as reported on Form 5A.
	<p>Operator acknowledges the proximity of the following offset well(s) of concern and proposes stated mitigation: 05-123-20077, MADDY 1-31, Option #3</p> <p>Operator agrees to: comply with the DJ Basin Horizontal Offset Policy to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit Form 42(s) ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API Number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p>
	<ol style="list-style-type: none"> 1) Provide 48 hour notice of MIRU via electronic Form 42. 2) Set 1520' of surface casing. (base of Upper Pierre aquifer). 3) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

Best Management Practices

No BMP/COA Type

Description

1	Storm Water/Erosion Control	<p>Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with oil and gas development throughout the State of Colorado. BMPs will be constructed as necessary to prevent stormwater from leaving the construction site. BMPs used will vary according to the location, and will remain until the pad is reclaimed.</p>
2	Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with oil and gas operations throughout the State of Colorado.</p> <ul style="list-style-type: none"> • Materials and fluids will be stored in a neat and orderly fashion. • Waste will be collected regularly and disposed of at an offsite facility. • Prompt cleanup is required of spills to minimize waste materials entering the stormwater runoff. • Drip pans will be used during fueling and maintenance to contain spills or leaks. • Cleanup of trash and discarded material will be done at the end of the work day. • Cleanup will consist of monitoring the road, location and any other work areas. • Material to be cleaned up includes trash, scrap, and contaminated soil.
3	Drilling/Completion Operations	<p>One of the first wells drilled on the pad will be logged with an open-hole resistivity log with gamma-ray from TD to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on the production casing (or intermediate casing if production liner is run). All wells on the pad will have the horizontal portion of the wellbore logged with a measured-while-drilling log with gamma-ray. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run." The Form 5 for a well without open-hole logs shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.</p>

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400961992	FORM 2 SUBMITTED
400962015	DIRECTIONAL DATA
400962017	OTHER
400962018	DEVIATED DRILLING PLAN
400962019	WELL LOCATION PLAT
400967389	OffsetWellEvaluations Data
400967395	SURFACE AGRMT/SURETY
400973929	DRILLING PLAN

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review complete.	3/29/2016 12:27:37 PM
Permit	Permitting task complete.	3/29/2016 12:20:09 PM
Engineer	Operator sent new drilling plan without OBM in the mud program.	1/19/2016 11:24:52 AM
Engineer	Operator agent called to acknowledge increased surface casing and to advise they will not be using OBM specified in the contingency mud program in the drilling plan.	1/15/2016 2:06:34 PM
Engineer	Contacted operator Re: Offset Well(s) w/o adequate isolation: 05-123-20077, MADDY 1-31, DA, plugs inadequate for Nbr and aquifer isolation.	1/12/2016 12:18:06 PM
Permit	Passed completeness.	1/8/2016 12:12:50 PM

Total: 6 comment(s)