

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

401002006

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

03/15/2016

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☒ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒Sidetrack ☐

Well Name: FEDERAL

Well Number: RGU 411-26-198

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: PO BOX 370

City: PARACHUTE State: CO Zip: 81635

Contact Name: VICKI SCHOEBER

Phone: (970)263-2721

Fax: ()

Email: VICKI.SCHOEBER@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: LOT 4 Sec: 26 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.940096

Longitude: -108.368783

Footage at Surface: 661 feet FNL/FSL FNL 200 feet FEL/FWL FWL

Field Name: SULPHUR CREEK

Field Number: 80090

Ground Elevation: 6585

County: RIO BLANCO

GPS Data:

Date of Measurement: 02/14/2013 PDOP Reading: 2.7 Instrument Operator's Name: J. KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL

 876 FNL 716 FWL 876 FNL 716 FWL
 Sec: 26 Twp: 1S Rng: 98W Sec: 26 Twp: 1S Rng: 98W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.☒ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____

Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1S R98W

SEC. 23: LOTS 1 (38.67, NE/4NE/4), 2 (38.70, NW/4NE/4), 3 (38.74, NE/4NW/4), 4 (38.73, NW/4NW/4), 5 (38.80, SW/4NW/4), 6 (38.80, SE/4NW/4), 7 (38.75, SW/4NE/4), 8 (38.72, SE/4NE/4), 9 (38.77, NE/4SE/4), 10 (38.77, NW/4SE/4), 11 (38.84, NE/4SW/4), 12 (38.85, NW/4SW/4), 13 (38.93, SW/4SW/4), 14 (38.93, SE/4SW/4), 15 (38.83, SW/4SE/4), 16 (38.82, SE/4SE/4) [ALL]

SEC. 26: LOTS 2 (38.94, NW/4NE/4), 3 (38.99, NE/4NW/4), 4 (39.02, NW/4NW/4), 5 (38.97, SW/4NW/4), 6 (38.94, SE/4NW/4), 7 (39.05, SW/4NE/4), 8 (39.03, SE/4NE/4), 9 (39.11, NE/4SE/4), 10 (39.13, NW/4SE/4), 11 (38.88, NE/4SW/4), 12 (38.88, NW/4SW/4), 13 (38.86, SW/4SW/4), 14 (38.85, SE/4SW/4), 15 (39.12, SW/4SE/4), 16 (39.19, SE/4SE/4) [NW/NE/4, S/2NE/4, NW/4, S/2]

Total Acres in Described Lease: 1206 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC60732

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 716 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>2950</u> Feet
Building Unit:	<u>2950</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>3397</u> Feet
Above Ground Utility:	<u>702</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>5280</u> Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone ☐ Exception Zone ☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 321 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Ryan Gulch Unit Unit Number: 068239X

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
SEGO	SEGO			
WILLIAMS FORK	WMFK			

DRILLING PROGRAM

Proposed Total Measured Depth: 12354 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

5280 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Spent drilling fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings at a well pad location, or at an approved disposal trench. Separated water is re-used for drilling, or disposed at a permitted inj. well.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	50	80	0
SURF	14+3/4	9+5/8	36	0	3853	1398	3853	0
1ST	8+3/4	4+1/2	11.6	0	12354	1266	12354	7374

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This permit refile is to allow for changes in the WPX Energy Rocky Mountain LLC drilling schedule. No changes have been made to the surface hole location, bottomhole location, lease description or surface use since the original permit was issued.

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: 436652

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Vicki Schoeber

Title: Regulatory Specialist Date: 3/15/2016 Email: vicki.schoeber@wpxenergy.co

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/17/2016

Expiration Date: 04/16/2018

API NUMBER

05 103 12090 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Approval of this refile APD does not provide relief from compliance with the COGCC Reclamation Rules.
	(1) Operator shall comply with the most current revision of the Northwest Notification Policy. See attached notice. (2) Operator shall provide cement coverage from the production casing shoe (4+1/2" First String) to a minimum of 200' above all Mesa Verde Group (and Ohio Creek Formation, if present) oil, gas, and water-bearing sandstone and coalbed formations. Verify production casing cement coverage with a cement bond log.

Best Management Practices

No	BMP/COA Type	Description
1	Planning	<ul style="list-style-type: none"> * Share/consolidate corridors for pipeline ROWs to the maximum extent possible. * Minimize newly planned activities and operations within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river. * Locate roads outside of drainages where possible and outside of riparian habitat. * Avoid constructing any road segment in the channel of an intermittent or perennial stream * Minimize the number, length, and footprint of oil and gas development roads * Use existing roads where possible * Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors * Where possible, consolidate pipeline and existing roadways, or roadways that are planned for development * Maximize the use of directional drilling to minimize habitat loss/fragmentation * Maximize use of remote completion/frac operations to minimize traffic * Maximize use of remote telemetry for well monitoring to minimize traffic.
2	Drilling/Completion Operations	<ul style="list-style-type: none"> * Use centralized hydraulic fracturing operations. * Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures). * Conduct well completions with drilling operations to limit the number of rig moves and traffic.
3	Drilling/Completion Operations	<ul style="list-style-type: none"> * WPX will run triple-combo open hole logs from well TD up to base of surface casing on one of the first wells drilled on a multi-well pad. Remaining wells on the pad will be logged with either cased hole pulsed neutron or triple-combo open hole. Every well will also have a CBL log from well TD up through well surface. Form 5 Completion Reports will identify wells on the pad with triple-combo open hole logs.
4	Interim Reclamation	<ul style="list-style-type: none"> * Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation requirements * Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife * WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas. * Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings. * Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors. * Avoid dust suppression activities within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river where possible.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

Policy
NW Colorado Notification Policy. http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401002006	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review complete.	4/12/2016 11:18:41 AM
Engineer	Offset wells target the Mesaverde. No mitigation required. Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is a 3001 foot deep monitoring well for industrial purposes. Geologic prognosis shows the proposed surface casing covers the entire Green River formation.	3/30/2016 3:04:37 PM
Permit	Passed completeness.	3/16/2016 12:41:52 PM

Total: 3 comment(s)