

HALLIBURTON

iCem[®] Service

URSA RESOURCES GROUP II LLC

For: Hans Wychgram

MONUMENT RIDGE B 43B-08-07-95

8 5/8 SURFACE - SO# 902938693

API# 05-045-22915-00

Job Date: Thursday, November 26, 2015

Sincerely,

Grand Junction Cement Engineering

2.0 Real-Time Job Summary

2.1 Job Event Log

Type	Seq. No.	Activity	Date	Time	Source	DH Density (ppg)	Comb Pump Rate (bbl/min)	PS Pump Press (psi)	Pump Sig Tot (bbl)	Comments
Event	1	Call Out	11/26/2015	11:30:00	USER					ELITE # 8
Event	2	Pre-Convoy Safety Meeting	11/26/2015	14:00:00	USER					ALL HES EMPLOYEES
Event	3	Arrive At Loc	11/26/2015	16:00:00	USER					ARRIVED 3 HOURS EARLY DID NOT START CHARGING HOURS UNTIL REQUESTED ON LOCATION TIME
Event	4	Assessment Of Location Safety Meeting	11/26/2015	17:45:00	USER					ALL HES EMPLOYEES
Event	5	Pre-Rig Up Safety Meeting	11/26/2015	18:00:00	USER					ALL HES EMPLOYEES
Event	6	Rig-Up Equipment	11/26/2015	18:15:00	USER					1 HT-400 PUMP TRUCK (ELITE # 8) 2 660 BULK TRUCKS 1 F-550 PICKUP
Event	7	Comment	11/26/2015	18:30:00	USER					CUSTOMER WAS OFFERED SDS WATER TEMP: 65 F PH: 7 CHLORIDES: 0
Event	8	Pre-Job Safety Meeting	11/26/2015	19:30:00	USER					ALL HES EMPLOYEES AND RIG CREW RIG CIRCULATED FOR 30 MIN @ 10 BBL/MIN PRIOR TO JOB
Event	9	Start Job	11/26/2015	21:02:57	COM5					TD: 1775 TP: 1755 CSG: 8 5/8 32# J-55 SJ: 43 OH: 12 1/4 MUD WEIGHT: 9.5 PPG
Event	10	Prime Pumps	11/26/2015	21:04:16	COM5	8.33	2.0	74	2.0	PRIME LINES FRESH WATER
Event	11	Test Lines	11/26/2015	21:06:02	COM5	8.33		3429	2.0	PRESSURE TEST OK

Event	12	Pump Spacer 1	11/26/2015	21:09:52	COM5	8.33	4.0	186	20.0	20 BBL FRESH WATER SPACER
Event	13	Pump Lead Cement	11/26/2015	21:20:04	COM5	12.30	8.0	332	114.0	260 SKS 12.3 PPG VariCem 2.46 YIELD 14.17 GAL/SK LEAD CEMENT WEIGHT VERIFIED VIA PRESSURIZED MUD SCALES
Event	14	Pump Tail Cement	11/26/2015	21:36:30	COM5	12.80	4.0	126	46.5	120 SKS 12.8 PPG VariCem 2.18 YIELD 12.11 GAL/SK TAIL CEMENT WEIGHT VERIFIED VIA PRESSURIZED MUD SCALES
Event	15	Shutdown	11/26/2015	21:44:51	USER					
Event	16	Drop Top Plug	11/26/2015	21:46:50	USER					PLUG AWAY NO PROBLEMS
Event	17	Pump Displacement	11/26/2015	21:49:42	COM5	8.4	8.0	560	104.2	FRESH WATER DISPLACEMENT
Event	18	Slow Rate	11/26/2015	22:03:42	USER	8.4	2.0	392	94.2	SLOW RATE TO BUMP PLUG
Event	19	Bump Plug	11/26/2015	22:08:51	COM5	8.4	2.0	431	104.2	PRESSURE PRIOR TO BUMPING PLUG @ 431 PSI BUMPED PLUG UP TO 1114 PSI
Event	20	Other	11/26/2015	22:10:05	COM5	8.4		1114	104.2	FLOAT HELD 1 BBL RETURNED BACK TO TRUCKS TANK
Event	21	End Job	11/26/2015	22:11:02	COM5					GOOD RETURNS THROUGHOUT JOB PIPE WAS STATIC THROUGHOUT JOB CIRCULATED 20 BBLs FRESH WATER SPACER AND 10 BBL LEAD CEMENT TO SURFACE
Event	22	Pre-Rig Down Safety Meeting	11/26/2015	22:45:00	USER					ALL HES EMPLOYEES
Event	23	Rig-Down Equipment	11/26/2015	23:00:00	USER					

Event	24	Pre-Convoy Safety Meeting	11/26/2015	23:30:00	USER	ALL HES EMPLOYEES
Event	25	Crew Leave Location	11/26/2015	23:45:00	USER	THANK YOU FOR USING HALLIBURTON CEMENT DAVID CAMPBELL AND CREW