

LEAK REMEDIATION PLANS

REPUBLICAN WATER COLLECTION ROAD 29 & U

Initial spill Doc # 401034825

Per the attached soil analysis the SAR & EC levels are outside the allowable limits of Table 910-1.

The location has been treated with Agricultural grade pelleted gypsum and will be monitored for erosion and weed growth. We will take EC readings at approximately 60 day intervals on the affected area to verify the gypsum is working and will provide moisture if rainfall is not sufficient to help activate the gypsum.

Once the EC reading at the 6" depth is at an acceptable level we will start to probe deeper until the EC reading is acceptable at the 3' depth. We will then take a full soil analysis at the 3' depth.

Should the full soil analysis fall within the allowable limits of Table 910-1 we will continue to monitor the affected location for regrowth and erosion. Once the regrowth is back to 80% we will request closure.

Should the analytical results be above the allowable limits of Table 910-1 we will irrigate with water to drive the salt content down and/or add gypsum. We will continue to take EC readings, as well as, continue to monitor for regrowth and erosion.