

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401039841

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

2. Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: ILA BEALE

Phone: (720) 929-6408

Fax:

Email: ila.beale@anadarko.com

5. API Number 05-123-40840-00

7. Well Name: GREEN

8. Location: QtrQtr: NWNW Section: 8 Township: 1N Range: 65W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: WELD

Well Number: 5N-8HZ

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION
Treatment Date: 04/04/2016 End Date: 04/15/2016 Date of First Production this formation: 04/26/2016
Perforations Top: 7953 Bottom: 13356 No. Holes: 636 Hole size: 0.46
Provide a brief summary of the formation treatment: Open Hole: ☐

"PERF AND FRAC FROM 7953-13,356.
286 BBL ACID, 190,766 BBL SLICKWATER, 5,591 BBL WATER, - 196,642 BBL TOTAL FLUID
911,435# 100 MESH OTTAWA/ST. PETERS, 4,751,651# 40/70 OTTAWA/ST. PETERS, - 5,663,086# TOTAL SAND."

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 196642 Max pressure during treatment (psi): 7920
Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.30
Type of gas used in treatment: Min frac gradient (psi/ft): 0.93
Total acid used in treatment (bbl): 286 Number of staged intervals: 27
Recycled water used in treatment (bbl): 872 Flowback volume recovered (bbl): 18188
Fresh water used in treatment (bbl): 195485 Disposition method for flowback: RECYCLE
Total proppant used (lbs): 5663086 Rule 805 green completion techniques were utilized: ☒
Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/03/2016 Hours: 24 Bbl oil: 238 Mcf Gas: 259 Bbl H2O: 712
Calculated 24 hour rate: Bbl oil: 238 Mcf Gas: 259 Bbl H2O: 712 GOR: 1088
Test Method: FLOWING Casing PSI: 2150 Tubing PSI: Choke Size: 14/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1479 API Gravity Oil: 48
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:
Reason for Non-Production:
Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt
** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: ILA BEALE
Title: STAFF REG. SPECIALIST Date: Email: ila.beale@anadarko.com

Attachment Check List

Att Doc Num Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)