

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

AUG 11 1994

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS
Durango, Colorado

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Robert L. Wright

3. Address and Telephone No.

P.O. Box 1196, Cortez, Co 81321 (303)565-9298

4. Location of Well (Frontage, Sec., T., R., N., or Survey Description)

2232' FSL & 1096' FEL
NW SE Sec. 7 T35N R13W

5. Lease Designation and Serial No.

COC4231

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Federal No. 8

9. API Well No.

05830624600S1

10. Field and Pool, or Exploratory Area

Sierra

11. County or Parish, State

Montezuma, CO

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☒ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion or completion or Recompletion Report and Log)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

On June 20th, 1994 this well was plugged and abandoned as follows:

1. Pumped 110 sks or 198 cu. ft. of 13 lb./gal. Class B cement with fly ash and B.J. gel down the 2 3/8" tubing and up the annulus to the surface, tubing was not pulled from hole.
2. A Proper P & A marker has been erected and cemented in place.
3. All pits are levelled and the location is clean.
4. Will notify you with a Sundry when the location and roads are disced and reseeded.

SEE ATTACHED
CONDITIONS OF APPROVAL

14. I hereby certify that the foregoing is true and correct

Signed James P. Presley

Title Consultant

Date August 4, 1994

(This space for Federal or State office use)

Approved by (s) Kent Hoffman

Title ACTING AREA MANAGER

Date AUG 16 1994

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statement or representations as to any matter within its jurisdiction

*See Instruction on Reverse Side

DURANGO OFFICE COPY

KANDY

FEDERAL VANCE #7 083-06245

FEDERAL VANCE #8 083-06246

FEDERAL VANCE #1X 083-06029

3160

(CO-038)

COC-4231 ← Lease #

CERTIFIED MAIL-RETURN RECEIPT REQUESTED (P 611 871 082)

Robert L. Wright
P.O. Box 1196
Cortez, Colorado 81321

DEC 1 1997

RE: Surface Reclamation and
Bond release
all wells
Section 7, T. 35 N., R.13 W.
Montezuma County, Colorado

RECEIVED

APR - 1 2013

COGCC

Dear Mr. Wright

During your recent visit (November 4, 1997) to this office, you inquired as to the status of your bond for the above subject lease. Our records show you currently have a \$10,000 lease bond which covers liability under the subject lease. This is the only bond valid in the state of Colorado. Records also show a \$25,000 state bond, valid in the state of Utah only.

The \$10,000 lease bond has not been, or will not be released until all surface reclamation as outlined in orders from the Authorized Officer (enclosed) dated August 26, 1992 and April 6, 1994, have been fully complied with.

All reclamation orders have been completed except for the treatment and control of noxious weeds which have invaded the disturbed areas. Both Musk Thistle and Russian Knapweed have been observed on the reclaimed locations and access roads. These weeds are listed on the state of Colorado and Montezuma County list of noxious weeds and must be treated and controlled.

You are hereby ordered to treat the noxious weeds on the subject lease by methods to be approved by the Authorized Officer. These methods may include biological, mechanical or chemical treatments. Should chemical or biological treatment be requested, the operator must submit a Pesticide Use Proposal (attached) to the Authorized Officer a minimum of 60 days prior to the planned application date.

You must submit, to this office, a Plan of Action with time frames for treatment and control the noxious weeds on this lease, no later than March 1, 1998.

Reclamation will be considered successful with subsequent bond release, when the desired vegetative species are established, erosion is controlled, weeds are considered a minimal threat, and it is likely that ground cover will return to its pre-disturbance condition. The operator will continue reclamation, revegetation,

and noxious weed treatment efforts until this standard is met.


As per Title 43 CFR 3165.3, you may request a State Director Review of any instruction, order or decision of the authorized officer. This request must be in writing within 20 business days of receipt of this order. The decision of the State Director may then be appealed to the Interior Board of Appeals if you elect to do so.

If you have any questions concerning this matter, please call Randy Lewis at (970) 247-4874.

Sincerely,

(s) Kent Hoffman

Calvin N. Joyner
Area Manager



Enclosures

bcc:COC4231

Suspense: RLewis
MDO RF
RLewis 11/26/97

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

APR - 1 2013

COGCC

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Robert L. Wright

3. Address and Telephone No.

P.O. Box 1196, Cortez, CO 81321

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec. 7 T35N R13W

RECEIVED

SEP 29 1994

Bureau of Land Management
Durango, Colorado

5. Lease Designation and Serial No.

COC4231

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Federal

9. API Well No.

10. Field and Pool, or Exploratory Area

Sierra

11. County or Parish, State

Montezuma, CO

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☐ Subsequent Report
☒ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other Reclamation

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion or re-completion or re-completion report and log from)

3. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

On August 17, 18, 19 of 1994 the following work was performed:

1. All well sites on this lease were drilled, disced and reseeded.
2. All roads on the lease were drilled, disced and reseeded.
3. All roads were also burned for water shed and blocked off.

The recommended seed mixture was used throughout on all well sites

and roads. See attached seed mixture.

FEDERAL VANCE #7 083-06245

FEDERAL VANCE #8 083-06246

FEDERAL VANCE #IX 083-06029

I hereby certify that the foregoing is true and correct.

Signed

Title Consultant

Date 9/26/94

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

DURANGO OFFICE COPY

SEED FOR ALL NEEDS
SEED CONSULTING SERVICE

PLS SEED MIXTURE ANALYSIS

SPECIES	VARIETY	LOT #	ORIG	PURE	INERT	CROP	WEED	R/N	MOX	GERM	PLS %	DATE	PLS lbs	BULK #	% OF MIX
WHEATGR: WESTERN	VNS	03696	MT	94.38	4.69	0.49	0.44	NF	NF	97.00	91.55	02/02/94	10.00	10.97	60.61
INDIAN RICEGRASS	NEIPAR	03695	MT	99.99	0.01	0.00	0.00	NF	NF	89.00	88.99	01/25/94	4.00	4.49	24.24
CLOVER: YELLOW BLOSM SMT	VNS	02919	CN	99.39	0.38	0.18	0.05	NF	NF	78.00	77.52	05/24/94	2.00	2.58	12.12
SHRUB: SERVICEBERRY	NATIVE	03409	CO	97.80	2.20	0.00	0.00	NF	NF	88.00	86.06	02/12/94	0.50	0.58	3.03
													16.5	18.58	100.00

BLM RECLAMATION MIXTURE FOR BOB WRIGHT
TO SEED 1 ACRE

RECEIVED

APR - 1 2013

ATE 15 08/16/94
IME 15 14:41:52

COGCC

Southwest Seed, Inc.

13260 C. R. 29, Dolores, CO 81323, (303) 565-8722 Inv: N. 0012649

SEED: commercial & wholesale
agricultural & revegetative
Seeding Consultants

SOLD TO:

DATE: 8-10-74 BY: Noz

CASH) CHARGE RETURN ON ACCT:

TERMS: STATEMENT TOTAL IS DUE AND PAYABLE ON OR BEFORE 30 DAYS FROM STATEMENT DATE. AFTER WHICH 1.5% PER MONTH (18% PER YEAR) WILL BE ADDED TO THE UNPAID BALANCE. MINIMUM FINANCE CHARGE OF \$5.00.


SHIP TO:

[illegible]

Southwest Seed Inc. warrants that the seeds we sell are as described by us on our container within recognized

Total	150
-------	-----

SURFACE USE CONDITIONS OF APPROVAL
FOR SUBSEQUENT ABANDONMENT OF THE FOLLOWING WELLS
on Federal lease Number COC-4231



FEDERAL Numbers 7,8,10 and 11
FEDERAL Vance No.1-X

Upon plugging the wells as approved in this Notice of Intent to Abandon, the following surface related items shall be accomplished.

1. Remove all trash and unused equipment from and around all locations, this includes cans, barrels, pipe, sucker rod, unused pumpjacks, wire, pipelines and other materials. These shall be removed from public land.
2. All disturbed areas will be recontoured to blend as nearly as possible with the natural topography. This includes removing all berms and refilling all cuts. All compacted portions of the pad will be ripped to a depth of 12 inches unless in solid rock.
3. All roads not required for access to private land will be recontoured, waterbarred, ripped and seeded to blend as near as possible to the surrounding vegetation. Those portions of the roads requiring reclamation will be staked by a BLM representative before any dirt work takes place.
4. Any stockpiled topsoil will be spread evenly over the disturbed area. Seed will be broadcast between September 1 and December 1 with the following prescription. Seed may be drilled at half the rate of the broadcast seeding. Seed depth = 1/2 inch. All seeding rates in pounds of pure live seed. Seed should be adapted varieties.

<u>Species</u>	<u>Common Name</u>	<u>Rate lbs./acre</u>
<u>Agropyron smithii</u>	Western Wheatgrass(Arriba)	10
<u>Oryzopsis hymenoides</u>	Indian Ricegrass	4
<u>Melilotus officinalis</u>	Yellow sweetclover	2
<u>Amelanchier utahensis</u>	Serviceberry	<u>1/2</u>
		16 1/2

5. Water bars will be built as follows to control erosion:

Grade	Spacing
2%	Every 200 feet
2-4%	Every 100 feet
4-5%	Every 75 feet
5+%	Every 50 feet

The following condition of approval applies to the above mentioned wells along with the following abandoned wells: Federal No. 9 and 14 and the Federal Vance No. 6.

6. These wells will not be approved for final abandonment until the thistle problem is eliminated.

The goal of surface reclamation is to restore the area as close as possible to its natural setting.

If you have any questions related to this surface use plan, please contact Randy Lewis at (303) 247-4082.

RECEIVED

APR - 1 2013

COGCC

RECEIVED

APR - 1 2013

COGCC

3160

Robert L. Wright
Federal Lease COC4231
Federal Wells 7, 8, 10, and 11, Fed. Vance No. 1-X
Sec. 7, T. 35 N., R. 13 W.
Montezuma County, Colorado

Conditions of Approval - Subsequent Report of Abandonment

1. When the wellsites are ready for final surface inspection, please contact this office in order that an onsite inspection can be made. Final Abandonment Notice (FAN) can be submitted via Sundry Notice at that time.

2. After the FAN is approved by this office, your liability associated with the subject well will terminate.
