



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE  
457

Date	3-19-16	Well Owner	P.D.C	Well No.	10L-201	Lease	Spaur
County	Weld	State	Colorado				
Charge to	Petroleum Development Corporation						
Address	1775 Sherman Street Suite 3000						
City, State Zip	Denver Colorado 80203 (EnSign 121)						
Type of Job			Depth	Ft.			
Surface	9 5/8" CSG 36 #12 1/4" Hole		Bottom of Surface	Ft.	1371		
Plug			Plug Landed @	1329	Ft.	Time On	0600
Production			Pipe Landed @	1371	Ft.	Plug Down	1030

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Data Acquisition System				
Cement Neat	630	SKS		
Calcium Chloride	3	%		
Gel % Flo-Cele 1/4 # Per Sack				
Mileage Heavy Vehicle	AFE 2138	108	Miles	
Mileage Pick-Up	Coding 8100-112		Miles	
Fuel Surcharge	Date 3-19-16			
Additional Cement	By Carl P. Hernandez		SKS	
Mixing Rate	4 Bpm	Centralizers	8	
Disp. Rate	5 Bpm	Cement Guide Shoe	1	
Slurry Vol.	1.36 cu ft SK	Cement Basket	1	
Slurry Wt.	15.0 ppg	Baffle Plate	1	
Water/Cement	5.0 Gals-SK	Box Thread Lock	1	
Water Temp.	48°F			
Total Slurry Vol.	152.5	BBLS Cement		
Landed Plug @	1250	PSI / Final Lift @ 850	PSI	
Pre-Flush W/	40	BBLS H <sub>2</sub> O		Sub Total
Displace W/	102.7	BBLS H <sub>2</sub> O		Tax CO 2.1
Circulate	6	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		36			
1217/1218		Bulk Truck		36/36			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Evan, Justin

Received By \_\_\_\_\_

Customer or His Agent