

FORM  
2

Rev  
08/13

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401054279

**(SUBMITTED)**

Date Received:

05/26/2016

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Evans 0780

Well Number: 6-21H

Name of Operator: SANDRIDGE EXPLORATION & PRODUCTION LLC

COGCC Operator Number: 10598

Address: 123 ROBERT S KERR AVE

City: OKLAHOMA CITY

State: OK

Zip: 73102

Contact Name: Laci Bevans

Phone: (405)429-5610

Fax: ( )

Email: lbevans@sandridgeenergy.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160010

#### WELL LOCATION INFORMATION

QtrQtr: NESW Sec: 16 Twp: 7N Rng: 80W Meridian: 6

Latitude: 40.574071

Longitude: -106.382214

Footage at Surface: 1393 feet FNL/FSL FSL 1627 feet FEL/FWL FWL

Field Name: NORTH PARK HORIZONTAL NIOBRARA

Field Number: 60120

Ground Elevation: 8136

County: JACKSON

GPS Data:

Date of Measurement: 05/03/2016 PDOP Reading: 1.2 Instrument Operator's Name: ADL

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
693 FSL 1650 FWL 100 FSL 1650 FWL  
Sec: 16 Twp: 7N Rng: 80W Sec: 21 Twp: 7N Rng: 80W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

The surface in which this well will be drilled from is private surface and the minerals directly below the well pad are as well. this unit contains private minerals in sec 16-7N-80W (All-640ac), private minerals in sec 21-7N-80W (N2, N2S2 & S2SW4-560ac) and USA minerals in sec 21-7N-80W (S2 SE4 -80ac). No minerals penetrated or produced by this well will be anything other than leased private minerals.

Total Acres in Described Lease: 1280 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: \_\_\_\_\_ Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 3948 Feet  
Building Unit: 5280 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 5280 Feet  
Above Ground Utility: 1271 Feet  
Railroad: 5280 Feet  
Property Line: 1378 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone ☐ Exception Zone ☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 660 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 300 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

The location from which this well will be drilled is on private surface. All minerals this well will penetrate and produce are all private.

## OBJECTIVE FORMATIONS

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| NIOBRARA               | NBRR           | 531-23                  | 1280                          | Sec. 16 & 21: All                    |

## DRILLING PROGRAM

Proposed Total Measured Depth: 14496 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator: \_\_\_\_\_

5280 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

## CASING PROGRAM

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR   | 26           | 16+1/4         | 42    | 0             | 90            | 189       | 90      | 0       |
| SURF        | 12+1/4       | 9+5/8          | 36    | 0             | 2500          | 629       | 2500    | 0       |
| 1ST         | 8+3/4        | 5+1/2          | 20    | 0             | 14496         | 2366      | 14496   | 0       |

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments \_\_\_\_\_

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Laci Bevans

Title: Regulatory Analyst Date: 5/26/2016 Email: lbevans@sandridgeenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

|  |  |
|--|--|
|  |  |
|--|--|

## Best Management Practices

### No BMP/COA Type

### Description

|   |                                |  |
|---|--------------------------------|--|
| 1 | Drilling/Completion Operations | One of the first wells drilled on the pad will be logged with an open hole resistivity log and gamma ray log from the kick off point to into the surface casing. All wells on the pad will have a cement bond log with gamma ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma ray log. The form 5, completion report, for each well on the pad will list all logs run and have those logs attached. The form 5 for a well without open hole logs shall clearly state "no open hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open hole logs were run. |
|---|--------------------------------|--|

Total: 1 comment(s)

## Attachment Check List

| <u>Att Doc Num</u> | <u>Name</u>            |
|--------------------|------------------------|
| 401054279          | FORM 2 SUBMITTED       |
| 401054314          | DRILLING PLAN          |
| 401054316          | ANTI-COLLISION WAIVER  |
| 401054317          | DEVIATED DRILLING PLAN |
| 401054318          | SURFACE AGRMT/SURETY   |
| 401054330          | WELL LOCATION PLAT     |
| 401057693          | DIRECTIONAL DATA       |

Total Attach: 7 Files

### General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
|                   |                |                     |

Total: 0 comment(s)