

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400990658

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Date Received:

05/19/2016

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: MARKHAM

Well Number: 11

Name of Operator: CUB CREEK ENERGY

COGCC Operator Number: 10542

Address: 200 PLAZA DRIVE SUITE 100

City: HIGHLANDS
RANCH

State: CO

Zip: 80129

Contact Name: Paul Gottlob

Phone: (720)420-5747

Fax: ()

Email: paul.gottlob@iptenergyservices.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20140112

WELL LOCATION INFORMATION

QtrQtr: NWSE Sec: 32 Twp: 4N Rng: 68W Meridian: 6

Latitude: 40.269060

Longitude: -105.023130

Footage at Surface: 2485 feet FNL/FSL FSL 1517 feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5039

County: WELD

GPS Data:

Date of Measurement: 12/30/2015 PDOP Reading: 1.6 Instrument Operator's Name: B. ROTTINGHAUS

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FSL 2310 FSL 460 FEL FEL 2310 FSL 460 FEL/FWL FWL
Sec: 32 Twp: 4N Rng: 68W Sec: 32 Twp: 4N Rng: 68W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

See attached Mineral Lease Map.

Total Acres in Described Lease: 251 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 713 Feet
Building Unit: 827 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 1507 Feet
Above Ground Utility: 2877 Feet
Railroad: 5280 Feet
Property Line: 167 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 03/04/2016

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 180 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Spacing Unit: S/2N/2 & N/2S/2 Sec. 32-T4N-R68W.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12148 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

328 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	43	0	80	400	80	0
SURF	13+1/2	9+5/8	36	0	1500	681	1500	0
1ST	8+3/4	5+1/2	20	0	12148	2232	12148	0

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments The attached SUA has an Exception Location Waiver on page 4 in (8).
The Oil & Gas Location Assessment is already in process - Doc #400990702.
This permit is 1 of 2 Northern Boundary wells being submitted together.

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Paul Gottlob

Title: Regulatory & Engin. Tech. Date: 5/19/2016 Email: paul.gottlob@iptenergyservices

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 6/17/2016

Expiration Date: 06/16/2018

API NUMBER

05 123 43275 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Bradenhead tests shall be performed and reported according to the following schedule and Form 17 submitted within 10 days of each test.: 1) Within 60 days of rig release, prior to stimulation. 2) 6 months after rig release, prior to stimulation. 3) Within 30 days of first production, as reported on Form 5A.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (Spud Notice), for the first well/activity on the pad and provide 48 hour spud notice for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j and provide cement coverage from the end of production casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

Best Management Practices

No	BMP/COA Type	Description
1	Planning	604.c(2)M. Fencing: A meeting with the surface owner will determine a fencing plan.
2	Planning	604.c.(2)J.i Blowout Prevention Equipment ("BOPE"): A double ram and annular preventer will be used during drilling. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.
3	Planning	604.c.(2)J.ii Backup stabbing valves be required on well servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using both low-pressure air and high-pressure fluid.
4	Planning	604.c.(2)N. Control of fire hazards: All material that is considered a fire hazard shall be a minimum of 25' from the wellhead tanks or separators. Electrical equipment shall comply with API IRP 500 and will comply with the current national electrical code.
5	Planning	317.r Statewide Wellbore Collision Prevention: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
6	Traffic control	604.c.(2)S. Access Roads: The access road will be constructed to accommodate local emergency vehicles. This road will be maintained for access at all times. Traffic will be routed to minimize local interruption. Dust control measures will also be utilized.
7	Traffic control	604.c.(2)D: If required by the local government, a traffic plan shall be coordinated with the local jurisdiction prior to commencement of move in and rig up. Any subsequent modification to the traffic plan must be coordinated with the local jurisdiction.
8	General Housekeeping	604.c.(2)P. Trash Removal: All trash, debris and material not intrinsic to the operation of the oil and gas facility shall be removed and legally disposed of as applicable.
9	Construction	803. Light sources during all phases of operations will be directed downwards and away from occupied structures where possible. Once the drilling and completion rigs leave the site, there will be no permanently installed lighting on site. Lighting shall be mounted at compressor stations on a pole or building and directed downward to illuminate key areas within the facility, while minimizing the amount of light projected outside the facility.
10	Construction	604.c.(2).Q. All guy line anchors left buried for future use shall be identified by a marker of bright color not less than four (4) feet in height and not greater than one (1) foot east of the guy line anchor.
11	Construction	604.c.(2).E. This will be a multi-well pad.
12	Noise mitigation	604.c.(2)A. Sound walls and/or hay bales will be used if necessary to surround the well site during drilling operations.
13	Emissions mitigation	604.c.(2)C.i. Green Completions - Emission Control System: Test separators and associated flow lines and sand traps shall be installed on-site to accommodate green completions techniques pursuant to COGCC Rules. In the anticipated absence of a viable gas sales line, the flowback gas shall be thermally oxidized in an emissions control device (ECD), which will be installed and kept in operable condition for least the first 90-days of production pursuant to CDPHE rules. This ECD shall have an adequate capacity for 1.5 times the largest flowback within a 10 mile radius, will be flanged to route gas to other or permanent oxidizing equipment and shall be provided with the equipment needed to maintain combustions where non-combustible gases are present. There is a gas sales line nearby that will be tapped for gas sales.
14	Odor mitigation	805: Oil & gas facilities and equipment shall be operated in such a manner that odors and dust do not constitute a nuisance or hazard to public welfare. Odors will be managed by engine filters and well gas will initially be flared until connected to sales line.

15	Drilling/Completion Operations	604.c.1: Upon initial rig-up and at least once every thirty (30) days during drilling operations thereafter, pressure testing of the casing string and each component of the blowout prevention equipment including flange connections shall be performed to seventy percent (70%) of working pressure or seventy percent (70%) of the internal yield of casing, whichever is less. Pressure testing shall be conducted and the documented results shall be retained by the operator for inspection by the Director for a period of one (1) year. Activation of the pipe rams for function testing shall be conducted on a daily basis when practicable.
16	Drilling/Completion Operations	604.c.(2)L. Closed chamber drill stem tests shall be allowed. All other drill stem tests shall require approval by the Director. None planned for this well.
17	Drilling/Completion Operations	604.c.(2).O. Drilling and Completion-All loadlines shall be bullplugged or capped.
18	Drilling/Completion Operations	604.c.(2)B.i Operator will be utilizing a closed loop system.
19	Drilling/Completion Operations	Operator will comply with COGCC Policy for Braden-head Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
20	Drilling/Completion Operations	Requirement to log well. 317.p One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from Kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.
21	Final Reclamation	604.c.(2)T. Within 90 days subsequent to the time of plugging and abandonment of the entire site, superfluous debris and equipment shall be removed from the site. Identification of plugged and abandoned wells will be identified pursuant to 319.a.(5)
22	Final Reclamation	604.c.(2).U. Final Reclamation-The operator shall identify the location of the wellbore with a permanent monument as specified in Rule 319.a.(5). The operator shall also inscribe or imbed the well number and date of plugging upon the permanent monument.

Total: 22 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf
Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area. http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400990658	FORM 2 SUBMITTED
400990688	WELL LOCATION PLAT
401047857	OffsetWellEvaluations Data
401047972	SURFACE AGRMT/SURETY
401047988	LEASE MAP
401047994	OIL & GAS LEASE
401048707	PROPOSED SPACING UNIT
401049262	EXCEPTION LOC REQUEST
401050640	DIRECTIONAL DATA
401050642	DEVIATED DRILLING PLAN

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	6/15/2016 2:58:27 PM
Engineer	Offset Wells Evaluated	3/2/2016 1:36:39 PM
Permit	Permitting Review Complete.	3/2/2016 1:10:24 PM
Permit	Surface Use Agreement has waivers for Rule 318A.a & 318A.c. See page 4, Section 8.	3/2/2016 1:10:23 PM
Permit	Open Hole Logging BMP submitted by operator.	3/2/2016 1:10:22 PM
Permit	Passed completeness.	5/25/2016 3:37:16 PM
Permit	Corrected BMP Rule 317.p typo.	5/25/2016 3:30:33 PM

Total: 7 comment(s)