

# Well Completion Diagram - Planned Post P&A

API Well No. 05-001-06945

Operator: Energy Search Company


Well Name: Ginther #1

Spindle Field, Adams County, Colorado

Coordinates: 660' FWL 660' FNL NWNW Sec. 20-T1S-R67W 6th PM

23-Jun-16

Bore Diameters (inches)



Cement Top 0'

Cemented with 100 sxs  
Cement Bottom 100'

Casing cut off 4' below ground level

Cement top: Surface

37 sxs 15.8# CI G 1.15 cu. ft./sx Cement

8 5/8" Surface casing @ 100'

Cement bottom: 150'

Cement top: 440' (calculated)

50 sxs 15.8# CI G 1.15 cu. ft./sack Cement

Cement bottom: 585'

Cement top: 1251' (calculated)

75 sxs 15.8# CI G 1.15 cu. ft./sx Cement

4 1/2" Casing cut off @ 1456'

Cement bottom: 1506'

Cement top 4012' (calculated)

CIBP @ 5169', 2 sxs 15.8# CI G Cement on tc

Sussex Perfs 5219' - 5236'

4 1/2" 9.5# @ 5276' cemented with 250 sxs

TD = 5276'

