

**FORM
INSP**Rev
05/11**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

06/09/2016

Document Number:

680600772

Overall Inspection:

SATISFACTORY**FIELD INSPECTION FORM**

Location Identifier	Facility ID	Loc ID	Inspector Name:	On-Site Inspection	2A Doc Num:
	428189	428191	ROY, CATHERINE	<input type="checkbox"/>	

Operator Information:OGCC Operator Number: 77330Name of Operator: SG INTERESTS I LTDAddress: 100 WAUGH DR SUITE 400City: HOUSTON State: TX Zip: 77007

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☒ NO FOLLOW UP INSPECTION REQUIRED
- ☐ INSPECTOR REQUESTS FORM 42 WHEN CORRECTIVE ACTIONS ARE COMPLETED

Contact Information:

Contact Name	Phone	Email	Comment
,	970-385-0696	inspections@sginterests.com	All Inspections

Compliance Summary:QtrQtr: LOT 6 Sec: 26 Twp: 11S Range: 90W

Insp. Date	Doc Num	Insp. Type	Insp Status	Satisfactory /Action Required	PA P/F/I	Pas/Fail (P/F)	Violation (Y/N)
03/20/2013	670400013	WO	WO	SATISFACTORY			No

Inspector Comment:

This is a reclamation and stormwater inspection. Our documents indicate there is an open permit for a well on this location that has not been drilled.

Related Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status	
428189	WELL	WO	10/22/2012	SI	051-06106	HUGHES 11-90-26 2	RI	<input checked="" type="checkbox"/>
441484	WELL	XX	04/12/2015	LO	051-06140	Hughes 11-90-26 3	RI	<input checked="" type="checkbox"/>

Equipment:Location Inventory

Special Purpose Pits: _____	Drilling Pits: <u>2</u>	Wells: <u>2</u>	Production Pits: _____
Condensate Tanks: <u>1</u>	Water Tanks: <u>4</u>	Separators: <u>2</u>	Electric Motors: _____
Gas or Diesel Mortors: _____	Cavity Pumps: _____	LACT Unit: _____	Pump Jacks: <u>2</u>
Electric Generators: _____	Gas Pipeline: <u>1</u>	Oil Pipeline: _____	Water Pipeline: <u>1</u>
Gas Compressors: _____	VOC Combustor: _____	Oil Tanks: _____	Dehydrator Units: _____
Multi-Well Pits: _____	Pigging Station: _____	Flare: <u>2</u>	Fuel Tanks: _____

Location**Lease Road:**

Type	Satisfactory/Action Required	comment	Corrective Action	Date

Signs/Marker:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Emergency Contact Number (S/AR): _____ Corrective Date: _____

Comment: _____

Corrective Action: _____

Good Housekeeping:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Spills:				
Type	Area	Volume	Corrective action	CA Date

☐ Multiple Spills and Releases?

Fencing/:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Equipment:				
Type:	#	Satisfactory/Action Required:		
Comment				
Corrective Action				Date:

Venting:	
Yes/No	
Comment	

Flaring:			
Type	Satisfactory/Action Required		
Comment:			
Corrective Action:		Correct Action Date:	

<u>Predrill</u>			
Location ID:	428189		
Lease Road Adeq.:	Pads:	Soil Stockpile:	
S/AR:			
Corrective Action:	Date:	CDP Num.:	

Form 2A COAs:

Group	User	Comment	Date

OGLA	kubeczko	<p>SITE SPECIFIC COAs:</p> <p>Location is in a sensitive area because of proximity to wetlands and surface water; therefore, operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days), and maintained in good condition.</p> <p>Operator must implement best management practices to contain any unintentional release of fluids, including any fluids conveyed temporary surface pipelines or buried pipelines.</p> <p>Location is in a sensitive area because of shallow groundwater; therefore either a lined drilling pit or closed loop system must be implemented.</p> <p>Location is in a sensitive area because of shallow groundwater; therefore any pits constructed to hold fluids (i.e., production pit, frac pit, reserve pit) must be lined.</p> <p>The moisture content of any drill cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts.</p> <p>No portion of any pit that will be used to hold liquids shall be constructed on fill material, unless the pit and fill slope are designed and certified by a professional engineer, subject to review and approval by the director prior to construction of the pit. The construction and lining of the pit shall be supervised by a professional engineer or their agent. The entire base of the pit must be in cut.</p> <p>The drilling (reserve) pit must be fenced and netted. The operator must maintain the fencing and netting until the pit is closed in accordance with Rule 905. Closure of Pits, and Buried or Partially Buried Produced Water Vessels.</p> <p>The surface soils and materials are fine-grained and highly unconsolidated; therefore appropriate BMPs need to be in place during all drilling and well completion operations. Standard stormwater BMPs must be implemented at this location to insure compliance with CDPHE and COGCC requirements and to prevent any stormwater run-on and /or stormwater runoff.</p> <p>Notify the COGCC Oil and Gas Location Assessment (OGLA) Specialist for Western Colorado (Dave Kubeczko; email dave.kubeczko@state.co.us) and the COGCC Field Inspection Supervisor for Northwest Colorado (Shaun Kellerby; email shaun.kellerby@state.co.us) 48 hours prior to start of fracing operations.</p> <p>Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or pit located on the well pad or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area with additional downgradient perimeter berming (an increase in the height of the pad perimeter berm can address this requirement). The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released material.</p> <p>Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service any temporary surface pipelines or configuration of the permanent pipeline network.</p> <p>Berms or other containment devices shall be constructed to be sufficiently impervious to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.</p>	12/27/2011
------	----------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------

OGLA	kubeczkd	Revised COA 25 - If the wells are to be hydraulically stimulated, flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or storage vessel located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area constructed to be sufficiently impervious to contain any spilled or released material.	03/18/2015
OGLA	kubeczkd	<p>Operator must implement best management practices (secondary containment and spill response equipment) to contain any unintentional release of fluids along all portions of the surface pipeline route where temporary pumps and other necessary equipment are located.</p> <p>Operator must routinely inspect the entire length of the surface pipeline to ensure integrity. Operator shall conduct daily inspections of surface poly pipeline routes for leaks during active transfer of fluids. Inspections shall be conducted by viewing the length of the pipeline; operator will endeavor to minimize surface disturbance during pipeline monitoring.</p> <p>Prior to operation, pipelines will be air and hydro tested for integrity. When in operation, pump stations will be manned continuously to ensure immediate response to pressure changes or pump issues. Qualified personnel, interconnected via 2-way radio, manning each booster pump will carefully synchronize pump turn-on and shut-down according to written and practiced procedure. The entire line will be monitored, where feasible, during pumping and flowback operations. For stream or intermittent stream crossings, operator will ensure appropriate containment by installing over-sized pipe "sleeves" which extend the length of the crossing and beyond to a distance deemed adequate to capture and/or divert any possible release of fluids and prevent infusion into the stream water. Operator will design their infrastructure and utilize pipeline materials to exceed required pressures and flow rates by a minimum of 30%. The DR 9 poly pipeline used in this project is rated to support pressure surges up to 500 psi, continual surges of 375 psi, and a maximum operating pressure of 250 psi. Pumps used in this project will operate at pressures 20-30 psi below the maximum operating pressure of the poly pipeline at all times.</p> <p>Operator will utilize, to the extent practical, all existing access and other public roads, and/or existing pipeline right-of-ways, when placing/routing the surface pipelines. This will reduce surface disturbance and fragmentation of wildlife habitat in the area.</p>	03/18/2015
OGLA	kubeczkd	Notify the COGCC 48 hours prior to start of pad reconstruction/regrading (if necessary), rig mobilization, spud, start of hydraulic stimulation operations, start of flowback operations (if different than start of hydraulic stimulation operations), and pipeline testing using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).	03/18/2015

S/AR: _____ **Comment:** _____

CA: _____ **Date:** _____

Wildlife BMPs:

BMP Type	Comment
Drilling/Completion Operations	Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or pit located on the well pad or into tanker trucks for offsite disposal. The entire level pad will be surrounded by a berm to contain any potential release on the well pad. The berm is approximately 2 ½ feet in height around the pad except at the entrance where it is approximately 1 1/2 feet in height to allow vehicles to drive over it. Tanks will be set on compacted earth in an area of the pad that has been constructed on cut soils.

S/AR: _____ **Comment:** _____

CA: _____ **Date:** _____

Comment: _____

Staking:**On Site Inspection (305):**Surface Owner Contact Information:

Name: _____ Address: _____
 Phone Number: _____ Cell Phone: _____

Operator Rep. Contact Information:

Landman Name: _____ Phone Number: _____
 Date Onsite Request Received: _____ Date of Rule 306 Consultation: _____
 Request LGD Attendance: _____

LGD Contact Information:

Name: _____ Phone Number: _____ Agreed to Attend: _____

Summary of Landowner Issues:

Summary of Operator Response to Landowner Issues:

Onsite Inspection Memorandum Summarizing Discussions at Inspection as Attachment:

Facility

Facility ID: 428189 Type: WELL API Number: 051-06106 Status: WO Insp. Status: RI

Facility ID: 441484 Type: WELL API Number: 051-06140 Status: XX Insp. Status: RI

Environmental**Spills/Releases:**

Type of Spill: _____ Description: _____ Estimated Spill Volume: _____
 Comment: _____
 Corrective Action: _____ Date: _____
 Reportable: _____ GPS: Lat _____ Long _____
 Proximity to Surface Water: _____ Depth to Ground Water: _____

Water Well:

DWR Receipt Num: _____ Owner Name: _____ GPS : _____ Lat _____ Long _____

Field Parameters:

Sample Location: _____

Emission Control Burner (ECB): _____

Comment: _____

Pilot: _____ Wildlife Protection Devices (fired vessels): _____

Reclamation - Storm Water - Pit**Interim Reclamation:**

Date Interim Reclamation Started: _____ Date Interim Reclamation Completed: _____

Inspector Name: ROY, CATHERINE

Land Use: OTHER, RANGELAND

Comment: Project area is surrounded by open sagebrush rangeland. Interim reclamation has not been conducted. Slopes and soil stockpile are revegetating. Interim reclamation will need to be conducted after second well is drilled or when it is determined that second well will not be drilled.

1003a. Waste and Debris removed? Pass

CM _____

CA _____ CA Date _____

Unused or unneeded equipment onsite? Pass

CM _____

CA _____ CA Date _____

Pit, cellars, rat holes and other bores closed? _____

CM _____

CA _____ CA Date _____

Guy line anchors marked? _____

CM _____

CA _____ CA Date _____

1003b. Area no longer in use? _____ Production areas stabilized ? _____

1003c. Compacted areas have been cross ripped? _____

1003d. Drilling pit closed? _____ Subsidence over on drill pit? _____

Cuttings management: _____

1003e. Areas no longer needed for drilling or subsequent operations for have been re-vegetated to 80% of pre-existing? _____

Production areas have been stabilized? _____ Segregated soils have been replaced? _____

RESTORATION AND REVEGETATION

Cropland

Top soil replaced _____ Recontoured _____ Perennial forage re-established _____

Non-Cropland

Top soil replaced _____ Recontoured _____ 80% Revegetation _____

1003 f. Weeds Noxious weeds? _____

Comment: _____

Overall Interim Reclamation

Final Reclamation/ Abandoned Location:

Date Final Reclamation Started: _____ Date Final Reclamation Completed: _____

Final Land Use: RANGELAND

Reminder: _____

Comment: _____

Well plugged _____ Pit mouse/rat holes, cellars backfilled _____

Debris removed _____ No disturbance /Location never built _____

Access Roads Regraded _____ Contoured _____ Culverts removed _____

Gravel removed _____

Location and associated production facilities reclaimed _____ Locations, facilities, roads, recontoured _____

Compaction alleviation _____ Dust and erosion control _____

Inspector Name: ROY, CATHERINE

Non cropland: Revegetated 80% _____

Cropland: perennial forage _____

Weeds present _____ Subsidence _____

Comment: _____

Corrective Action: _____ Date _____

Overall Final Reclamation _____

Well Release on Active Location ☐

Multi-Well Location ☐

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

S/A/V: SATISFACTOR
Y _____ Corrective Date: _____

Comment: Stormwater erosion is controlled on the location at this time. See attached photos.

CA: _____

Pits: ☐ NO SURFACE INDICATION OF PIT

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
680600772	INSPECTION APPROVED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=3893686
680600773	Inspection Photos	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=3893678