

**FORM INSP**  
Rev 05/11

**State of Colorado  
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:  
07/08/2016  
Document Number:  
675203023  
Overall Inspection:  
SATISFACTORY

**FIELD INSPECTION FORM**

Location Identifier	Facility ID	Loc ID	Inspector Name:	On-Site Inspection	2A Doc Num:
	442551	442549	CONKLIN, CURTIS	<input type="checkbox"/>	

**Operator Information:**

OGCC Operator Number:	10433
Name of Operator:	LARAMIE ENERGY LLC
Address:	1401 SEVENTEENTH STREET #1400
City:	DENVER State: CO Zip: 80202

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED
- INSPECTOR REQUESTS FORM 42 WHEN CORRECTIVE ACTIONS ARE COMPLETED

**Contact Information:**

Contact Name	Phone	Email	Comment
Ellsworth, Stuart		Stuart.ellsworth@state.co.us	Engineering Supervisor
Bankert, Wayne	(970) 683-5419	wbankert@laramie-energy.com	Senior Regulatory & Environmental Coordinator
Hartman, Robert	(970) 244-3041	bhartman@blm.gov	Petroleum Engineer

**Compliance Summary:**

QtrQtr: NESW Sec: 28 Twp: 9S Range: 93W

**Inspector Comment:**

Stimulation/Flowback inspection

**Related Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status	
442546	WELL	WO	11/21/2015	LO	077-10246	Piceance Fed 28-11E	WO	<input type="checkbox"/>
442547	WELL	WO	12/21/2015	LO	077-10247	Piceance Fed 28-05E	WO	<input type="checkbox"/>
442548	WELL	WO	10/29/2015	LO	077-10248	Piceance Fed 28-14E	WO	<input type="checkbox"/>
442550	WELL	WO	11/02/2015	LO	077-10249	Piceance Fed 28-13E	WO	<input type="checkbox"/>
442551	WELL	DG	10/09/2015	LO	077-10250	Piceance Fed 28-21E	WO	<input checked="" type="checkbox"/>
442553	WELL	WO	05/07/2015	LO	077-10251	Piceance Fed 28-08E	WO	<input type="checkbox"/>
442555	WELL	WO	12/17/2015	LO	077-10252	Piceance Fed 28-06E	WO	<input type="checkbox"/>
442556	WELL	WO	11/16/2015	LO	077-10253	Piceance Fed 28-12E	WO	<input type="checkbox"/>
442558	WELL	WO	10/20/2015	LO	077-10254	Piceance Fed 28-19E	WO	<input checked="" type="checkbox"/>
442559	WELL	WO	12/09/2015	LO	077-10255	Piceance Fed 28-09E	WO	<input type="checkbox"/>

Inspector Name: CONKLIN, CURTIS

442560	WELL	WO	10/14/2015	LO	077-10256	Piceance Fed 28-20E	WO	<input checked="" type="checkbox"/>
442562	WELL	WO	11/26/2015	LO	077-10257	Piceance Fed 28-15E	WO	<input type="checkbox"/>
442563	WELL	WO	10/24/2015	LO	077-10258	Piceance Fed 28-18E	WO	<input checked="" type="checkbox"/>
442564	WELL	WO	11/07/2015	LO	077-10259	Piceance Fed 28-17E	WO	<input checked="" type="checkbox"/>
442565	WELL	WO	12/05/2015	LO	077-10260	Piceance Fed 28-10E	WO	<input type="checkbox"/>
442566	WELL	WO	12/13/2015	LO	077-10261	Piceance Fed 28-07E	WO	<input type="checkbox"/>
442567	WELL	WO	11/12/2015	LO	077-10262	Piceance Fed 28-16E	WO	<input type="checkbox"/>

**Equipment:**

Location Inventory

Special Purpose Pits: _____	Drilling Pits: _____	Wells: <u>17</u>	Production Pits: _____
Condensate Tanks: <u>8</u>	Water Tanks: _____	Separators: <u>5</u>	Electric Motors: _____
Gas or Diesel Mortors: _____	Cavity Pumps: _____	LACT Unit: _____	Pump Jacks: _____
Electric Generators: _____	Gas Pipeline: _____	Oil Pipeline: _____	Water Pipeline: _____
Gas Compressors: _____	VOC Combustor: <u>1</u>	Oil Tanks: _____	Dehydrator Units: _____
Multi-Well Pits: _____	Pigging Station: _____	Flare: _____	Fuel Tanks: _____

**Location**

**Lease Road:**

Type	Satisfactory/Action Required	comment	Corrective Action	Date
Access	SATISFACTORY			

**Signs/Marker:**

Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date
TANK LABELS/PLACARDS	SATISFACTORY			
WELLHEAD	SATISFACTORY			

Emergency Contact Number (S/AR): SATISFACTORY

Corrective Date: \_\_\_\_\_

Comment: \_\_\_\_\_

Corrective Action: \_\_\_\_\_

**Good Housekeeping:**

Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

**Spills:**

Type	Area	Volume	Corrective action	CA Date

Multiple Spills and Releases?

<b>Fencing/:</b>				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

<b>Equipment:</b>				
Type:	#	Satisfactory/Action Required:		
Comment				
Corrective Action				Date:

<b>Facilities:</b>		<input type="checkbox"/> New Tank	Tank ID: _____	
Contents	#	Capacity	Type	SE GPS
PRODUCED WATER		500 BBLS	STEEL AST	,
S/AR	SATISFACTORY	Comment: 35 Frack Tanks on location		
Corrective Action:				Corrective Date:

**Paint**

Condition	Adequate
-----------	----------

Other (Content) \_\_\_\_\_

Other (Capacity) \_\_\_\_\_

Other (Type) \_\_\_\_\_

**Berms**

Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Corrective Action				Corrective Date
Comment				

<b>Venting:</b>	
Yes/No	NO
Comment	

<b>Flaring:</b>				
Type	Satisfactory/Action Required			
Comment: _____				
Corrective Action:				Correct Action Date:

<b>Predrill</b>				
Location ID: 442551				
Lease Road Adeq.: _____		Pads: _____		Soil Stockpile: _____
S/AR: _____				
Corrective Action: _____		Date: _____		CDP Num.: _____

**Form 2A COAs:**

Group	User	Comment	Date
OGLA	kubeczkd	<p>Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service any temporary surface or permanent buried pipelines and following any reconfiguration of the pipeline network.</p> <p>Operator will utilize, to the extent practical, all existing access and other public roads, and/or existing pipeline right-of-ways, when placing/routing the surface pipelines. This will reduce surface disturbance and fragmentation of wildlife habitat in the area.</p>	07/13/2015
OGLA	kubeczkd	<p>Operator must ensure secondary containment for any volume of fluids contained at tank site during operations (as shown on the Location Drawing and the Construction Layout Drawings attachments); including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days and after significant precipitation events, and/or in accordance with CDPHE regulations), and maintained in good condition.</p> <p>The location is in an area of moderate to high run-on/run-off potential; therefore standard stormwater BMPs must be implemented at this location prior to construction, throughout construction, drilling, and completion operations to insure compliance with CDPHE and COGCC requirements and to prevent any stormwater run-on and /or stormwater run-off.</p> <p>The access road will be constructed and maintained as to not allow any sediment to migrate from the access road to nearby surface water or any drainages leading to surface water.</p> <p>Strategically apply fugitive dust control measures, including enforcing established speed limits on private roads, to reduce fugitive dust and coating of vegetation and deposition in water sources.</p> <p>Berms or other containment devices shall be constructed to be sufficiently impervious (corrugated steel with poly liner) to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.</p>	07/13/2015
OGLA	kubeczkd	<p>Notify the COGCC 48 hours prior to start of pad construction, rig mobilization, spud, pipeline testing, start of hydraulic stimulation operations, and start of flowback operations (if different than the start of hydraulic stimulation operations) using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).</p>	07/13/2015

<p>OGLA</p>	<p>kubeczkd</p>	<p>The moisture content of drill cuttings managed onsite shall be kept as low as practicable to prevent accumulation of liquids greater than de minimis amounts. After drilling and completion operations have been completed, the drill cuttings that will remain on the well pad location (cuttings management area, the cut portion of the pad, cuttings trench, dry cuttings drilling pit), must meet the applicable standards of Table 910-1. Land-farming of E&amp;P waste is prohibited on the location; however, this shall not preclude onsite disposal of E&amp;P waste in accordance with COGCC Rules and permit conditions. After the drill cuttings have been amended (if necessary) and placed on the well pad, sampling frequency of the drill cuttings (to be determined by the operator) shall be representative of the material left on location. No offsite disposal of cuttings to another oil and gas location shall occur without prior approval of a an amended Waste Management Plan (submitted via a Form 4 Sundry Notice) specifying disposal location and waste characterization method. Commercial disposal of drill cuttings will only require notification to COGCC via a Form 4 Sundry Notice.</p> <p>If the wells are to be hydraulically stimulated, flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or storage vessel located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area constructed to be sufficiently impervious to contain any spilled or released material.</p> <p>Potential odors associated with the completions process and/or with long term production operations must be controlled/mitigated.</p>	<p>07/13/2015</p>
-------------	-----------------	---	-------------------

**S/AR:** \_\_\_\_\_ **Comment:** Notifications have been received.

**CA:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Wildlife BMPs:**

BMP Type	Comment
<p>Wildlife</p>	<p>PICEANCE ENERGY, LLC</p> <p>Best Management Practices (BMP's) To Reduce Impacts to Wildlife on the Piceance 28-10 Pad For Operations in Sec. 28, Twn. 9S, Rng. 93W 6th PM Mesa County, CO</p> <p>COGCC Mapping indicates: ** NO RSO (Restricted Surface Occupancy) on the Piceance 28-10 Pad ** SWH (Black Bear) on the Piceance 28-10 Pad Note: COGCC Order 399-7 Excuses Piceance Energy from consultation with CDOW (CPW) contained in rule 306c.</p> <p>In an effort to minimize the impacts to wildlife, the following BMP's are part of Piceance Energy's (PE) standard operating procedures for drilling and operations within the Piceance Basin. This list is a partial of PE's policy.</p> <p>Initial Stages for Infrastructure and Roads</p> <p>1. Road design and General</p> <ul style="list-style-type: none"> <li>- No firearms, no dogs on location, and no feeding of wildlife.</li> <li>- Minimize the amount of traffic on lease roads within 3 hours of sunrise and sunset.</li> <li>- Use existing routes as much as possible to avoid new disturbance and habitat fragmentation and minimize new road construction.</li> <li>- Maximize the topography as much as possible in designing roads to reduce, visual, noise, impacts, etc.</li> <li>- Participate in road sharing agreements with other Operators when possible.</li> <li>- Design and surface roads based on the traffic, speed, and type of vehicles to reduce, dust, mud, and environmental damage.</li> <li>- Locate roads away from riparian areas and bottoms of drainages as much as possible or re-route entirely.</li> <li>- Obtain Army Corp of Engineer Permits for any stream crossings prior to construction.</li> </ul>

- Analyze crossings and flow characteristics to determine the best method of crossing, (i.e. culvert, bridge, or low water).
- Armor all stream crossings to reduce erosion and to comply with Stormwater Requirements.
- Implementation of fugitive dust control measures including but not limited to water or magnesium chloride applications, and road surfacing.
- Limit traffic to the minimum needed for safe and efficient operations.
- No driving or parking off of disturbed areas.
- Install and use locked gates or other means when allowed by landowner or Federal Agencies to prevent unauthorized travel on roads and rights-of ways.

## 2. Well pad design and location

- Locate well pads to maximize directional drilling practices. PE currently plans and attempts to locate pads for the maximum number of wells which can safely be developed from each pad. This is normally 16-20 wells per pad which equates to roughly 4 well pads per section.
- Design each location to accommodate both current and future gas production.
- Locate well pads to minimize disturbance yet maximize use to reduce surface impacts.
- Review State and Federal GIS mapping to avoid Sensitive Wildlife Habitat (SWH), Restricted Surface Occupancy (RSO) areas, steep slopes, etc., as much as possible with roads and pad location.
- Design and install gathering lines within the disturbed area of new roads and adjacent to as much as possible to reduce disturbance construction.
- Design Rights-of Way widths to the minimum needed for safe and efficient construction of pipelines
- Remote Telemetry for production operations

## 3. Drilling and Production Operations

- Implement remote telemetry in all operations
- Where topographically possible and subject to landowner approval, use centralized water gathering and transportation systems.
- Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents, and openings.
- Locate facilities to minimize visual effects (e.g. paint color, screening, etc.)
- PE implements a dewatering system in its operations. No fluid pits are constructed or used during drilling or completion operations.
- PE implements an aggressive weed management program. PE incorporates and uses the BLM Colorado River Valley Field Office's "Noxious and Invasive Weed Management Plan for Oil and Gas Operators- March 2007" for all operations. Each spring, Piceance Energy inventories all pads, roads, and pipelines to insure no noxious weeds have been introduced. If noxious weeds are found, the county will be notified and the weeds will be treated. Weeds are continuously monitored and treated throughout the growing season. Only herbicides approved by the EPA and State are used by certified weed applicators.

## 4. Reclamation

- Strip and segregate topsoil from other soil horizons during pad, road, and pipeline construction.
- Minimize topsoil degradation by windrowing no higher than 5 feet when possible.
- Immediately seed topsoil to reduce erosion and prevent weed establishment and maintain soil microbial activity.
- Use only certified weed free native seed mixes, unless recommended otherwise by Federal Agencies or the Landowner.
- Use locally adapted seed when available.
- Use diverse seed mixes to mirror the surrounding area unless recommended otherwise by Federal Agencies or the Landowner.
- Monitor re-vegetation success until a minimum of 75% of preferred perennial plant cover (no weeds) is established.
- Perform "interim" reclamation on all disturbed areas not needed for active producing operations.
- If possible, conduct interim and final reclamation during optimum periods (e.g. late fall/early winter or early spring).
- If needed, fence reclaimed areas to minimize livestock/wildlife impact until plant species have are capable of sustaining grazing.

PICEANCE ENERGY, LLC  
BMPS FOR

Sensitive Wildlife Habitat and Restricted Surface Occupancy  
 Areas Specific to Piceance Energy, LLC  
 Operations within the Piceance Basin  
 Mesa County, CO

Sensitive Wildlife Habitat (SWH)

Black Bear

- Initiate a food and waste/refuse management program that uses bear-proof food storage containers and trash receptacles.
- Initiate an education program that reduces bear conflicts.
- Establish policy to prohibit keeping food and trash in sleeping quarters.
- Establish policy to support enforcement of state prohibition on feeding of black bear.
- Report bear conflicts immediately to CPW .

Signature   /s/ Wayne P. Bankert   Date   5/8/2014    
 Wayne P. Bankert  
 Senior Reg. & Env. Coordinator

Storm Water/Erosion Control      CDPHE Stormwater Certification Number COR03K454 for North Vega Project Area will include this location.

**S/AR:** \_\_\_\_\_ **Comment:** \_\_\_\_\_

**CA:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Comment:** \_\_\_\_\_

**Staking:**

**On Site Inspection (305):**

Surface Owner Contact Information:

Name: \_\_\_\_\_ Address: \_\_\_\_\_

Phone Number: \_\_\_\_\_ Cell Phone: \_\_\_\_\_

Operator Rep. Contact Information:

Landman Name: \_\_\_\_\_ Phone Number: \_\_\_\_\_

Date Onsite Request Received: \_\_\_\_\_ Date of Rule 306 Consultation: \_\_\_\_\_

Request LGD Attendance: \_\_\_\_\_

LGD Contact Information:

Name: \_\_\_\_\_ Phone Number: \_\_\_\_\_ Agreed to Attend: \_\_\_\_\_

Summary of Landowner Issues:

\_\_\_\_\_

Summary of Operator Response to Landowner Issues:

\_\_\_\_\_

Onsite Inspection Memorandum Summarizing Discussions at Inspection as Attachment:

\_\_\_\_\_

**Facility**

Facility ID:   442551   Type:   WELL   API Number:   077-10250   Status:   DG   Insp. Status:   WO

**Workover**

Comment: FLOWBACK: Tetra overseeing flowback. No visible signs of leak or spills. Green completions in place. Water stored on location and reused for stimulation.

Facility ID: 442558 Type: WELL API Number: 077-10254 Status: WO Insp. Status: WO

**Workover**

Comment: FLOWBACK: Tetra overseeing flowback. No visible signs of leak or spills. Green completions in place. Water stored on location and reused for stimulation.

Facility ID: 442560 Type: WELL API Number: 077-10256 Status: WO Insp. Status: WO

**Well Stimulation**

Stimulation Company: Schlumberger Stimulation Type: HYDRAULIC FRAC

Other: \_\_\_\_\_

**Observation:**

Maximum Casing Recorded: 6285 PSI

Tubing: \_\_\_\_\_

Surface: \_\_\_\_\_

Intermediate: \_\_\_\_\_

Production: \_\_\_\_\_

Instantaneous Shut-In Pressure (ISIP) 1887

Bradenhead Psi: 13

Frac Flow Back: Fluid: Gas:

Facility ID: 442563 Type: WELL API Number: 077-10258 Status: WO Insp. Status: WO

**Workover**

Comment: FLOWBACK: Tetra overseeing flowback. No visible signs of leak or spills. Green completions in place. Water stored on location and reused for stimulation.

Facility ID: 442564 Type: WELL API Number: 077-10259 Status: WO Insp. Status: WO

**Workover**

Comment: FLOWBACK: Tetra overseeing flowback. No visible signs of leak or spills. Green completions in place. Water stored on location and reused for stimulation.

**Environmental**

**Spills/Releases:**

Type of Spill: \_\_\_\_\_ Description: \_\_\_\_\_ Estimated Spill Volume: \_\_\_\_\_

Comment: \_\_\_\_\_

Corrective Action: \_\_\_\_\_ Date: \_\_\_\_\_

Reportable: \_\_\_\_\_ GPS: Lat \_\_\_\_\_ Long \_\_\_\_\_

Proximity to Surface Water: \_\_\_\_\_ Depth to Ground Water: \_\_\_\_\_

**Water Well:**

Lat Long

DWR Receipt Num: \_\_\_\_\_ Owner Name: \_\_\_\_\_ GPS : \_\_\_\_\_

**Field Parameters:**

Sample Location: \_\_\_\_\_

Emission Control Burner (ECB): \_\_\_\_\_

Comment: \_\_\_\_\_

Pilot: \_\_\_\_\_ Wildlife Protection Devices (fired vessels): \_\_\_\_\_

**Reclamation - Storm Water - Pit**

**Interim Reclamation:**

Date Interim Reclamation Started: \_\_\_\_\_ Date Interim Reclamation Completed: \_\_\_\_\_

Land Use: RANGELAND, RECREATIONAL

Comment: \_\_\_\_\_

1003a. Waste and Debris removed? \_\_\_\_\_

CM \_\_\_\_\_

CA \_\_\_\_\_ CA Date \_\_\_\_\_

Unused or unneeded equipment onsite? \_\_\_\_\_

CM \_\_\_\_\_

CA \_\_\_\_\_ CA Date \_\_\_\_\_

Pit, cellars, rat holes and other bores closed? \_\_\_\_\_

CM \_\_\_\_\_

CA \_\_\_\_\_ CA Date \_\_\_\_\_

Guy line anchors marked? \_\_\_\_\_

CM \_\_\_\_\_

CA \_\_\_\_\_ CA Date \_\_\_\_\_

1003b. Area no longer in use? \_\_\_\_\_ Production areas stabilized ? \_\_\_\_\_

1003c. Compacted areas have been cross ripped? \_\_\_\_\_

1003d. Drilling pit closed? \_\_\_\_\_ Subsidence over on drill pit? \_\_\_\_\_

Cuttings management: \_\_\_\_\_

1003e. Areas no longer needed for drilling or subsequent operations for have been re-vegetated to 80% of pre-existing? \_\_\_\_\_

Production areas have been stabilized? \_\_\_\_\_ Segregated soils have been replaced? \_\_\_\_\_

**RESTORATION AND REVEGETATION**

Cropland

Top soil replaced \_\_\_\_\_ Recontoured \_\_\_\_\_ Perennial forage re-established \_\_\_\_\_

Non-Cropland

Top soil replaced \_\_\_\_\_ Recontoured \_\_\_\_\_ 80% Revegetation \_\_\_\_\_

1003 f. Weeds Noxious weeds? \_\_\_\_\_

Comment: \_\_\_\_\_

Overall Interim Reclamation \_\_\_\_\_

**Final Reclamation/ Abandoned Location:**

Date Final Reclamation Started: \_\_\_\_\_ Date Final Reclamation Completed: \_\_\_\_\_

Final Land Use: RANGELAND, RECREATIONAL

Reminder: \_\_\_\_\_

Comment: \_\_\_\_\_

Well plugged \_\_\_\_\_ Pit mouse/rat holes, cellars backfilled \_\_\_\_\_

Debris removed \_\_\_\_\_ No disturbance /Location never built \_\_\_\_\_

Access Roads Regraded \_\_\_\_\_ Contoured \_\_\_\_\_ Culverts removed \_\_\_\_\_

Gravel removed \_\_\_\_\_

Location and associated production facilities reclaimed \_\_\_\_\_ Locations, facilities, roads, recontoured \_\_\_\_\_

Inspector Name: CONKLIN, CURTIS

Compaction alleviation \_\_\_\_\_ Dust and erosion control \_\_\_\_\_

Non cropland: Revegetated 80% \_\_\_\_\_ Cropland: perennial forage \_\_\_\_\_

Weeds present \_\_\_\_\_ Subsidence \_\_\_\_\_

Comment: \_\_\_\_\_

Corrective Action: \_\_\_\_\_ Date \_\_\_\_\_

Overall Final Reclamation \_\_\_\_\_ Well Release on Active Location  Multi-Well Location

**Storm Water:**

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

S/A/V: \_\_\_\_\_ Corrective Date: \_\_\_\_\_

Comment: \_\_\_\_\_

CA: \_\_\_\_\_

**Pits:**  NO SURFACE INDICATION OF PIT