

FORM  
2

Rev  
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401033528

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

05/10/2016

Well Name: YUUBERG

Well Number: RU 413-7

Name of Operator: TEP ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: PO BOX 370

City: PARACHUTE State: CO Zip: 81635

Contact Name: VICKI SCHOEBER Phone: (970)263-2721 Fax: ( )

Email: VICKI.SCHOEBER@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030107

WELL LOCATION INFORMATION

QtrQtr: LOT 3 Sec: 7 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.452118

Longitude: -107.825801

Footage at Surface: 1926 feet FNL/FSL FSL 158 feet FEL/FWL FWL

Field Name: RULISON Field Number: 75400

Ground Elevation: 7358 County: GARFIELD

GPS Data:

Date of Measurement: 12/10/2008 PDOP Reading: 2.9 Instrument Operator's Name: J. KIRKPATRICK

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1652 FSL 296 FWL 1652 FSL 296 FWL  
Sec: 7 Twp: 7S Rng: 93W Sec: 7 Twp: 7S Rng: 93W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T7S-R93W

SEC. 7: LOTS 1 (40.27 NW/4NW/4), 2 (40.21 SW/4NW/4), 3 (40.15 NW/4SW/4), 4 (40.09 SW/4SW/4), E/2W/2

T7S-R94W

SEC. 12 LOTS 1 (37.02 NE/4NE/4), 2 (39.63 NW/4NE/4), 5 (37.56 SE/4NE/4), 6 (37.98 NE/4SE/4), SW/4NE/4, NW/4SE/4

Total Acres in Described Lease: 553 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 690 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 4504 Feet

Building Unit: 4504 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 2293 Feet

Above Ground Utility: 3581 Feet

Railroad: 5280 Feet

Property Line: 857 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 304 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

CA - COC57580 - All of Sec. 7, T7S-R93W, Top MVRD to base of MVRD

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-76		

## DRILLING PROGRAM

Proposed Total Measured Depth: 9406 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator: \_\_\_\_\_

3753 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48	0	60	23	60	0
SURF	13+1/2	9+5/8	32.3	0	1124	272	1124	0
1ST	8+3/4	4+1/2	11.6	0	9406	900	9406	4798

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments \_\_\_\_\_

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ No \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 413683

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Vicki Schoeber

Title: Regulatory Specialist Date: 5/10/2016 Email: vicki.schoeber@wpenergy.co

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 7/11/2016

Expiration Date: 07/10/2018

### API NUMBER

05 045 23257 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

- |  |   |
|--|---|
|  | <p>1)Operator shall comply with the most current revision of the Northwest Notification Policy.</p> <p>2)Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1).</p> <p>3)Operator shall comply with the most current revision of the Mamm Creek Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1).</p> <p>4)Operator shall comply with the Notice to Operators Drilling Wells in the Buzzard, Mamm Creek, and Rulison fields, Garfield County and Mesa County – Procedures and Submittal Requirements for Compliance with COGCC Order Nos. 1-107, 139-56, 191-22, and 369-2 (July 8, 2010).</p> <p>5)Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to a minimum of 500' above the Lower Wasatch (as defined by COGCC in the report "Casing and Cement Standards for Geologic Isolation Piceance Basin Bradenhead Monitoring Area and Nearby Fields," dated April 18, 2016, COGCC Document No. 2056199, Appendix A Field Scout Cards and Annotated Type Logs) to provide isolation of the Lower Wasatch, all Mesaverde Group formations including the Ohio Creek Formation, if penetrated, and underlying formations. Verify production casing cement coverage with a cement bond log. This requirement shall supersede the top of cement requirements in the Mamm Creek Field Notice to Operators.</p> |
|--|---|

## Best Management Practices

No	BMP/COA Type	Description
1	Planning	<ul style="list-style-type: none"> <li>• Maximize the utility of surface facilities by developing multiple wells from a single pad (directional drilling), and by co-locating multi-purpose facilities (for example, well pads and compressors) to avoid unnecessary habitat fragmentation and disturbance of additional geographic areas.</li> <li>• Minimize newly planned activities and operations within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river.</li> <li>• Avoid constructing any road segment in the channel of an intermittent or perennial stream</li> <li>• Minimize the number, length, and footprint of oil and gas development roads</li> <li>• Use existing roads where possible</li> <li>• Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors</li> <li>• Combine and share roads to minimize habitat fragmentation</li> <li>• Where possible, consolidate pipeline and existing roadways, or roadways that are planned for development</li> <li>• Maximize the use of directional drilling to minimize habitat loss/fragmentation</li> <li>• Maximize use of long-term centralized tank batteries to minimize traffic</li> <li>• Maximize use of remote telemetry for well monitoring to minimize traffic</li> <li>• Phase and concentrate development activities, so that large areas of undisturbed habitat for wildlife remain.</li> <li>• Maintain undeveloped areas within development boundaries sufficient to allow wildlife to persist within development boundaries during all phases of construction, drilling, and production.</li> </ul>
2	Drilling/Completion Operations	<ul style="list-style-type: none"> <li>• WPX will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completions operations.</li> <li>• WPX will implement best management practices to contain any unintentional release of fluids.</li> <li>• Either a lined drilling pit or closed loop system will be implemented.</li> <li>• Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures).</li> </ul>
3	Drilling/Completion Operations	<p>* WPX will run triple-combo open hole logs from well TD up to base of surface casing on one of the first wells drilled on a multi-well pad. Remaining wells on the pad will be logged with either cased hole pulsed neutron or triple-combo open hole. Every well will also have a CBL log from well TD up through well surface. Form 5 Completion Reports will identify wells on the pad with triple-combo open hole logs.</p>
4	Interim Reclamation	<ul style="list-style-type: none"> <li>• Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation Requirements</li> <li>• Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife</li> <li>• WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas.</li> <li>• Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings.</li> <li>• Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.</li> </ul>

Total: 4 comment(s)

### **Applicable Policies and Notices to Operators**

Policy
Mamm Creek Field Area Notice to Operators. <a href="http://cogcc.state.co.us/documents/reg/Policies/Mamm%20Creek%20Drilling.pdf">http://cogcc.state.co.us/documents/reg/Policies/Mamm%20Creek%20Drilling.pdf</a>
Piceance Rulison Field - Notice to Operators. <a href="http://cogcc.state.co.us/documents/reg/Policies/NoticeToOp-20060623-2.pdf">http://cogcc.state.co.us/documents/reg/Policies/NoticeToOp-20060623-2.pdf</a>
NW Colorado Notification Policy. <a href="http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf">http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf</a>
Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field). <a href="http://cogcc.state.co.us/documents/reg/Policies/NT0_07082010.pdf">http://cogcc.state.co.us/documents/reg/Policies/NT0_07082010.pdf</a>
Notice Concerning Operating Requirements for Wildlife Protection. <a href="http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf">http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf</a>

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
401033528	FORM 2 SUBMITTED
401038058	DIRECTIONAL DATA
401038766	WELL LOCATION PLAT
401041136	DEVIATED DRILLING PLAN
401041138	DEVIATED DRILLING PLAN

Total Attach: 5 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Nearest well belonging to another operator is Laramie Energy's South Leverich 18-05D to the South. Final review complete.	7/8/2016 3:23:02 PM
Engineer	Revised cement top meets COA#5 based on operator's geologic prognosis for Lower Wasatch top.	6/20/2016 1:44:38 PM
Permit	Changed production casing top of cement from 5098' to 4798' and sacks of cement from 842 to 900 as directed by operator.	6/20/2016 9:48:55 AM
Permit	Pad has been built and has 4 producing wells. Preliminary review complete.	6/15/2016 7:17:12 AM
Engineer	Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 127 feet deep. Offset Well Evaluation: Existing offset oil and gas wells within 1,500 feet of this wellbore meet standards. No mitigation required.	5/23/2016 3:15:40 PM
Permit	Passed completeness.	5/19/2016 2:01:04 PM

Total: 6 comment(s)