

FORM
5
Rev
09/14

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
401062451

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 96155 Contact Name: Elvera Berryman
 Name of Operator: WHITING OIL & GAS CORPORATION Phone: (303) 390-4221
 Address: 1700 BROADWAY STE 2300 Fax: (303) 390-1598
 City: DENVER State: CO Zip: 80290

API Number 05-123-42111-00 County: WELD
 Well Name: Horsetail Well Number: 07G-0609
 Location: QtrQtr: SWNE Section: 7 Township: 10N Range: 57W Meridian: 6
 Footage at surface: Distance: 2643 feet Direction: FNL Distance: 1798 feet Direction: FEL
 As Drilled Latitude: 40.853503 As Drilled Longitude: -103.791786

GPS Data:
 Date of Measurement: 03/01/2016 PDOP Reading: 1.8 GPS Instrument Operator's Name: Larry D. Brown

** If directional footage at Top of Prod. Zone Dist.: 2554 feet. Direction: FNL Dist.: 2478 feet. Direction: FEL
 Sec: 7 Twp: 10N Rng: 57W
 ** If directional footage at Bottom Hole Dist.: 1290 feet. Direction: FNL Dist.: 2462 feet. Direction: FEL
 Sec: 6 Twp: 10N Rng: 57W

Field Name: WILDCAT Field Number: 99999
 Federal, Indian or State Lease Number: _____

Spud Date: (when the 1st bit hit the dirt) 03/23/2016 Date TD: 03/26/2016 Date Casing Set or D&A: 03/27/2016
 Rig Release Date: 03/27/2016 Per Rule 308A.b.

Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 12755 TVD** 5751 Plug Back Total Depth MD 12755 TVD** 5751

Elevations GR 4892 KB 4913 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:
LWD, MUD, RCBL (Note, Neutron log run on Horsetail Fed 07G-0612)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	65	0	101		0	101	VISU
SURF	13+1/2	9+5/8	36	0	2,024	660	0	2,024	VISU
1ST	8+1/2	5+1/2	20	0	12,746	2,420	80	12,746	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	1,685		NO	NO	
HYGIENE	3,535		NO	NO	
SHARON SPRINGS	5,684		NO	NO	
NIOBRARA	5,693		NO	NO	

Comment:

BHL was drilled 30' too far to the north (30' INTO the federal setback of 1320'). Tartan Sub is at 12651.3' (lowest interval to complete) and 73.7' off the federal setback to the north, Float Collar is at 12696.9' and 28.1' off the federal setback to the north. Cement fills the hole from 12696.9' to TD.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Elvera Berryman

Title: Engineering Technician

Date: _____

Email: elvera.berryman@whiting.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
401062736	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
401062748	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
401062726	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401062727	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401062749	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401062863	PDF-CBL 2ND RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401063664	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
401063665	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)