



YETTER WELL SERVICE, INC.

P.O. Box 1808 • Sterling, Colorado 80751-7808

Phone (970) 522-2885

Date 8-27-14

COMPANY Beren Corp

LEASE Thompson

WELL NO. 1

RIG 9

COUNTY Logan

Work Ordered By: Ed Haynes Job Description: Dt A

	HOURS	TOTAL
Travel To Loc, nipple down well. Rig up J-W		
Set plug @ 5540' Dump 2 Sacks Cement Rig up		
for 4 1/2" weld bell nipple, install 4 1/2" work		
Casing. Load hole with 40 lbs Gel. Rig up		
J-W free point 4 1/2" casing off @ 1024'		
Casing pulled free Rig down J-W. Rig up Casing		
Truck lay down 26 TS Rig down 4 1/2" Casing	1 1/2	\$ 3162 50
S.D.F.N		

RODS	PUMP	SUBS		
TUBING	SUBS	OTHER		
Remarks:				
FURNISHED	Csg tool trucks	@ 22.50	2	170 00
	4 1/2" csg recovery			350 00
	210 bbl tank	30 days		150 00
	50 bbl tank			50 00

Casing wiper

63 75

UNIT CHARGE

Empty 13
Man 17
Phil 5
Hydr 5

1 1/2
1 1/2
1 1/2
1 1/2

TAX \$63.75

2 49

TOTAL

\$3963 74



YETTER WELL SERVICE, INC.

P.O. Box 1808 • Sterling, Colorado 80751-7808
Phone (970) 522-2885

Date 8-28-14

COMPANY Beren Corp
RIG 9

LEASE Hanson
COUNTY Logan

WELL NO. _____

Work Ordered By: Ed Daines Job Description: Q4A

	HOURS	TOTAL
Travel To Loc. uncap well Rig up For 2 1/2 Tally in hole To 1026' Rig up Cement unit pump 50 sack Cement plug. Rig down cement unit. pull tubing To Derrick. Standby 4 hrs. Run Tubing in as cement @ 800' pull Tubing To 274' pump 2nd p. 11 pull Tubing To 200' Rig up & pump 50 sack Cement plug. pull Tubing. Cap well SDFM	9 1/2	\$2612 50

RODS	PUMP	SUBS
TUBING	SUBS	OTHER

Remarks:

FURNISHED

4 1/2 Collar
210 Tank
50 bbl Tank

10 5/8 Well Head ADAPTOR

UNIT CHARGE

Randy B
Mat M
Phil H
Tyler J

4 1/2
9 1/2
9 1/2
9 1/2

TAX \$65.00

TOTAL

254
\$2755 04



YETTER WELL SERVICE, INC.

P.O. Box 1808 • Sterling, Colorado 80751-7808
Phone (970) 522-2885

Date Aug. 28 2014

COMPANY BEREAS CORP

LEASE Thompson

WELL NO. 1

RIG Cement equip

COUNTY Hogan Co

Work Ordered By: Ed Hanes Job Description:

3-28 To location with bulk truck.
Mix & pump 50 ss cement down tubing for
stub plug. 2% chlorides added cement weight
was 14.5#. Displace with 5 bbls for balance
plug. Stand by for 4 1/2 hrs for cement to
set up. Plug was tagged @ 800'

Mix 50 ss cement with 2% chlorides @ 14 1/2#.
Pump down tub @ 200' for 1/2 in 1/2 out plug
Displace for balance plug.
Wash up.

Cont Pg 2

RODS	PUMP	SUBS		
TUBING	SUBS	OTHER		
Remarks:				
FURNISHED	Cement blending unit		6	800 00
	Cement bulk truck			576 00
	Tool pusher 1/2 day			300 00

UNIT CHARGE

J. RUFF
A. YETTER

TAX
TOTAL

\$ 1676 00

YETTER WELL SERVICE, INC.

P.O. Box 1808 • Sterling, Colorado 80751-7808
 303-622-2885

Phone (970) 522-2885

Date Aug 29 2014

COMPANY: BEER COOP

LEASE Thompson

WELL NO. _____

RIG Cement equip

PAGE 2

COUNTY Logan, Co.

Work Ordered By:

Job Description:

HOURS

TOTAL

29. To location, logging @ 145'. Mix 45 ss cement to 14 1/2" pump down tub, filled surface csg to top. Wash up, rack out. Return to yard.

RODS

PUMP

SUBS

TUBING

SUBS

OTHER

Remarks:

FURNISHED

145 sr bulk cement

@ 14.00

\$2030	00
--------	----

9 ~~sw~~ gel bentonite

② 16.60

149 40

Cement blending unit

14	00
----	----

$\frac{1}{2}$ sack chlorides

2

150	00
-----	----

1 Ton for gel

25	00
----	----

Plastic liner

30000

Took Pusher 1/2 day.

30000

UNIT CHARGE

A. YETTER

I. RUFF

TAX	\$ 2218.40
-----	------------

TOTAL

865

\$ 2754	9
---------	---

YETTER WELL SERVICE, INC.

P.O. Box 1808 • Sterling, Colorado 80751-7808
Phone (970) 522-2885

Date 8-29-14

COMPANY

LEASE Thompson

WELL NO.

COUNTY *Logan*

RIG

Job Description:

Work Ordered By: Ed Haynes

HOURS

TOTAL

Travel To Loc Rig up For Tubing Run Tubing, Tag
Cement @ 145' Rig up cement unit. pump 45
Sacks, From 145' To Surface Rig down Cement unit.
pull Tubing, Rig down more of F.

卷

\$1237	50
--------	----

RODS

PUMP

SUBS

TUBING

SUBS

OTHER

Remarks:

FURNISHED

UNIT CHARGE

TAX

TOTAL

\$1337	50
--------	----