

Operator: Synergy Resources Corporation
Well Name: Anders Coombs #6
Legal: NWNW, Sec 25, T5N, R66W
Location: Weld County, CO
API: 05-123-12852

Wellbore History




Spud Date: 12/22/1985
 Surf Csg: 8.625", 24# @ 501'
 Prod Csg: 4.5", 11.6# @ 7355'

TOC: 5600' from CBL.
 Perfs: Niobrara: 7066'-7070'
 Codell: 7244'-7259'

P&A Procedure

Set retainer @ 6,991' and squeeze perfs
 Pmp 5 sks @ 6,991' (50' plug)
 Pmp 10 sx @ 1600' (100' plug)
 Cut Casing @ 500' and POOH
 Pmp 235 sx @ 550'- 0'

Key

-  Existing Cement Coverage
-  Retainer
-  Cement Pumped

