

July 27, 2016

Steven Hale
Environmental Specialist
Encana Oil & Gas (USA) Inc.
1125 Escalante Drive
Rangely, CO 81648

RE: K28-2103 WELL PAD FINAL RECLAMATION STATUS

Dear Steven,

Per your request, WestWater biologists have completed vegetation monitoring for the above referenced reclaimed location. We utilized the Bureau of Land Management's (BLM) Assessment, Inventory, and Monitoring (AIM) strategy for data collection and the resulting data has been entered into the Database for Inventory, Monitoring and Assessment (DIMA). In addition to monitoring the reclaimed area we selected and inventoried a reference site for this location.

Attached you will find the results summary and photos of the reclaim and reference areas. Based on the information we collected this year and our understanding of BLM and Colorado Oil & Gas Conservation Commission (COGCC) final reclamation requirements we believe this site meets the criteria to submit Final Abandonment Notice.

If there is any additional information we can provide or clarify please contact me.

Sincerely,



Nicholas Jaramillo
Environmental Scientist

Encana		
Location:	K28-2103 Well Pad	
Date:	7/12/2016	
Scientific Name	Common Name	Foliar Cover
Graminoids		
Agropyron cristatum (L.) Gaertn.	crested wheatgrass	33.3
Bromus tectorum L.	cheatgrass	8.0
Pascopyrum smithii (Rydb.) Á. Löve	western wheatgrass	16.7
Psathyrostachys juncea (Fisch.) Nevski	Russian wildrye	7.3
Grass cover subtotal		65.3
Forbs		
Alyssum desertorum Stapf	desert madwort	6.0
Grindelia squarrosa (Pursh) Dunal	curlycup gumweed	2.7
Forb cover subtotal		8.7
Shrubs		
Atriplex canescens (Pursh) Nutt.	fourwing saltbush	4.0
Gutierrezia sarothrae (Pursh) Britton & Rusby	broom snakeweed	5.3
Shrub cover subtotal		9.3
	Reference Site	Reclaim Site
Vegetative Cover	92.0	64.7
Basal Cover	4.0	2.7
Bare ground	4.0	26.0
Desirable Cover	44.0	58.0
% Desirable of Reference	-	131.8



Reclaim Transect 1



Reclaim Transect 2



Reclaim Transect 3



Reference Transect