

Diana,

I would like to make 1 adjustment to the sidetrack plan below with your approval, we pulled back to 10,300 and continued to see shale over the shakers. So the new open hole sidetrack point would be **7,520**. Everything will stay the same that will be the only adjustment to the plan. We will make sure this is reflected in our Forms as well.

Thanks,

Ty Entenmann

From: Diana Burn - DNR [<mailto:diana.burn@state.co.us>]
Sent: Wednesday, August 10, 2016 8:29 AM
To: Ty Entenmann <ntenmann@extractionog.com>; Mike Hickey - DNR <mike.hickey@state.co.us>; Barbara Westerdale - DNR <barbara.westerdale@state.co.us>; Penny Garrison - DNR <penny.garrison@state.co.us>
Cc: Kamrin Ruder <kruder@extractionog.com>
Subject: RE: Winder #6 123-39573

Please proceed as proposed.

Thanks,
Diana

From: Ty Entenmann [<mailto:ntenmann@extractionog.com>]
Sent: Wednesday, August 10, 2016 7:08 AM
To: Diana Burn - DNR
Cc: Kamrin Ruder
Subject: Winder #6

Diana,

We had an issue on the Winder #6, drilling ahead in the Niobrara we stayed low for a throw we were anticipating. However, it was larger than seismic and the offset well indicated. This caused us to expose the Sharron Springs for 250'. We conditioned mud and weighted up our fluid but this gave us little success. While the hole tried to grab us we felt the best option was to sidetrack. With your permission we would like to open hole sidetrack (no cement) at 7.520'. This will allow us to adjust targets and stay below the Sharron Springs through this throw.

API Number - 05123957300

Total MD drilled to: 13,864'

Surface casing – 9 5/8" 36# set at 1539'.

Proposed fish: None

The plan would be to open hole sidetrack

Proposed sidetrack point – 10,300’’

Objective formation of sidetrack: Niobrara

Proposed BHL: 964 FNL 460 FWL Sec 8, T6N, R67W (Same as original APD).

Thanks for your time,



Ty Entenmann

Drilling Engineer

Extraction Oil & Gas

370 17th St, Suite 5300

Denver, CO 80202

Direct: 720.557.8326

www.ExtractionOG.com