

JOB SUMMARY		PROJECT NUMBER TN # FL100	TICKET DATE 6/15/2016
COUNTY Weld	COMPANY Whiting	CUSTOMER REP Kyle Renton	
LEASE NAME Horsetail	Well No. 07H-1813	EMPLOYEE NAME Ben Doran	
JOB TYPE Production			

Cody Bushnell

Thank You For Using
O - TEX Pumping

O-Tex / Equipment and Personnel Report					
O-Tex Location		Customer		Project Number FL1001	Job Date 6/15/2016
Pampa Tx		Whiting		State CO	County Weld
Lease Name Horsetail	Well No.	O-Tex Field Supervisor Ben Doran	Customer Representative Kyle Renton		Phone 970.380.2666
Job Type Production		Man Hours			
USE THIS FORM TO NOTE ANY ISSUES ENCOUNTERED WITH THE PERFORMANCE OF THIS JOB. THIS MAY INCLUDE TIME AT THE SHOP, ON THE ROAD OR DELAYS WITH DRILLING CONTRACTOR.					
DATE	TIME	VOLUME	RATE	PRESS	JOB PROCEDURES
6/15/2016	4:00				Arrive on location
6/15/2016	4:05				Talk to client rep.
6/15/2016	4:10				Spot trucks and rig in iron and hoses
6/15/2016	4:45				Wait on rig to circulate and rig out casers
6/15/2016	5:55				Safety Meeting
6/15/2016	6:38	3 BBL	2BPM	70	Fill lines
6/15/2016	6:41			5000PSI	All lines held pressure
6/15/2016	6:45	60 BBL	7.00	1300	30 BBL Mudflush, 30 BBL Visweep
6/15/2016	6:54	50	10.50	1300	Scavenger/ 11.5 PPG, 2.27 Yield, 13.21 Water Req, 85.14 Sack Weight
6/15/2016	7:00	96	10.50	1500	Lead 12 PPG, 1.96 Yield, 10.9 Water Req, 85.13 Sack Weight
6/15/2016	7:08	141.4	10.50	1500	Fill, 12 PPG, 1.96 Yield, 10.9 Water Req, 85.13 Sack Weight
6/15/2016	7:21	427.4	11.00	700	Tail 13.5 PPG, 1.5 Yield, 7.5 Water Req, 87.38 Sack Weight
6/15/2016	8:04	10			Wash out lines
6/15/2016	8:11				Drop Plug
6/15/2016	8:12	309.8	10.50	1900	40 BBL of cement to surface @ 12 PPG
6/15/2016	8:54			2490	500 PSI over
6/15/2016	8:56				Check Floats 2 BBL Back
6/15/2016	9:05				Rig Out
6/15/2016	9:30				Leave Location
JOB CALCULATIONS					
50 BBL Scavenger @ 11.5 PPG, 96 BBL Lead @ 12 PPG, 141.4 BBL Fill @ 12 PPG, 427.4 BBL Tail@ 13.5 PPG					
CASING DATA					
309.8 BBL of Displacement					
Shoe Track 1 BBL					
ANNULAR DATA					
Annular Capacity 585 BBL					
Perfect Hole expecting 129.8 BBL of Slurry to Surface					
PLEASE NOTE ANY CONTRACTOR ISSUES OR COMMENTS BELOW					

Job Data Sheet



COMPANY Whiting				PROJECT NUMBER TN # FL1001		AFE/WORK ORDER 0		DATE 6/15/2016		
CONTRACTOR 0				Owner		LEGAL DESCRIPTION W NE 12/T10N/R58V		API 0		
LEASE & WELL # Horsetail				07H-1813		COUNTY Weld		STATE CO		
DIRECTIONS						MILEAGE 60				
HWY 71 to CR 120 W to CR 133, S 1/4, E into										
Pumping Services	Job Procedures: Take Radios. Bring Back All Circulating Iron and Equipment								JobType: Production	
	Casing Size 5 1/2	Casing Weight 20.00	Thread Butress	Tbng/DP Size 0	Weight 0	Plug. Cont. YES	Swage NO	Top Plug YES	Bottom Plug YES	
							% Excess 15%			
	Number and Type Units 2						Casing Depth 14020	Hole Depth 14020	Hole Size 8 1/2	
Materials	Remarks 0						Tubing Depth 0	Depth-TVD 7000	Mud Weight/Type 9 WBM	
	Scavenger	# of Sacks 105	Type 50/50 Poz/Type III	Additives						
		Weight PPG 11.5	Yield Ft3/Sk 2.27	Water Gal/Sk 13.21	0.3% ASM-3 + 0.5% CFL-10 + 2% FWC-2 + 0.1% LTR + 0.25 lb/sk LCL-7					
		Lead	# of Sacks 275	Type 50/50 Poz/Type III	Additives					
			Weight PPG 12	Yield Ft3/Sk 1.96	Water Gal/Sk 10.9	0.3% ASM-3 + 0.5% CFL-10 + 2% FWC-2 + 0.1% LTR + 0.25 lb/sk LCL-7				
		Lead	# of Sacks 405	Type 50/50 Poz/Type III	Additives					
			Weight PPG 12	Yield Ft3/Sk 1.96	Water Gal/Sk 10.9	0.3% ASM-3 + 0.5% CFL-10 + 2% FWC-2 + 0.1% LTR + 0.25 lb/sk LCL-7				
	Tail	# of Sacks 1620	Type 35/65 Poz/Class G	Additives						
		Weight PPG 13.5	Yield Ft3/Sk 1.5	Water Gal/Sk 7.5	0.3% ASM-3 + 0.5% CFL-10 + 0.2% SPC-2 + 0.25 lb/sk LCL-7					
	Flush	Quantity 30	Type Mudflush	Additives SAPP + 5 gal WS-30						
	Spacer	Quantity 30	Type Visweep	Additives 10 gal WG-1L						
	Sugar	Quantity 100	Type 0	Additives Add to Ticket if Needed						
Safety and Info	DRIVE AND WORK SAFE AT ALL TIMES									
Sales Items	Casing Size 5 1/2	Casing Weight 20.00	Thread Butress	Circulating Iron YES						
	Guide Shoe NO	Float Shoe 3rd Party		Float Collar 3rd Party		Insert Float Valve NO				
	Centralizers - Number 0	Size 0		Type 0						
	Wall Cleaners - Number	Type		MSC (DV Tool) NO		MSC Plug Set NO				
	Limit Clamps	Thread lock NO		Other						
	Remarks GET ALL NUMBERS FROM CO. MAN FOR TICKET									
Customer Rep. Kyle Renton		Cell Phone 970.380.2666	Office Phone	Fax	Time of Call 0800					
Call Taken By Barlen Joyner					Date Ready 6/15/16	Time Ready 1200				
Crew Called Ben Doran Sam Cheal Sean Barden Cody Bushnell					Time 0800					

Client Whiting
Ticket No. 1001
Location Sec12:T10N:R58W
Comments Pump job as per design

Client Rep Kyle Renton
Well Name Horsetail 07H-1813
Job Type Production Casing

Supervisor Ben Doran
Unit No. 445033
Service District Fort Lupton
Job Date 06/15/2016

Unit 445033 Rate Total



Unit 445033 Pump Pressure



Unit 445033 Density

