

CPC 117 A-5 - NE-SE-7-T2S-R6SW - ADAMS Co., COLO.

WELL DIAGRAM @ : 3-29-91

KB: 5347'  
GL: 5339'

PREVIOUS OPERATOR: AMOCO

CMT'D 10JTS OF 8-5/8" 24#  
BKT K-55 CSG. W/ 325SX  
331', 8-5/8" SHOE

5-1/2" OD-K-55-BKT-STG CSG  
RAN 262 JTS & CMT'D IN 2 STAGES  
W/ 600SX - (DV TOOL @ 1700')

TUBING STRING (10-27-76 LATEST?)  
273 JTS-2-7/8" EUE J-55 L.S. # 8328.08'  
SN 1110'  
TAIL JST + TBG. ANCHOR 33.09'  
KB 8.00'  
TBG LANDED DE @ 8370'

ROD STRING (7-4-88 LATEST?)

80 JTS 7/8" X 25' 2000'  
250 JTS 3/4" X 25' 6250'  
7/8" X 6' POLY ROD 6'  
3/4" X 2' POLY ROD 2'

2" 25-RHAC 16-6-3-4  
PUMP

"J" SAND PERFS.

(1SPF) 8304' squeezed  
(2SPF) 8330'  
8342'

8337' SN

8370'

PERFS 8304-8342':

FRAC'D

9000# 20-40 SD  
9000# 10-20 SD  
2000# 8-12 BEADS

8369' PBTD

FRAC'D W/ 5000# 20-40 SD.

842