

FORM
2
Rev
08/16

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
401050469

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

TYPE OF WELL OIL GAS COALBED OTHER _____
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Refiling
Sidetrack

Date Received:
07/07/2016

Well Name: YOUBERG Well Number: SR 411-12
Name of Operator: TEP ROCKY MOUNTAIN LLC COGCC Operator Number: 96850
Address: PO BOX 370
City: PARACHUTE State: CO Zip: 81635
Contact Name: VICKI SCHOEBER Phone: (970)263-2721 Fax: ()
Email: VSCHOEBER@TERRAEP.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160057

WELL LOCATION INFORMATION

QtrQtr: SWNE Sec: 12 Twp: 7S Rng: 94W Meridian: 6
Latitude: 39.455361 Longitude: -107.833915

Footage at Surface: 1912 Feet FNL 2120 Feet FEL

Field Name: RULISON Field Number: 75400

Ground Elevation: 7254 County: GARFIELD

GPS Data:
Date of Measurement: 04/21/2016 PDOP Reading: 2.8 Instrument Operator's Name: J. Kirkpatrick

If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1244 FNL 1136 FWL 1244 FNL 1136 FWL
Sec: 12 Twp: 7S Rng: 94W Sec: 12 Twp: 7S Rng: 94W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T7S R94W
SEC. 12: LOTS 3 (39.04 NE/4NW/4), 4 (38.04 NW/4NW/4), 7 (38.40 SE/4SE/4), S/2NW, SW, SWSE

Total Acres in Described Lease: 395 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # COC36490

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 1136 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet
 Building Unit: 5280 Feet
 High Occupancy Building Unit: 5280 Feet
 Designated Outside Activity Area: 5280 Feet
 Public Road: 257 Feet
 Above Ground Utility: 1773 Feet
 Railroad: 5280 Feet
 Property Line: 470 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
 - Enter 5280 for distance greater than 1 mile.
 - Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
 - Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
 - Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
 - Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 395 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 1136 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

CA -COC55168 – All of Sec. 12, T7S-R94W, MVRD

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-76	640	All of Section 12

DRILLING PROGRAM

Proposed Total Measured Depth: 9731 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 1773 Feet No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48	0	60	23	60	0
SURF	13+1/2	9+5/8	32.3	0	1100	266	1100	0
1ST	8+3/4	4+1/2	11.6	0	9731	765	9731	

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number _____

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: 324061

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: VICKI SCHOEBER

Title: Regulatory Specialist Date: 7/7/2016 Email: VSCHOEBER@TERRAEP.CO

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 9/9/2016

Expiration Date: 09/08/2018

API NUMBER 05 045 23291 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

- | | |
|--|--|
| | <p>1)Operator shall comply with the most current revision of the Northwest Notification Policy.</p> <p>2)Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1).</p> <p>3)Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to a minimum of 200' above the Lower Wasatch (as defined by COGCC in the report "Casing and Cement Standards for Geologic Isolation Piceance Basin Bradenhead Monitoring Area and Nearby Fields," dated April 18, 2016, COGCC Document No. 2056199, Appendix A Field Scout Cards and Annotated Type Logs) to provide isolation of the Lower Wasatch, all Mesaverde Group formations including the Ohio Creek Formation, and underlying formations, if penetrated. Verify production casing cement coverage with a cement bond log.</p> |
|--|--|

Best Management Practices

No	BMP/COA Type	Description
1	Planning	<ul style="list-style-type: none"> * Maximize the utility of surface facilities by developing multiple wells from a single pad (directional drilling), and by co-locating multipurpose facilities (for example, well pads and compressors) to avoid unnecessary habitat fragmentation and disturbance of additional geographic areas. * Minimize the number, length, and footprint of oil and gas development roads * Use existing roads where possible * Combine utility infrastructure (gas, electric, and water) planning with roadway planning to avoid separate utility corridors * Combine and share roads to minimize habitat fragmentation * Where possible, consolidate pipeline and existing roadways, or roadways that are planned for development * Maximize the use of directional drilling to minimize habitat loss/fragmentation * Maximize use of long-term centralized tank batteries to minimize traffic * Phase and concentrate development activities, so that large areas of undisturbed habitat for wildlife remain.
2	Drilling/Completion Operations	<ul style="list-style-type: none"> * Use centralized hydraulic fracturing operations. * Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures).
3	Drilling/Completion Operations	<p>* TEP will run triple-combo open hole logs from well TD up to base of surface casing on one of the first wells drilled on a multi-well pad. Remaining wells on the pad will be logged with either cased hole pulsed neutron or triple-combo open hole. Every well will also have a CBL log from well TD up through well surface. Form 5 Completion Reports will identify wells on the pad with triple-combo open hole logs.</p>
4	Interim Reclamation	<ul style="list-style-type: none"> * Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation requirements * Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife * TEP will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeded and reclamation of disturbed areas. * Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings. * Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

Policy
Piceance Rulison Field - Notice to Operators. http://cogcc.state.co.us/documents/reg/Policies/NoticeToOp-20060623-2.pdf
NW Colorado Notification Policy. http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

Att Doc Num	Name
401050469	FORM 2 SUBMITTED
401064976	DIRECTIONAL DATA
401064977	DEVIATED DRILLING PLAN
401064978	DEVIATED DRILLING PLAN
401071361	SURFACE AGRMT/SURETY
401071364	WELL LOCATION PLAT
401074409	FED. DRILLING PERMIT

Total Attach: 7 Files

General Comments

User Group	Comment	Comment Date
Permit	Review of this form is complete. Ready for final approval.	3/2/2016 1:41:56 PM
Permit	Initial review complete.	3/5/2016 2:34:59 PM
LGD	KHW Pass	7/28/2016 1:39:13 PM
Engineer	<p>Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information was used to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 127 feet.</p> <p>Offset Well Evaluation: Existing offset oil and gas wells within 1,500 feet of this wellbore meet standards. No mitigation required.</p> <p>Operator's geologic prognosis for the Lower Wasatch top is 5553'. Removed operator's proposed first string cement top. Operator's proposed first string cement top is not adequate to satisfy COGCC's new cement coverage requirements, effective April 18, 2016. Increase cement coverage accordingly, as specified in Condition of Approval #3.</p>	7/14/2016 8:50:40 AM
Permit	Passed completeness.	7/12/2016 10:21:57 AM

Total: 5 comment(s)