

FORM  
2

Rev  
08/16

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401114151

(SUBMITTED)

Date Received:

09/19/2016

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: B&V

Well Number: 24D-07-07-95

Name of Operator: URS OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1050 17TH STREET #1700

City: DENVER

State: CO

Zip: 80265

Contact Name: JENNIFER LIND

Phone: (720)508-8362

Fax: ( )

Email: JLIND@URSARESOURCES.COM

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120125

#### WELL LOCATION INFORMATION

QtrQtr: NWSW Sec: 7 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.450228

Longitude: -108.047108

Footage at Surface: 1903 Feet FNL/FSL FSL 552 Feet FEL/FWL FWL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 5083

County: GARFIELD

GPS Data:

Date of Measurement: 06/10/2014 PDOP Reading: 1.7 Instrument Operator's Name: HOFFMANN

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FSL 82 FSL 1900 FSL 1900 FSL 1900  
FEL/FWL FWL 82 FEL/FWL FWL 1900 FEL/FWL FWL 1900

Sec: 7 Twp: 7S Rng: 95W Sec: 7 Twp: 7S Rng: 95W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

PLEASE SEE LEASE MAP ATTACHED TO ORIGINAL APD SUBMITTAL.

Total Acres in Described Lease: 173 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 570 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 650 Feet  
Building Unit: 650 Feet  
High Occupancy Building Unit: 692 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 529 Feet  
Above Ground Utility: 849 Feet  
Railroad: 1104 Feet  
Property Line: 247 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☒ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: 05/23/2014

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/23/2014

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 330 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 82 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	440-72	320	SEC.7 - S/2

## DRILLING PROGRAM

Proposed Total Measured Depth: 6928 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: \_\_\_\_\_ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	84	0	60	111	60	0
SURF	12+1/4	8+5/8	32	0	1841	380	1841	0
1ST	7+7/8	4+1/2	11.6	0	6928	482	6928	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☒ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number 440-72

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments B&V 24D-07-07-95 APD refile. Please note, the B&V pad location has been constructed and conductors have been set at this location. Ursa currently has plans to begin drilling operations on the B&V pad beginning November, 2016. No changes to the original APD are proposed at this time, all attachments submitted with the original Form 2 are still valid and therefore are not re-attached with this submittal.

I certify there have been no changes to land use or mineral lease description and there will be no additional surface disturbance associated with this well. The location does not require a variance from any of the rules listed in Rule 306.d. (1).(a).(ii). This location is not within a wildlife Restricted Surface Occupancy area.

First String / Production cement will be > 500 feet above TOG. Please see attached plat for reference to cultural setbacks. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the proposed B&V 24C-07-07-95. Distance to existing/proposed well belonging to another operator was measured to the TEP T&T LTD PA 444-12 (API 05-045-22428).

Ursa requests the approval of a 502.b. variance request to spacing order number 440-72 pursuant to Rule 318.c. as the BHL for this well falls 82' from the spacing unit boundary. Variance request letter and mineral interest owner waivers attached.

UMA notification to LGD was sent on 5/23/14. Pre-application Notice / Buffer Zone Notice was sent to building unit owners within 1000' of the location on 5/23/14. UMA BMPs, LGD notification certification and pre-application certification are attached to the associated B&V pad Form 2A (Doc #400632523).

This application is in a Comprehensive Drilling Plan No CDP #: \_\_\_\_\_

Location ID: 440634

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: 9/19/2016 Email: JLIND@URSARESOURCES.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

### API NUMBER

05 045 22714 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description



## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which openhole logs were run.

Total: 1 comment(s)

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401114151	FORM 2 SUBMITTED
401114240	VARIANCE REQUEST
401118767	SURFACE AGRMT/SURETY

Total Attach: 3 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

