

Foundation Energy Management, LLC

Well / Battery Devlin 12-33	Prospect Name Tri-States	Total Depth 1767	Est. Start Date 7/20/2015
Location 1940 FNL, 660 FWL	Sec-Twn-Rng SW-NW Sec. 33 4S 43W	Producing Horizon Niobrara	County & State Yuma, Colorado

WBD Before

Prepared Date: 6/23/2015
Prepared By: Austin McCollum

General Info

API #: 05-125-06715

KB Elevation: 3850'

GL Elevation: 3845'

Spud Date: 03-04-1982

Completion Date: 03-28-1982

TVD: 1767'

MD: 1767'

Last PBTD: 1732'

Tubing Detail

2-3/8 inch(OD)

4.7 # (weight)

J-55 grade

Tubing Tally

		Length	Depth
52 jts	2-3/8	1643'	1643'

Surface Casing

7 inch (OD)

17 # (weight)

322' depth from KB

0 cement top

80 sacks of cement

9-7/8 inch (OD) HOLE SIZE

Visual Returns

Rod Design

		length	depth
65 jts	5/8	1625	1625

Production Casing

4-1/2 inch (OD)

9.5 # (weight)

1732 depth from KB

684' cement top

100 sacks of cement

6-1/4 inch (OD) HOLE SIZE

Calculated

Open Perforations

1599' - 1614' (2 SPF)

Niobrara

PBTD: 1732'