



Xtreme 20

Well:	Rabbit Ears 0681 1-23H Pilot Hole		
Field:	North Park		
County:	Jackson, CO		
Surface:	1720' FNL & 2246' FEL, Section 23-T06N-R81W		
PBHL:	1720' FNL & 2246' FEL, Section 23-T06N-R81W		
GL:	8,308'	KB:	8,324'

Drilling:	Tyler McCullar
Manager:	Ron Goff
Geology:	Scott Cherry
Completions:	Jake Thomas
Land:	Rick Silman
AFE #:	

Wellhead Equipment	
Tubing Head	11" 5M X 7-1/16" 5M
B-Section	
A-Section	9-5/8" SOW x 11" 5M

Tubular Detail						
	Size	Wt	Grade	Conn	From	To
Surface	9-5/8"	36#	J-55	LT&C	0'	2400'
Intermediate						
Production:						

Logging Program			
	Detail	From	To
Run #1	Triple Combo + Sonic	TD	2,400'

Well Configuration	Vertical
Target Formation	Frontier

Wellhead Equipment

Wellhead Equipment	
Tubing Head	11" 5M X 7-1/16" 5M
B-Section	
A-Section	9-5/8" SOW x 11" 5M

Tubular Detail

	Size	Wt	Grade	Conn	From	To
Surface	9-5/8"	36#	J-55	LT&C	0'	2400'
Intermediate						
Production:						

Logging Program

	Detail	From	To
Run #1	Triple Combo + Sonic	TD	2,400'

Well Configuration

Well Configuration	Vertical
Target Formation	Frontier

Wellbore Log Data

Depth (ft)	Formation / Description
1,985'	Lance
2,400'	9-5/8", 36#, J-55
2,900'	Fox Hills
3,480'	Sussex
4,000'	Shannon
4,346'	Top of KOP Plug #5
4,846'	Bottom of KOP Plug
4,945'	Mancos
5,040'	Top of Cement Plug #4 (200')
5,240'	Niobara - Bottom of Cement Plug
6,275'	Carlisle
6,285'	Top of Cement Plug #3 (200')
6,485'	Frontier - Bottom of Cement Plug
6,835'	Top of Cement Plug #2 (200')
7,035'	Dakota
7,195'	Morrison
7,555'	Top of Cement Plug #1 (200')
7,755'	Entrada
8,425'	Chugwater
8,500'	TD Pilot

Prepared By	Date	Cementing	Logging Company	Mud Loggers	Mud Company	Disposal
Tyler McCullar	10/13/2016	-	-	-	-	-
		-	-	-	-	-
		-	-	-	-	-