

BOX ELDER B-1 - NE-SE SEC. 12 T2S-R66W, ADAMS CO., CO

GL = 5261'

KB = 5269'

WELL DIAGRAM

PREVIOUS OPERATOR: KOCH

SPUDDED: 1-25-72

COMPLETED: 3-5-72

Perf. at TOC - circ. to surface

fill annular to surface

fill hole to surface -

Approx. 300 SACKS

20 SKs Cement 1750' - 1650'

CMTD 8-5/8" 24# K-55 CSG.
W/150 SX

219' - 8-5/8" CSG. SHOE

CMTD 5-1/2" OD, 17# CSG. IN
2 STAGES W/500 SX. -

1700' 150 SKs
50/50 poz

* J SAND PERFS.

8293 - 8318' (2SPF)

FRAC'D W/

4000# - 20-408d

8000# - 10-20 6d.

1000# - 8-12 PROPP.

13,000#

CIBP 8220' dumphail
2 SKs Cement on top

8335' - PBTD

- 5-1/2" CSG. SHOE

- TD