



## Rabbit Ears 0681 3-23H

SWNE Section 23-T6N-R81W (Surface Hole Location)

SWNE Section 34-T6N-R81W (Bottom Hole Location)

Jackson County, Colorado

### Drilling Plan

#### 1. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS & ANTICIPATED WATER, OIL, GAS OR MINERAL FORMATIONS:**

##### Vertical

Formation	TVD (ft)	Hydrocarbon/Water Bearing Zones
Lance	1985	
Fox Hills	2900	
Sussex	3480	
Shannon	4000	
Mancos	4945	
Niobrara	5240	Oil / Gas

##### Horizontal

Formation	MD/TVD (ft)	Lat/Long	Hydrocarbon/ Water Bearing Zones
Kick Off Point	5150 / 4977	40° 28' 37.297 N / 106° 27' 25.419 W	
Niobrara Entry Point	5490 / 5240	40° 28' 37.274 N / 106° 27' 28.158 W	Oil / Gas
Landing Point – EOC	6479 / 5585	40° 28' 33.104 N / 106° 27' 37.414 W	Oil / Gas
TD	17280 / 5585	40° 26' 51.245 N / 106° 28' 19.138 W	Oil / Gas

NOTE: Kick Off & Landing Points may change based upon results of correlations in the vertical hole

All shows of fresh water and hydrocarbons will be adequately protected and reported.  
Gas detection to be operational prior to drilling the Niobrara.

## **2. PRESSURE CONTROL EQUIPMENT:**

All well control equipment shall be in accordance with Onshore Order #2 for 5M systems.

The minimum specifications for pressure control equipment that will be provided are included on the attached schematic diagram showing size and pressure ratings

5,000# BOP with 5" Pipe Rams  
5,000# BOP with Blind Rams  
5,000# Annular  
Rotating Head

Auxiliary equipment to be used

- Upper kelly cock with the handle available
- Stabbing Valve

The choke manifold will include appropriate valves and adjustable chokes. The kill line will have one check valve.

Ram type preventers will be pressure tested to full working pressure (utilizing a tester and a test plug) at:

- initial installation
- whenever any seal subject to test pressure is broken
- following related repairs
- 30 day intervals

The annular preventer will be pressure tested to 50 percent of the rated working pressure

All pressure tests shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

Annular preventers shall be functionally operated at least weekly.

Pipe and blind rams shall be activated each trip.

A BOPE pit level drill will be conducted weekly for each drilling crew.

All test and drills will be recorded in the drilling log.

The accumulator will have sufficient capacity to open the HCR valve, close all rams plus the annular preventer, and retain 200 psi above pre-charged pressure without the use of closing unit pumps. The system will have two independent power sources to close the preventers in accordance with 5M system requirements outlined in Onshore Order #2.

Remote controls shall be readily accessible to the driller Master controls shall be at the accumulator.

**3. CASING & CEMENTING PROGRAM:**

- A. The proposed casing program will be as follows. **See attached document for casing design parameters and safety factors.**

Section	Measured Depth (ft)	Hole Size (in)	Size (in)	Grade	Weight (#/ft)	Thread	Condition
Conductor	0-90	20	16	H-40	65	STC	New
Surface	0-2,400	12-1/4	9-5/8	J-55	36.0	LTC	New
Production	0-17,280	8-3/4	5-1/2	P-110	20	DQX	New

All casing strings below the conductor shall be pressure tested to 0.22 psi/ft. of casing string length or 1,500 psi, whichever is greater, but not to exceed 70% minimum internal yield.

- B. The proposed cementing program will be as follows

**Conductor String:** Top of cement – surface  
Estimated volume gauge hole (70.68 ft<sup>3</sup>) + 50% excess

**Lead:** 63 sks Type III  
Yield: 1.67 ft<sup>3</sup>/sk  
Weight: 13.5 lbm/gal  
Mix Water: 8.83 gal/sk

**Surface String:** Top of cement – surface  
Estimated volume gauge hole (751.63 ft<sup>3</sup>) + 60% excess

**Lead:** 435 sks Class G  
Yield: 2.185 ft<sup>3</sup>/sk  
Weight: 12.5 lbm/gal  
Mix Water: 12.17 gal/sk

**Tail:** 142 sks Class G  
Yield: 1.763 ft<sup>3</sup>/sk  
Weight: 13.5 lbm/gal  
Mix Water: 9.01 gal/sk

**Production String:** Top of cement – Surface  
Estimated volume gauge hole (4173.01 ft<sup>3</sup>) + 25% excess  
(if open hole logs are run, caliper + 5% excess will be used)

**Lead:** 706 sks Class G  
Yield: 2.299 ft<sup>3</sup>/sk  
Weight: 12 lbm/gal  
Mix Water: 12.57 gal/sk

**Tail:** 2316 sks Class G  
Yield: 1.653 ft<sup>3</sup>/sk  
Weight: 13.5 lbm/gal  
Mix Water: 7.87 gal/sk

After cementing, but before commencing any test, the casing string will stand cemented until cement has reached a compressive strength of 500 psi at the shoe. WOC times will be recorded in the driller's log.

**4. DRILLING FLUIDS PROGRAM:**

Interval (ft)	Type	Weight (ppg)	Viscosity	Ph	Water Loss (cc)	Remarks
Surface	Spud	8.4-9.0	40-60	8-10	NC	WBM – gel & lime
Production	OBM	10.3	40-50	8-9	<9 (HTHP)	OBM

NC = no control

Sufficient quantities of mud material will be maintained on site or be readily accessible for the purpose of assuring well control SPR will be recorded on daily drilling report after mudding up Electronic/mechanical mud monitoring equipment will be utilized and will include a pit volume totalizer (PVT), stroke counter, and flow sensor as a minimum.

**5. EVALUATION PROGRAM:**

**Logs (while drilling)**                      MWD-GR                      Kick Off point to TD

**OH Logs:**                                      Triple Combo – TD to Surface Casing

**Cores:**    None anticipated

**DST's**    None anticipated

**6. ABNORMAL CONDITIONS:**

No anticipated abnormal pressures or temperatures expected to be encountered No hydrogen sulfide expected.

Anticipated bottom-hole pressure is approximately 2971 psi (10.23 ppg EMW)

**7. OTHER INFORMATION:**

The anticipated starting date and duration of the drilling and completion operations will be as follows

Start Date: Upon Approval  
Duration: 60 days

The well will be drilled from surface location to bottom hole location per attached directional plan. The proposed well path should not pose any collision or interference concerns with any existing wells along its proposed path.

Drilling will use approximately 9500 bbls of fresh water for the operation. See attached map and directions to water source at Petry Lake.

A completion rig will be used for completion operations. All conditions of this approved plan will be applicable during all operations conducted with the completion rig.