



1	COMPANY:	CHEVRON USA INC.	CASING	LINER	TUBING	TAILPIPE
3	WELL NUMBER:	CT CARNEY 15-35	SIZE	7"	5 1/2"	2 7/8"
4	FIELD/LEASE:	RWSU	WEIGHT	23#	17#	6.5#
5	COUNTY:	RIO BLANCO	GRADE	J-55	L-80	K-55
	STATE:	COLORADO	THREAD		LTC	EUE
	DATE:	18-Oct-16	DEPTH	5842'	5753'	6466'
6	ITEM	DESCRIPTION	O.D.	I.D.	LENGTH	DEPTH
	Well Type	WAG INJECTOR	END OF TAILPIPE			5676.78
	KB				11.00	
7	1	TC1A TUBING HANGER			0.85	11.00
	2	COMPRESSION #12,000			-1.50	11.85
	3	1 JT 2 7/8" F.L. PXP (NEW)	3.460	2.125	32.03	10.35
	4	4' X 2 7/8" PUP JT F.L. (NEW)	3.668	2.125	4.15	42.38
8	5	171 JTS 2 7/8" F.L. TUBING (NEW)	3.668	2.125	5544.01	46.53
	6	5 1/2" PS-1 PACKER RHS-RHR COATED & CARBIDES	4.641	2.401	7.00	5590.54
	7	1 JT 2 7/8" FGW-TK15 (NEW)	3.868	2.401	31.40	5597.54
9	8	1.875F EXT. POLAR ON/OFF TOOL 316 S.S.	4.475	1.875	4.60	5628.94
	9	6' X 2 7/8" FGW-TK15 PUP JT. (NEW)	3.868	2.401	6.16	5633.54
	10	5 1/2" x 2 3/8" LOK-SET COATED & CARBIDE RHS-RHR	4.641	1.901	4.10	5639.70
	11	1 JT 2 7/8" FGW-F.L. (NEW)	3.868	2.125	32.61	5643.80
	12	2 7/8" W/L ENTRY GUIDE	3.668	2.500	0.37	5676.41
						5676.78
10		7" 23# J-55 0'-5842'				
		5 1/2" 17# L-80 0'-5753'				
		5 1/2" 17# K-55 5753'-6466'				
		TIE-BACK LINER PACKER @5751'				
		LINER HANGER @5753				
11		PERFS 5852'-6434'				
		BTM PACKER SET WITH 20,000# OF COMPRESSION				
		TOP PACKER SET WITH 12,000# OF COMPRESSION				
		CASING TESTED 1200 PSI				
		TUBING TESTED 2500 PSI				
		PBTD 6439'				

Prepared for: **BRANDON SCHILLING**

Prepared by: **ANDY KEY**

MILLER PUMPS / PACKERS
1161 E. 1300 S. VERNAL UT.
435-781-0666

Form # 42 401130369