

PxA Intent Wellbore Diagram

Best Information as of 5/1/16

Elev. GL: 4700'
KB: 4710'

8-5/8", 24#
Set @ 303'

Spud: 1/13/2000
Comp: 3/25/2000

10 sx Surface Plug

50 sx Csg Plug 350' to 250'

100 sx Stub Plug 5550'-5400'

Cut casing @ ~ 5500'

Hole size 7-7/8" to TD

Top of Cement @ \pm 5990'
Niobrara Top @ 5970'

Production Casing
5-1/2" 15.5# J-55
set @ 6774' w/160 sx

Set CIBP @ 6525' w/10 sx cmt
on top

6588' perforated w/4 SPF

6592'

PBTD @ 6747'

TD: 6777'

Markus Production, Inc.

Wickstrom #42-16

SE/NE Section 16-T6N-R60W
Morgan County, Colorado
API# 05-087-08106