

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
401141944
(SUBMITTED)

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____ Refilling ☐
ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐ Sidetrack ☐

Date Received:

Well Name: Gunderson Well Number: 20-04W
Name of Operator: LARAMIE ENERGY LLC COGCC Operator Number: 10433
Address: 1401 SEVENTEENTH STREET #1400
City: DENVER State: CO Zip: 80202
Contact Name: Joan Proulx Phone: (970)263-3641 Fax: ()
Email: jproulx@laramie-energy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120081

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 20 Twp: 9S Rng: 93W Meridian: 6
Latitude: 39.266919 Longitude: -107.795317
Footage at Surface: 972 Feet FNL/FSL 1975 Feet FEL/FWL FWL
Field Name: BUZZARD CREEK Field Number: 9500
Ground Elevation: 7145 County: MESA
GPS Data:
Date of Measurement: 08/09/2015 PDOP Reading: 1.5 Instrument Operator's Name: Braden Box
If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
Footage at Top of Prod Zone: FNL/FSL 785 FNL 1300 FWL 785 FNL 1300 FWL
Sec: 20 Twp: 9S Rng: 93W Sec: 20 Twp: 9S Rng: 93W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian
The Surface Owner is: ☒ is the mineral owner beneath the location.
(check all that apply) ☒ is committed to an Oil and Gas Lease.
☒ has signed the Oil and Gas Lease.
☐ is the applicant.
The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian
The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes
The right to construct the Oil and Gas Location is granted by: oil and gas lease
Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Twn. 9S Rng. 93W 6th PM Mesa County, CO
Sec 20: W2NW

Total Acres in Described Lease: 80 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 29 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1090 Feet
Building Unit: 1092 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 1159 Feet
Above Ground Utility: 1171 Feet
Railroad: 5280 Feet
Property Line: 325 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone ☐ Exception Zone ☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 200 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 785 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

This well is inside COGCC Order 369-15. As per the Order Condition No. 5, Laramie Energy, LLC will submit a CA to the BLM at least 90 days before the anticipated date of first production (as defined in COGCC Rules) from the initial well completed

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK-ILES	WFILS	369-15	480	S20: W2, SE

DRILLING PROGRAM

Proposed Total Measured Depth: 7601 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: _____ Feet ☒ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE

Cuttings Disposal Method: Other

Other Disposal Description:

Due to character limit (255), See submittal comments for Drilling Waste Management

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	112	0	60	120	60	0
SURF	11	8+5/8	24.0	0	1530	296	1530	0
1ST	7+7/8	4+1/2	11.6	0	7601	1200	7601	1022

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

Location Drawing
Production Layout
Access Road Map
Hydrology Map
Stormwater
Wildlife BMP's
Submitted as part of Location Assessment Doc No: 401141886

Disposal Description: (Drilling Waste Management)

PE plans to drill the wells within this project boundary with a dewatering system with no need for a reserve pit. Drilling fluids are recycled and re-used with cuttings being de-watered and captured in a catch pan, stacked in a cuttings management area and allowed to dry. Once the cuttings are dry and satisfy the COGCC for rule 910 analytics, the cuttings will be stacked along the cut slope then buried and covered with a minimum of 3 feet of cover. This operation will occur after the completion of the wells.

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: _____ Email: jproulx@laramie-energy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged open-hole with a triple combo log (HRI w/ SP,GR, CAL and Spectral Density/Dual Spaced Neutron) from TD into the surface casing. All wells on the pad will have a radial analysis bond log with gamma ray run on production casing from TD to surface after rig moves off pad. All wells not logged with an open hole log will have a cased hole NEO neutron emulated open hole log run from TD to surface. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 1 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401150473	DIRECTIONAL DATA
401150474	DEVIATED DRILLING PLAN
401150633	DRILLING PLAN
401151411	WELL LOCATION PLAT

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

