

Gunderson 20-05E Mesa County, Colorado DRILLING PROGNOSIS

Surface Location

NE/4 of NW/4
Section 20 T9S R93W 6th P.M.
Graded Elevation 7146' MSL
RKB Elevation 7176' (30' KB H&P 522)

SHL Geographical Coordinates (NAD-83)

Slot A-5
Latitude 39.266864000° N
Longitude 107.795281000° W

Directional Target

50-ft radius cylinder centered on BHL
From estimated top of gas (TOG) to TD

BHL Geographical Coordinates (NAD-83)

Latitude 39.266935000° N
Longitude 107.788371000° W

Casing OD	Hole Size	Weight	Condition	Grade	Coupling	Setting Depth (MD)	Top of Cement
16"	26"	¾" WT	New	-	Welded	60-ft BGL	surface
8-5/8"	11"	24 ppf	New	J-55	STC	1530-ft	surface
4-1/2"	7-7/8"	11.6 ppf	New	Next-80	LTC	7948-ft	1022-ft

Cementing Details

8-5/8" Surface Casing

Halliburton Name	VariCem GJ5	Tail
Type	Extended	Extended
Additives	Pol-E-Flake	Pol-E-Flake
Planned top	Surface	1000-ft
Density (ppg)	12.30	12.80
Yield (cf/sx)	2.45	2.18
Volume (sx)	187	109
Volume (bbls)	82	42

4-1/2" Production Casing

Halliburton Name	NeoCem GJ2	Tail
Type	II/V	50:50 Poz:G
Additives	Pol-E-Flake	Pol-E-Flake, Kol-Seal
Planned top	1030-ft	5698-ft
Density (ppg)	12.50	13.30
Yield (cf/sx)	1.94	1.79
Volume (sx)	819	445
Volume (bbls)	283	142

Formation Tops (Sd = Sand; Sh = Shale; SW = salt water)

Name	MD (ft)	TVD (ft)	Description	Expected Pore Pressure (ppg)	Planned Mud Weight (ppg)
Wasatch	-	G.L.	Sd/Sh; freshwater to 500'	8.3	8.5 - 8.8
'G' Sand	2606	2453	Sd/Sh; gas	8.8	9.0 - 9.3
Williams Fork	4908	4553	Sd/Sh; gas & SW	8.8	9.0 - 9.3
Top of Gas	5898	5503	Sd/Sh; gas & SW	8.8 - 9.2	9.0 - 9.5
Cameo	6998	6603	Sd/Sh/Coals; gas & condensate	8.8 - 9.2	9.0 - 9.5
Base Cameo Coal	7658	7263	Sd/Sh/Coals; gas & condensate	8.8 - 9.2	9.0 - 9.5
Rollins	7698	7303	Sd/Sh; gas, condensate & SW	9.0 - 9.5	9.3 - 9.7
Total Depth	7948	7553	Sd/Sh; gas, condensate & SW	9.0 - 9.5	9.5 - 9.7

BOP : 11" 5M Double Gate & 11" 5M Annular Preventer, Rotating Head