

Foundation Energy Management, LLC
Drilling - Completion - Workover - Facilities
DISCUSSION

Well / Battery Newton 33-32	Prospect Name Tri-States	Total Depth 2591	Est. Start Date 1/1/2015
Location NW SE	Sec-Twn-Rng Sec 32 - T2N - R44W	Producing Horizon Niobrara	County & State Yuma, CO

AFE Description
Plug and Abandon

WBD Before

Prepared Date: 11/17/2015
Prepared By: Neil Hutton

General Info

API #: 05-125-09535

KB Elevation: 3849
GL Elevation: 3843

Spud Date: 10/13/2005
Completion Date: 10/16/2005

TVD: 2636
MD: 2636
Last PBTD: 2591

Surface Casing

7" inch (OD)	
20 # (weight)	
J55 grade	
386 depth from KB	
0 cement top	Calculated
148 sacks of cement	
9.875 inch (OD) HOLE SIZE	

Tubing Tally

80jts	J-55	2,475'
-------	------	--------

Production Casing

4-1/2 inch (OD)	
9.5 # (weight)	
J-55 grade	
2633 depth from KB	
1,050 cement top	CBL
160 sacks of cement	
6.25 inch (OD) HOLE SIZE	

Open Perforations

2,422' - 2,442' (3 SPF)

PBTD: 2254'