

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401107619

(RE-SUBMITTED)

Date Received:

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: ROCKY

Well Number: 20N-33HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: SHAYELYN MARSHALL

Phone: (720)929-6907

Fax: (720)929-7907

Email: SHAYELYN.MARSHALL@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NENE Sec: 33 Twp: 2N Rng: 65W Meridian: 6

Latitude: 40.101614

Longitude: -104.661188

Footage at Surface: 257 Feet

FNL/FSL

FNL

541

Feet

FEL/FWL

FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4930

County: WELD

GPS Data:

Date of Measurement: 11/04/2016

PDOP Reading: 1.4

Instrument Operator's Name: ROB WILSON

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL

FEL/FWL

Bottom Hole: FNL/FSL

FEL/FWL

51

FNL

1320

FEL

462

FSL

1340

FEL

Sec: 33

Twp: 2N

Rng: 65W

Sec: 33

Twp: 2N

Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 2 North, Range 65 West, 6th P.M.
Section 33: E/2
Weld County, Colorado

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 3328 Feet
Building Unit: 4843 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 4777 Feet
Above Ground Utility: 4772 Feet
Railroad: 5280 Feet
Property Line: 257 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 235 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 462 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

PROPOSED UNIT CONFIGURATION:
2N65W SEC 28: S2SE
2N65W SEC 33: E2

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		400	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12374 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 982 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42.1	0	40	30	40	0
SURF	13+1/2	9+5/8	36	0	1500	600	1500	0
1ST	7+7/8	5+1/2	17	0	12364	1446	12364	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments KMG requested rejection of this permit due to the criteria that more than 3 attachments will require revision due to changes of the well locations. Changes to the permit include: Surface hole location, drilling plan, casing program, right to construct (now SUA), exception location (both 318A.a and 318A.c) and cultural distances (now further away from BUs). Please see new attachments for more detail.

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: Water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field, depending on what is feasible at the time of drilling. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

The following well(s) belong to KMG and are not within 150' of KMG's proposed well, however may appear to be less than 150' in 2D view:

COOK 16N-28HZ - ~3600 vertical feet

COOK 16C-28HZ- ~5200 vertical feet

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SHAYELYN MARSHALL

Title: REGULATORY ANALYST Date: _____ Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

No	BMP/COA Type	Description
1	Planning	This proposed oil and gas location is located in a rural rangeland area. The nearest building unit is located 4756' away.
2	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
4	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

Att Doc Num	Name
401107619	FORM 2 SUBMITTED
401144016	FORM 2 SUBMITTED
401144017	FORM 2 REJECTED
401158939	WELL LOCATION PLAT
401158940	PROPOSED SPACING UNIT
401158942	DEVIATED DRILLING PLAN
401158943	DIRECTIONAL DATA
401158944	EXCEPTION LOC REQUEST
401158945	EXCEPTION LOC WAIVERS
401158946	SURFACE AGRMT/SURETY
401160113	OFFSET WELL EVALUATION

Total Attach: 11 Files

General Comments

User Group	Comment	Comment Date
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

RE-SUBMITTED