

**FORM**  
**21**  
Rev  
08/14

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
401131491  
Date Received:  
10/31/2016

**MECHANICAL INTEGRITY TEST**

1. Duration of the pressure test must be a minimum of 15 minutes.
2. An original pressure chart must accompany this report if this test was not witnessed by an OGCC representative.
3. For production wells, test pressures must be at a minimum of 300 psig.
4. New injection wells must be tested to maximum requested injection pressure.
5. For injection wells, test pressures must be at least 300 psig or average injection pressure, whichever is greater.
6. A minimum 300 psi differential pressure must be maintained between the tubing and tubing/casing annulus pressure.
7. Do not use this form if submitting under provisions of Rule 326.a(1)B. or C.
8. Written OGCC notification must be provided 10 days prior to the test via Form 42, Field Operations Notice
9. Packers or bridge plugs, etc., must be set within 100 feet of the perforated interval to be considered a valid test.

Complete the Attachment  
Checklist

OP OGCC

OGCC Operator Number: <u>100185</u>	Contact Name: <u>Ryan Tompkins</u>	
Name of Operator: <u>ENCANA OIL &amp; GAS (USA) INC</u>	Phone: <u>(970) 285-2685</u>	
Address: <u>370 17TH ST STE 1700</u>		
City: <u>DENVER</u>	State: <u>CO</u>	Zip: <u>80202-5632</u> Email: <u>ryan.tompkins@encana.com</u>
API Number: <u>05-045-21907</u>		OGCC Facility ID Number: <u>431950</u>
Well/Facility Name: <u>SG</u>		Well/Facility Number: <u>8516B-33 E34496</u>
Location QtrQtr: <u>SWNW</u>	Section: <u>34</u>	Township: <u>4S</u> Range: <u>96W</u> Meridian: <u>6</u>

Pressure Chart		
Cement Bond Log		
Tracer Survey		
Temperature Survey		
Inspection Number		

SHUT-IN PRODUCTION WELL       INJECTION WELL      Last MIT Date: \_\_\_\_\_

**Test Type:**

Test to Maintain SI/TA status       5-Year UIC       Reset Packer

Verification of Repairs       Annual UIC TEST

Describe Repairs or Other Well Activities: \_\_\_\_\_

Wellbore Data at Time of Test		
Injection Producing Zone(s)	Perforated Interval	Open Hole Interval
	NP	
Tubing Casing/Annulus Test		
Tubing Size:	Tubing Depth:	Top Packer Depth:
		Multiple Packers? <input type="checkbox"/>

**Casing Test**

Use when perforations or open hole is isolated by bridge plug or cement plug; use if cased-hole only with plug back total depth.

Bridge Plug or Cement Plug Depth

2944

Test Data (Use -1 for a vacuum)				
Test Date	Well Status During Test	Casing Pressure Before Test	Initial Tubing Pressure	Final Tubing Pressure
10-20-2016	TEMPORARILY ABANDONED	0		
Casing Pressure Start Test	Casing Pressure - 5 Min.	Casing Pressure - 10 Min.	Casing Pressure Final Test	Pressure Loss or Gain
349	345	344	343	-6

Test Witnessed by State Representative?       OGCC Field Representative \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jason Eckman

Title: Sr. Regulatory Analyst      Email: jason.eckman@encana.com      Date: 10/31/2016

Based on the information provided herein, this Notice (Form 21) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: BURGER, CRAIG      Date: 1/13/2017

**CONDITIONS OF APPROVAL, IF ANY:**

**Attachment Check List**

<u>Att Doc Num</u>	<u>Name</u>
401131491	FORM 21 SUBMITTED
401139554	FORM 21 ORIGINAL
401139556	PRESSURE CHART
401139557	MECHANICAL INTEGRITY TEST

Total Attach: 4 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Surface casing only. Cement at the surface casing shoe has not been drilled out.	01/13/2017

Total: 1 comment(s)