

**FORM
INSP**Rev
X/15**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

01/12/2017

Submitted Date:

01/17/2017

Document Number:

674603094**FIELD INSPECTION FORM**
 Loc ID 318841 Inspector Name: Maclaren, Joe On-Site Inspection ☐ 2A Doc Num:
Operator Information:OGCC Operator Number: 11065Name of Operator: BRUCE* JACKIEAddress: 2010 46TH AVE #20City: GREELEY State: CO Zip: 80634**Status Summary:**

- ☒ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☐ NO FOLLOW UP INSPECTION REQUIRED

Findings:13 Number of Comments6 Number of Corrective Actions☒ Corrective Action Response Requested**Contact Information:**

Contact Name	Phone	Email	Comment
Mah, Steven		steven.mah@state.co.us	
Leonard, Mike		mike.leonard@state.co.us	
Ellsworth, Stuart		stuart.ellsworth@state.co.us	
Schlagenhauf, Mark		mark.schlagenhauf@state.co.us	
Burn, Diana		diana.burn@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
242287	WELL	DM	02/20/1981	GW	123-10078	BROWN-MONFORT 1	DM

General Comment:

This is a follow-up field inspection conducted on 1/12/2016. The Actions Required outlined on the previous field inspection doc #674602717 performed on 7/28/2016 have not been completed. Details are outlined in this report. Photo's uploaded can be accessed via link(s) at end of report.

LocationOverall Good: ☐

Signs/Marker:			
Type	WELLHEAD		
Comment:	No signage at wellhead.		
Corrective Action:	Install sign to comply with rule 210. ACTION REQUIRED NOT COMPLETED	Date:	08/29/2016

Emergency Contact Number:		
Comment:	No emergency contact information at wellhead.	
Corrective Action:	Install emergency contact information at wellhead. ACTION REQUIRED NOT COMPLETED	Date: 08/29/2016

Good Housekeeping:		
Type	STORAGE OF SUPL	
Comment:	Poly pipe stored at wellhead; Portable office trailer units (owned by CIVEO/ 877-248-3660) are being stored in close proximity and restricting access to wellhead.	
Corrective Action:	Remove/ move supplies and equipment away from wellhead; allow for vehicle access to wellhead. ACTION REQUIRED NOT COMPLETED	Date: 09/29/2016
Type	WEEDS	
Comment:	Weeds observed around wellhead.	
Corrective Action:	Remove existing weeds; Control future weed growth at wellhead. ACTION REQUIRED NOT COMPLETED	Date: 08/29/2016

Overall Good: ☐

Spills:			
Type	Area	Volume	

In Containment: No

Comment:

☐ Multiple Spills and Releases?

Fencing/:		
Type	WELLHEAD	
Comment:	Jersey barriers around/ protecting wellhead.	
Corrective Action:		Date:

Equipment:			corrective date
Type: Flow Line	# 1		
Comment:	Well site flowline runs approximately 300 linear feet south from wellhead then turns east for approximately 965' and surfaces at the Noble Energy Justine 1-10, Western 35 -10, 28-15 tank battery site/ facility. (Note: approximate route of flowline identified with assistance of current landowner).		
Corrective Action:	Properly abandon flowlines no longer in use per COGCC Rule 1103 (See comment section at end of report). ACTION REQUIRED NOT COMPLETED	Date:	10/29/2016
Type: Deadman # & Marked	#		
Comment:	No rig anchors were located; spoke with current landowner who has not observed any existing anchors on property.		
Corrective Action:		Date:	

Venting:		
Yes/No		
Comment:		

Corrective Action:		Date:	
Flaring:			
Type			
Comment:			
Corrective Action:		Date:	

Inspected Facilities

Facility ID: 242287 Type: WELL API Number: 123-10078 Status: DM Insp. Status: DM

Idle Well

Purpose: ☒ Shut In ☐ Temporarily Abandoned

Reminder: _____

Comment: No records of Mechanical Integrity Testing (as indicated on previous field inspection Doc #674100517 performed on 3/20/2014). Note: Well is shut in and has not been used for domestic purposes as indicated on COGCC field inspection Doc #200209162 performed on 4/21/2009.

Corrective Action: Well must be either:

Date: 10/29/2016

1) Per COGCC Rule 326.b.(1) a successful mechanical integrity test shall be performed on each shut-in well within

two (2) years of the initial shut-in date or

2) Be properly plugged and abandoned.

ACTION REQUIRED NOT COMPLETED

COGCC Comments

Comment	User	Date
COGCC Rule 1103. ABANDONMENT Each pipeline abandoned in place shall be disconnected from all sources and supplies of natural gas and petroleum, purged of liquid hydrocarbons, depleted to atmospheric pressure, and cut off three (3) feet below ground surface, or the depth of the pipeline, whichever is less and sealed at the ends. This requirement shall also apply to compressor or gas plant feeder pipelines upon decommissioning or closure of a portion or all of a compressor station or gas plant. Notice of such abandonment shall be filed with the Commission and with the local governmental designee or local government jurisdiction.	maclarej	01/16/2017
COGCC Rule 708. General Liability Insurance. All operators shall maintain general liability insurance coverage for property damage and bodily injury to third parties in the minimum amount of one million dollars (\$1,000,000) per occurrence. Such policies shall include the Commission as a "certificate holder" so that the Commission may receive advance notice of cancellation.	maclarej	01/16/2017
Note: This well remains bonded by Jackie Bruce at \$1000.00	maclarej	01/16/2017
Note: The initial field inspection doc #674602717 was sent certified mail on 8/2/2016 (Received and signed by Bob Bruce on 8/6/2016) to physical address of operator as shown below: Bob & Jackie Bruce 2010 46 Avenue Unit 20 Greeley, Co 90634 970-392-9944	maclarej	01/16/2017

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
674603102	Initial Inspection Photo's 7/28/2016	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4052746
674603103	Wellhead, No Signage, weeds, unused equipment	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4052747
674603104	Wellhead, surrounded by portable office units	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4052748