



FREMONT PAVING and REDI-MIX, INC.

839 MacKenzie Avenue
P. O. Box 841
Cañon City, Colorado 81215

Telephone:
(Bus.) 719 - 275-3264
(Res.) 719 - 275-8200

Mix Identification No.: **S3007**
Design Strength: 3000
Cementitious Content: 9.8
Typical Usage: CDOT 507.04 Sand Grout
Mix Proportions:

Materials:	Type or Size	ASTM Standard	Design Weights per Cubic Yard	
Cement	1-2	C-150	735	lb.
Fly Ash	Class C	C-618	188	lb.
Coarse Aggregate	67	C-33		lb.
Int. Aggregate	# 8	C-33		lb.
Fine Aggregate	Sand	C-33	2370	lb.
AEA		C-260	2.0	oz.
WRA	A	C-494		oz.
MRWR	A	C-494		oz.
HRWR	F	C-494		oz.
Water	City	C-94	417	lb.
Special Material	Fibermesh			lb.

The above weights are based upon aggregates in a saturated, surface dry (SSD) condition. Batch plant corrections must be made for moisture in aggregates. Mix proportions may be adjusted in accordance with ACI 301-99, section 4.2.3.6

Water Requirements: Total Cementitious Materials

W/C Ratio (gal. / sack)	5.10
W/C Ratio (By Weight)	0.45
Water Content (gal. / cu.yd)	50.1

Physical Properties of Mixture:

Slump	7 to 9	in.
Air Content	6 to 10	%
Unit Weight	132	pcf
Yield	28.11	cu. ft.

Compressive Strength (psi):

(Estimated)

	<u>7 Day</u>	<u>28 Day</u>
	3000	4200

John Young
Fremont Paving & Redi-Mix

Office (719) 275-3264
Fax (719) 275-8897
Mobile (719) 429-1442
johnyoung@cpucorp.net

ASPHALT

CONCRETE

SAND & GRAVEL

Equal Opportunity Employer

FREMONT PAVING and REDI-MIX, INC.



839 MacKenzie Avenue
P. O. Box 841
Cañon City, Colorado 81215

Telephone:
(Bus.) 719 - 275-3264
(Fax) 719 - 275-8897




UNIT WEIGHT	SLUMP TEST	AIR TEST	TEMP	CYLINDERS	TIME 12:29	LEAVE PLANT
CUSTOMER ID 1068	P.O. NO./PROJECT NO.	TRUCK F315	DATE 9/6/16	DRIVER TOM BARBER	ARRIVE JOB	FINISH POURING
SOLD TO Havernick Oil		JOB LOCATION KELSEY CT FLORENCE			LEAVE JOB	ARRIVE PLANT
QUANTITY THIS LOAD	QUANTITY ORDERED	QUANTITY DELIVERED	PRODUCT DESCRIPTION	UNIT OF MEASURE	UNIT PRICE	EXTENDED PRICE
9.00 9.00 yd	9.00	9.00	WELL MIX 8 SACK WELL MIX		\$168.75	\$1,518.75
INSTRUCTIONS SLUMP 4.00 DELIVERY INSTRUCTIONS:					SUB TOTAL TAX TOTAL	\$1,518.75 192.01 \$1,690.76
						
GENERAL TERMS AND CONDITIONS OF DELIVERY						

- The purchaser agrees to provide suitable roadways or approaches to points of delivery when material is to be delivered by trucks in places other than paved streets. We reserve the right to stop deliveries if the roadways or approaches are unsatisfactory to us. In the event Purchaser orders delivery beyond curb line, we will not assume liability for damage to sidewalks, driveways or other property and Purchaser hereby agrees to indemnify and hold Fremont Paving & Redi-Mix harmless against all liability, loss and expense incurred as a result of such deliveries. Customer is responsible for wrecker fees required on this delivery.
- I/we agree to pay an annual percentage rate of 24%. Failure to pay when agreed is basis for legal action to be taken and buyer agrees in event of suit to pay all cost of collection and reasonable attorney fees and hereby waives all rights of exemption as to personal property under the laws of the state of Colorado or any other state.
- Customer is required to provide mixer truck wash out on site.
- Fremont Paving & Redi Mix, Inc. agents and/or drivers may refuse to allow foreign chemicals to be added to the "mixer" at any time. Customer assumes full responsibility for the mix if he/she adds any water or other materials to the mix.
- We allow one hour unloading time free; any additional time will be billed at our normal rate.
- C.O.D. Deliveries must be paid on delivery.
- WE DO NOT GUARANTEE FINISHED RESULTS obtained from this load of concrete, as many important factors affecting the ultimate quality of the completed job are out of our control. We will not be responsible for any shortages if they are not reported at the time of delivery.

Water added on job _____

ADDED INGREDIENTS: Purchaser assumes FULL RESPONSIBILITY for strength, slump and quality of concrete when additional water or other material is requested on the job site. This load of concrete is produced in accordance with standard Specifications for Ready Mixed Concrete, A.S.T.M. Designation C-94-81 and the quality is guaranteed to be as indicated on the ticket with tested in accordance with these specifications. WARNING: Freshly mixed cement, mortar, concrete or grout contains chemicals which may cause skin irritation. Avoid contact with skin; take these PRECAUTIONS & KEEP AWAY FROM CHILDREN: Avoid all contact with eyes. Wear rubber boots and gloves and avoid prolonged contact directly with skin. In case of contact with skin or eyes: FLUSH THOROUGHLY WITH WATER. If irritation persists, promptly seek medical attention.



CUSTOMER'S REPRESENTATIVE
29095

PLEASE PAY FROM THIS INVOICE