

FORM
2
Rev
08/16

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
401180114

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Date Received:
01/10/2017

TYPE OF WELL OIL GAS COALBED OTHER _____
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Refiling
Sidetrack

Well Name: Piceance Federal Well Number: 29-18W
Name of Operator: LARAMIE ENERGY LLC COGCC Operator Number: 10433
Address: 1401 SEVENTEENTH STREET #1400
City: DENVER State: CO Zip: 80202
Contact Name: Joan Proulx Phone: (970)263-3641 Fax: ()
Email: jproulx@laramie-energy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120081

WELL LOCATION INFORMATION

QtrQtr: SENE Sec: 29 Twp: 9S Rng: 93W Meridian: 6
Latitude: 39.248489 Longitude: -107.788336

Footage at Surface: 2503 Feet FNL/FSL FNL 1293 Feet FEL/FWL FEL

Field Name: BUZZARD CREEK Field Number: 9500
Ground Elevation: 7531 County: MESA

GPS Data:
Date of Measurement: 04/22/2015 PDOP Reading: 1.2 Instrument Operator's Name: G McElroy

If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
946 FSL 1614 FWL 946 FSL 1614 FWL
Sec: 29 Twp: 9S Rng: 93W Sec: 29 Twp: 9S Rng: 93W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: applicant is owner

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Section 29 Communitized: CA No. COC-76682
Federal Lease COC 64786
Township 9S Range 93W 6th PM Mesa County, CO
Sec. 27: W2W2, NENW
Sec. 28: E2, NENW
Sec. 29: S2S2, SESW, S2SE
Sec. 30: SESW, Lot 4

Total Acres in Described Lease: 921 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # COC 064786

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 351 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1201 Feet
Building Unit: 4186 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 5280 Feet
Above Ground Utility: 513 Feet
Railroad: 5280 Feet
Property Line: 1293 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 396 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 946 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Section 29 Communitized: CA No. COC-76682
Federal Lease COC 64786
Township 9S Range 93W 6th PM Mesa County, CO
Sec. 27: W2W2, NENW
Sec. 28: E2, NENW
Sec. 29: S2S2, SESW, S2SE
Sec. 30: SESW, Lot 4

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK-ILES	WFILS	399-10	640	Sec 29 All

DRILLING PROGRAM

Proposed Total Measured Depth: 8466 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: _____ Feet No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Cuttings will be tested to Table 910 standards and will be buried on location. Drilling mud will be recycled/re-used in other drilling operations. Once all drilling operations are completed, drilling mud will be sent to a commercial disposal facility.

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26+0/0	16+0/0	112	0	60	100	60	0
SURF	11+0/0	8+5/8	24	0	1530	306	1530	0
1ST	7+7/8	4+1/2	11.6	0	8466	1368	8466	1030

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).

Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number _____

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: 334426

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 1/10/2017 Email: jproulx@laramie-energy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *Matthew Lee* Director of COGCC Date: 2/6/2017

Expiration Date: 02/05/2019

API NUMBER
05 077 10358 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>1)Operator shall comply with the most current revision of the Northwest Colorado Notification Policy.</p> <p>2)Operator shall comply with the Notice to Operators Drilling Wells in the Buzzard, Mamm Creek, and Rulison fields, Garfield County and Mesa County – Procedures and Submittal Requirements for Compliance with COGCC Order Nos. 1-107, 139-56, 191-22, and 369-2 (July 8, 2010).</p> <p>3)Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to a minimum of 200' above the Lower Wasatch (as defined by COGCC in the report "Casing and Cement Standards for Geologic Isolation Piceance Basin Bradenhead Monitoring Area and Nearby Fields," dated April 18, 2016, COGCC Document No. 2056199, Appendix A Field Scout Cards and Annotated Type Logs) to provide isolation of the Lower Wasatch, all Mesaverde Group formations including the Ohio Creek Formation, and underlying formations, if penetrated. Verify production casing cement coverage with a cement bond log. This requirement shall supersede the top of cement requirements in the Mamm Creek Field Notice to Operators.</p>
--	---

Best Management Practices

No BMP/COA Type

Description

1	Wildlife	<p>BMPS FOR Sensitive Wildlife Habitat and Restricted Surface Occupancy Areas Specific to Piceance Energy, LLC Operations within the Piceance Basin Mesa County, CO</p> <p>Sensitive Wildlife Habitat (SWH)</p> <p>Black Bear</p> <ul style="list-style-type: none"> • Initiate a food and waste/refuse management program that uses bear-proof food storage containers and trash receptacles. • Initiate an education program that reduces bear conflicts. • Establish policy to prohibit keeping food and trash in sleeping quarters. • Establish policy to support enforcement of state prohibition on feeding of black bear. • Report bear conflicts immediately to CPW . <p>Signature <u> </u>/s/ Wayne P. Bankert_____ Date <u> </u>9/19/2014_____</p> <p>Wayne P. Bankert Senior Reg. & Env. Coordinator</p>
2	Wildlife	<p>Best Management Practices (BMP's) To Reduce Impacts to Wildlife on the Gunderson 29-09 Pad For Operations in Sec. 29, Twn. 9S, Rng. 93W 6th PM Mesa County, CO</p> <p>COGCC Mapping indicates: ** NO RSO (Restricted Surface Occupancy) on the Gunderson 29-09 Pad ** SWH (Elk Winter Range and Black Bear) on the Gunderson 29-09 Pad Note: COGCC Order 399-7 Excuses Piceance Energy from consultation with CDOW (CPW) contained in rule 306c.</p> <p>In an effort to minimize the impacts to wildlife, the following BMP's are part of Piceance Energy's (PE) standard operating procedures for drilling and operations within the Piceance Basin. This list is a partial of PE's policy.</p>

Initial Stages for Infrastructure and Roads

1. Road design and General

- No firearms, no dogs on location, and no feeding of wildlife.
- Minimize the amount of traffic on lease roads within 3 hours of sunrise and sunset.
- Use existing routes as much as possible to avoid new disturbance and habitat fragmentation and minimize new road construction.
- Maximize the topography as much as possible in designing roads to reduce, visual, noise, impacts, etc.
- Participate in road sharing agreements with other Operators when possible.
- Design and surface roads based on the traffic, speed, and type of vehicles to reduce, dust, mud, and environmental damage.
- Locate roads away from riparian areas and bottoms of drainages as much as possible or re-route entirely.
- Obtain Army Corp of Engineer Permits for any stream crossings prior to construction.
- Analyze crossings and flow characteristics to determine the best method of crossing, (i.e. culvert, bridge, or low water).
- Armor all stream crossings to reduce erosion and to comply with Stormwater Requirements.
- Implementation of fugitive dust control measures including but not limited to water or magnesium chloride applications, and road surfacing.
- Limit traffic to the minimum needed for safe and efficient operations.
- No driving or parking off of disturbed areas.
- Install and use locked gates or other means when allowed by landowner or Federal Agencies to prevent unauthorized travel on roads and rights-of ways.

2. Well pad design and location

- Locate well pads to maximize directional drilling practices. PE currently plans and attempts to locate pads for the maximum number of wells which can safely be developed from each pad. This is normally 16-20 wells per pad which equates to roughly 4 well pads per section.
- Design each location to accommodate both current and future gas production.
- Locate well pads to minimize disturbance yet maximize use to reduce surface impacts.
- Review State and Federal GIS mapping to avoid Sensitive Wildlife Habitat (SWH), Restricted Surface Occupancy (RSO) areas, steep slopes, etc., as much as possible with roads and pad location.
- Design and install gathering lines within the disturbed area of new roads and adjacent to as much as possible to reduce disturbance construction.
- Design Rights-of Way widths to the minimum needed for safe and efficient construction of pipelines
- Remote Telemetry for production operations

3. Drilling and Production Operations

- Implement remote telemetry in all operations
- Where topographically possible and subject to landowner approval, use centralized water gathering and transportation systems.
- Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents, and openings.
- Locate facilities to minimize visual effects (e.g. paint color, screening, etc.)
- PE implements a dewatering system in its operations. No fluid pits are constructed or used during drilling or completion operations.
- PE implements an aggressive weed management program. PE incorporates and uses the BLM Colorado River Valley Field Office's "Noxious and Invasive Weed Management Plan for Oil and Gas Operators- March 2007" for all operations. Each spring, Piceance Energy inventories all pads, roads, and pipelines to insure no noxious weeds have been introduced. If noxious weeds are found, the county will be notified and the weeds will be treated. Weeds are continuously monitored and treated throughout the growing season. Only herbicides approved by the EPA and State are used by certified weed applicators.

4. Reclamation

		<ul style="list-style-type: none"> - Strip and segregate topsoil from other soil horizons during pad, road, and pipeline construction. - Minimize topsoil degradation by windrowing no higher than 5 feet when possible. - Immediately seed topsoil to reduce erosion and prevent weed establishment and maintain soil microbial activity. - Use only certified weed free native seed mixes, unless recommended otherwise by Federal Agencies or the Landowner. - Use locally adapted seed when available. - Use diverse seed mixes to mirror the surrounding area unless recommended otherwise by Federal Agencies or the Landowner. - Monitor re-vegetation success until a minimum of 75% of preferred perennial plant cover (no weeds) is established. - Perform "interim" reclamation on all disturbed areas not needed for active producing operations. - If possible, conduct interim and final reclamation during optimum periods (e.g. late fall/early winter or early spring). - If needed, fence reclaimed areas to minimize livestock/wildlife impact until plant species have are capable of sustaining grazing.
3	Drilling/Completion Operations	<p>One of the first wells drilled on the pad will be logged open-hole with a triple combo log (HRI w/SP, GR, CAL and Spectral Density/Dual Spaced Neutron) from TD into the surface casing. All wells on the pad will have a radial analysis bond log with gamma-ray run on production casing from TD to surface after the rig moves off the pad. All wells not logged with an open hole log will have a cased hole NEO neutron emulated open hole log run from TD to surface. The Form 5, Drilling Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API #, well name and number) the well in which open-hole logs were run.</p>

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Policy
NW Colorado Notification Policy. http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf
Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field). http://cogcc.state.co.us/documents/reg/Policies/NTO_07082010.pdf
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

Att Doc Num	Name
401180114	FORM 2 SUBMITTED
401180184	WELL LOCATION PLAT
401180188	DEVIATED DRILLING PLAN
401180189	TOPO MAP
401180191	DIRECTIONAL DATA
401180508	FED. DRILLING PERMIT

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Corrected the distance to the nearest building unit from 5280 to 4186 with operator approval. Final review complete.	02/02/2017
Engineer	Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 485 feet. Offset Well Evaluation: Existing offset oil and gas wells within 1,500 feet of this wellbore meet standards. No mitigation required.	01/17/2017
Permit	Well 29-17E has been moved. Corrected total acres in lease from 971' to 921' with operator approval. Corrected spacing order to reack 399-10 not 369-10 and added Sec 29 to the Unit configuration with operator approval. Changed distance to the unmit boundary from 945 to 946 with operator approval. Form passes completeness.	01/12/2017
Permit	Laramie is adding this well to the pad currently in process. We are updating the form 2A doc 401139697 with new attachments. This well will reside on the same spot as the 29-17E which is being moved. I am waiting on the new well location plat and directional survey in order to move the 29-17E so that we don't have two wells on the same spot. Once that is completed this form can be moved to in process.	01/10/2017

Total: 4 comment(s)