

**APPLICATION FOR PERMIT TO:**

**Drill**       Deepen       Re-enter       Recomplete and Operate

Date Received:  
01/26/2017

TYPE OF WELL    OIL     GAS     COALBED     OTHER \_\_\_\_\_      Refilling

ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES       Sidetrack

Well Name: Sanford      Well Number: J29-675

Name of Operator: NOBLE ENERGY INC      COGCC Operator Number: 100322

Address: 1625 BROADWAY STE 2200

City: DENVER      State: CO      Zip: 80202

Contact Name: Jan Kajiwara      Phone: (303)228-4092      Fax: ( )

Email: jan.kajiwara@nblenergy.com

**RECLAMATION FINANCIAL ASSURANCE**

Plugging and Abandonment Bond Surety ID: 20030009

**WELL LOCATION INFORMATION**

QtrQtr: NENW      Sec: 29      Twp: 5N      Rng: 66W      Meridian: 6

Latitude: 40.375700      Longitude: -104.804390

Footage at Surface:      748      Feet      FNL/FSL      2389      Feet      FEL/FWL      FWL

Field Name: WATTENBERG      Field Number: 90750

Ground Elevation: 4903      County: WELD

GPS Data:  
Date of Measurement: 06/13/2016    PDOP Reading: 1.9    Instrument Operator's Name: Brian Rottinghaus

If well is     Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**

Footage at Top of Prod Zone:    FNL/FSL      FEL/FWL      Bottom Hole:    FNL/FSL      FEL/FWL

990      FNL      2425      FWL      990      FNL      460      FEL

   Sec: 29      Twp: 5N      Rng: 66W      Sec: 27      Twp: 5N      Rng: 66W

**LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT**

Surface Ownership:     Fee       State       Federal       Indian

The Surface Owner is:     is the mineral owner beneath the location.  
(check all that apply)     is committed to an Oil and Gas Lease.  
    has signed the Oil and Gas Lease.  
    is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:     Fee       State       Federal       Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well:    Yes

The right to construct the Oil and Gas Location is granted by:    oil and gas lease

Surface damage assurance if no agreement is in place:      Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

5N-66W Sec. 29: NW, N2N2SW

Total Acres in Described Lease: 200 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 493 Feet  
Building Unit: 2046 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 274 Feet  
Above Ground Utility: 256 Feet  
Railroad: 5280 Feet  
Property Line: 290 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 0 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

Spacing Unit Docket # 1703000115

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

## DRILLING PROGRAM

Proposed Total Measured Depth: 20626 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 271 Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: 2614238

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	40	0	80	6	80	0
SURF	13+3/4	9+5/8	36	0	1850	658	1850	0
1ST	8+1/2	5+1/2	20	0	20695	2755		

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

**OTHER LOCATION EXCEPTIONS**

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

**OPERATOR COMMENTS AND SUBMITTAL**

Comments Eight well pad Sanford J30-690 (401152407), J30-685 (401152406), J30-680 (401152405), J30-675 (401152404), J29-690 (401152403), J29-685 (401152402), J29-680 (401152400), J 29-675 (401152397). Producing at J29-03 Multi (401152410) which is within disturbance area.  
Nearest well in the same formation calculated using COGCC data = 0' The lateral path will be less than the 150' minimum distance from another well as required by Rule 317.r. Noble is the Operator therefore, no consent letter is required per by Rule 317.s. Please see Anti-Collision BMP. Operator: Noble Energy, Inc. Well Names: Bensler J29-17D API 05-123-29137, Bensler J29-18D API 05-123-29139, Bensler J29-21D API 05-123-29136, UPV 27-1H6 API 05-123-18476, UPRC 27-3C API 05-123-17538, UPV 27-2H6 API 05-123-18477, UPRC 27-4C API 05-123-17594. Wells within 150' Noble operated: Igo 28-3H6 API 05-123-18373, UPV 29-2H6 API 05-123-18651, Igo Farms J28-31D API 05-123-30895. Nearest outside operated well, calculated using COGCC data = 271' Patina D&A Gracie J29-19 API 05-123-23203.  
Noble Energy, Inc. intends to permit this well as a monobore. No intermediate casing will be run. The surface casing will be set to cover the base of the Pierre Aquifer for Oil Based Mud considerations. Oil Based Mud will be planned for the production hole interval only. Noble Energy shall isolate both the Fox Hills and Upper Pierre Aquifers with surface casing from hydrocarbon bearing zones and exposure to oil based drilling fluid. Noble Energy also agrees to not expose the Upper Pierre Aquifer to oil based mud. All cuttings will be taken to a certified disposal. Exception Location and Twinning waiver language is included in attached SUA (Page 4, Section 6, Paragraph A).

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jan Kajiwara

Title: Regulatory Analyst Date: 1/26/2017 Email: regulatorynotification@nblener

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

**API NUMBER**  
05

**Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type	Description

## Best Management Practices

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
2	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place and maintained until the pad reaches final reclamation.
3	Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	If a skid is performed for the subject well, then the only required BOPE tests are for the BOPE connection bonnet seal breaks, as long as a full BOPE test was performed at the beginning of the pad, and as long as all necessary BOPE tests are completed at least every 30 days during the pad operations.
5	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with Cased hole Pulsed Neutron Log with Gamma Ray Log from kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.
6	Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed well path with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5. During and Post stimulation: Noble Energy will comply with the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated 5/29/12.

Total: 6 comment(s)

## Attachment Check List

<b>Att Doc Num</b>	<b>Name</b>
401152397	FORM 2 SUBMITTED
401191883	DIRECTIONAL DATA
401191884	DEVIATED DRILLING PLAN
401191885	WELL LOCATION PLAT
401191886	OPEN HOLE LOGGING EXCEPTION
401194359	OffsetWellEvaluations Data
401194362	SURFACE AGRMT/SURETY
401194837	EXCEPTION LOC REQUEST

Total Attach: 8 Files

**General Comments**

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>
		Stamp Upon Approval

Total: 0 comment(s)



**Public Comments**

No public comments were received on this application during the comment period.

