

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401200814

(SUBMITTED)

Date Received:

02/04/2017

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Brighton Lakes

Well Number: 3031-1-9HN

Name of Operator: WARD PETROLEUM CORPORATION

COGCC Operator Number: 10359

Address: 215 WEST OAK STREET #1000

City: FORT COLLINS

State: CO

Zip: 80521

Contact Name: Andrea Gross

Phone: (303)942-0506

Fax: ()

Email: agross@upstreampm.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20100221

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 20 Twp: 1S Rng: 66W Meridian: 6

Latitude: 39.944047

Longitude: -104.805222

Footage at Surface: 260 Feet FNL/FSL FSL 1010 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5049

County: ADAMS

GPS Data:

Date of Measurement: 12/12/2016 PDOP Reading: 1.3 Instrument Operator's Name: Dallas Neilsen

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
460 FNL 1650 FEL 460 FSL 1650 FEL
Sec: 30 Twp: 1S Rng: 66W Sec: 31 Twp: 1S Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Please see lease map

Total Acres in Described Lease: 51 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1121 Feet
Building Unit: 1121 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 247 Feet
Above Ground Utility: 289 Feet
Railroad: 5184 Feet
Property Line: 260 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 280 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Ward is on the March spacing docket. The docket number is 170300104.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	170300104	640	S.30:E2; S.31:E2

DRILLING PROGRAM

Proposed Total Measured Depth: 18033 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 37 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1500	509	1500	0
1ST	8+3/4	5+1/2	20	0	18033	2447	18033	

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Distance to the nearest well permitted in the same formation was measured to the permitted Brighton Lakes 3031-1-7HC. Distance to the nearest well by another operator was measured to the Freeman 1-A operated by K P Kauffman Company Inc. The Freeman 1-A is plugged and abandoned, therefore a stimulation setback consent is not required. The Exception Location Waiver for Rule 318A.a. (GWA Windows) and 318A.c. (GWA Twinning) is located in the attached Surface Use Plan in Section 6.18.

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Andrea Gross _____

Title: Permit Agent Date: 2/4/2017 Email: agross@upstreampm.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

No	BMP/COA Type	Description
1	Planning	Fencing: The wellsite will be fenced if requested by the Surface Owner.
2	Planning	Light sources during all phases of operations will be directed downwards and away from occupied structures. Permanent lighting will be installed around the facility to allow both the operator and haulers to conduct safe operations at night. All lights will be directed down toward the location or shielded so no light pollution leaves the facility. Sound walls will block temporary lighting.
3	Noise mitigation	Baseline noise monitoring and testing will be conducted prior to the commencement of construction. Sound mitigation will be designed based on the results of the study to meet COGCC noise requirements. During completion activities, onsite equipment shall be positioned to take full advantage of the sound mitigation measures provided by the sound walls, well pad grading, and surrounding topography. Sound wall(s) will remain in place through the end of completions operations.
4	Emissions mitigation	Green Completions: Test separators and associated flow lines and sand traps shall be installed on-site to accommodate Green completion techniques pursuant to COGCC Rules. Ward will utilize ECDs with adequate capacity, will be flanged to route gas to other or permanent oxidizing equipment and shall be provided with the equipment needed to maintain combustions where noncombustible gases are present.
5	Odor mitigation	Odor Control: Ward will comply with Rule 805 and Department of Public Health and Environment, Air Quality Control Commission, Regulation No. 2 Odor Emission, 5 C.C.R. 1001-4, Regulation No. 3 (5 C.C.R. 1001-5), and Regulation No. 7 Section XVII.B.1 (a-c) and Section XII. Ward will utilize Emission Control Devices to reduce odor emissions during production.
6	Drilling/Completion Operations	Closed Loop System: Closed Loop System will be used for drilling and fluid management. No reserve pit will be used.
7	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.
8	Drilling/Completion Operations	BOPE Testing: Upon initial rig-up and once every 30 days during drilling operations, pressure testing of the casing string and each component of the BOPE will be performed to 70% of working pressure or 70% of the internal yield of the casing, whichever is less.
9	Drilling/Completion Operations	BOPE for well servicing operations: Adequate blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves shall be required on well servicing operations during reverse circulation. Valves will be pressure tested before each well servicing operation using both low-pressure and high-pressure fluid.
10	Drilling/Completion Operations	BOPE: Ward will utilize drilling rigs with a minimum of a double ram and annular preventer.
11	Drilling/Completion Operations	Drill Stem Tests: Drill Stem Tests are not anticipated for this location.
12	Drilling/Completion Operations	Pit Level Indicators: Pit Level Indicators will not be needed as no pits will be used on location.
13	Drilling/Completion Operations	Anti-Collision: Ward will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice will be given to all offset operators within 150 feet prior to drilling.

Total: 13 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401200814	FORM 2 SUBMITTED
401200842	SURFACE AGRMT/SURETY
401200845	LEASE MAP
401200846	DEVIATED DRILLING PLAN
401200850	WELL LOCATION PLAT
401200851	WASTE MANAGEMENT PLAN
401200852	DIRECTIONAL DATA
401202405	OffsetWellEvaluations Data
401202406	EXCEPTION LOC REQUEST

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

