



Well History

Well Name: Noffsinger 32-5

API 05123204860000		Surface Legal Location SWNE 5 5N 64W		Field Name Wattenberg		State CO		Well Configuration Type Vertical					
Ground Elevation (ft) 4,630.00		Original KB Elevation (ft) 4,640.00		KB-Ground Distance (ft) 10.00		Spud Date 11/10/2001 00:00		Rig Release Date 11/15/2001 00:00		On Production Date 1/8/2002		Abandon Date	

Daily Operations

Start Date	Summary	End Date
11/21/2016	<p>CREW TO LOCATION. HELD SAFETY MEETING. NO PRESSURES. TOOH STANDING BACK 210 JTS, LD 10 JTS, LD BIT/SCRAPER. PU 4 1/2" STS'S RBP AND TIH W/ 209 JTS, SET RBP AT 6798.26', J-OFF OF RBP, LD 1 JTS. ESTABLISH CIRCULATION, CIRCULATED GAS OUT OF WELL. PRESSURE TEST CSG GOOD TO 2500# PSI. HOLD FOR 15 MINUTES. BLEED OFF PRESSURE. LD 4 MORE JTS, SPOT 2SX OF SAND, LD 5 MORE JTS. LAND WELL W 199 JTS AT 6470.09' KB. ND BOPS. NU WH. SWI. RDMO. CLEANED UP LOCATION. CREW TO YARD.</p> <p>LANDED TUBING AS FOLLOW;</p> <p>KB= 10.00' 199 JTS 2 3/8", 4.7#, J-55, 8RD TBG= 6465.89' SN= 1.20' RETREIVING HEAD= 3.00'</p> <p>TOTAL LANDED DEPTH= 6470.09' KB</p> <p>FMTD 11 JTS 2 3/8", 4.7#, J-55, 8RD TBG FROM WELL TO INVENTORY/ ATP YARD</p>	11/21/2016