

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401148283

Date Received:

11/16/2016

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: GM

Well Number: 705-34-8-HN2

Name of Operator: TEP ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: PO BOX 370

City: PARACHUTE

State: CO

Zip: 81635

Contact Name: Vicki Schoeber

Phone: (970)263-2721

Fax: ()

Email: vschoeber@terraep.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: LOT 7 Sec: 5 Twp: 7S Rng: 96W Meridian: 6

Latitude: 39.461156

Longitude: -108.125419

Footage at Surface: 774 Feet FNL/FSL FSL 868 Feet FEL/FWL FEL

Field Name: GRAND VALLEY

Field Number: 31290

Ground Elevation: 5977

County: GARFIELD

GPS Data:

Date of Measurement: 05/08/2013 PDOP Reading: 1.7 Instrument Operator's Name: Brian Baker

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

1685 FSL 1292 FEL 244 FSL 1383 FEL
Sec: 5 Twp: 7S Rng: 96W Sec: 8 Twp: 7S Rng: 96W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____

Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

LEASE IN THE FILE. The primary Federal Lease is COC24603. The "end of completions" falls in COC36219, 160 acres, SWSE, Section 8, T7S-R96W.

Total Acres in Described Lease: 2221 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC24603

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 601 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet
Building Unit: 5280 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 5280 Feet
Above Ground Utility: 5280 Feet
Railroad: 5280 Feet
Property Line: 1637 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 631 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 601 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

CA - COC049043, MVRD, 320 acres, E2 of Section 8, T7S-R96W
Exploratory Drilling & Spacing Unit - Sec 5: W2SE, E2SE (also described as Lot 6 & 7), Sec. 8: W2NE, SENE, NENE (also described as Lot 1), SE4

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	547-7	473	S-5 LOT 7, S-8 NE4

DRILLING PROGRAM

Proposed Total Measured Depth: 17600 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 1442 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Surface Cuttings Management Area

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	20	52.7	0	80	30	80	0
SURF	17+1/2	13+3/8	68	0	2693	707	2693	0
1ST	12+1/4	9+5/8	47	0	9452	828	9452	3345
S.C. 1.1	12+1/4	9+5/8	47	0	3800	488	3800	1693
2ND	8+1/2	5+1/2	23	0	17600	935	17600	8452

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This permit refill is to allow for changes in the TEP Rocky Mountain LLC drilling schedule. No changes have been made to the surface hole location, bottomhole location, lease description or surface use since the original permit was issued.

The Puckett 21A-17 well was used for the distance from proposed wellbore to nearest existing/permited wellbore belonging to another operator.

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: 334816

Is this application being submitted with an Oil and Gas Location Assessment application? _____ No _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Vicki Schoeber

Title: Regulatory Specialist Date: 11/16/2016 Email: vschoeber@terraep.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 2/19/2017

Expiration Date: 02/18/2019

API NUMBER

05 045 22662 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	The moisture content of water/bentonite based mud (WBM) generated drill cuttings managed onsite shall be kept as low as practicable to prevent accumulation of liquids greater than de minimis amounts. After drilling and completion operations have been completed, the WBM drill cuttings that will remain on the well pad location (cuttings management area, the cut portion of the pad, cuttings trench, dry cuttings drilling pit), must meet the applicable standards of Table 910-1. No liners are allowed to be disposed of with the drill cuttings. After the drill cuttings have been amended (if necessary) and placed on the well pad, sampling frequency of the drill cuttings (to be determined by the operator) shall be representative of the material left on location. No offsite disposal of cuttings to another oil and gas location shall occur without prior approval of a Waste Management Plan (submitted via a Form 4 Sundry Notice) specifying disposal location and waste characterization method. Commercial disposal of drill cuttings (i.e., a change in cuttings disposal method from the previously approved Form 2A) will require notification to COGCC via a Form 4 Sundry Notice.
	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016, revised October 6, 2016).
	1) Operator shall comply with the most current revision of the Northwest Notification Policy. 2) Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1). 3) Operator shall provide cement coverage from the intermediate casing shoe (9+5/8" First String) to a minimum of 200' above all Mesaverde Group (and Ohio Creek Formation, if present) oil, gas, and water-bearing sandstone and coalbed formations. Verify intermediate casing cement coverage with a cement bond log. 4) The operator's planned top of cement for the production casing (5 1/2" Second String) at about 1000' above the intermediate casing shoe is acceptable. Verify production casing cement coverage with a cement bond log.

Best Management Practices

No BMP/COA Type

Description

1	Drilling/Completion Operations	TEP will run triple-combo open hole logs in the vertical section of the Niobrara wells from KOP to base of surface casing on at least one well per pad location. CBL log will also be run from KOP up to surface. MWD/LWD logs with GR will be run for the lateral portion of the wells. Form 5 Completion Reports will identify wells on the pad with open hole logs.
---	--------------------------------	--

Total: 1 comment(s)

Applicable Policies and Notices to Operators

Policy
Piceance Rulison Field - Notice to Operators. http://cogcc.state.co.us/documents/reg/Policies/NoticeToOp-20060623-2.pdf
NW Colorado Notification Policy. http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

Att Doc Num

Name

401148283

FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

User Group

Comment

Comment Date

Final Review	Pushed back to pending for waste managment issue to be addressed by OGLA.	01/13/2017
Permit	According to the operator, and the previously submitted well location plat (page 2), the end of completion for this well is at 601' FSL making the BHL a legal location within the unit boundary. Final review complete.	01/11/2017
Engineer	Offset Well Evaluation: Existing offset oil and gas wells within 1,500 feet of this wellbore are shallow offsets or horizontal Niobrara wells. No mitigation required. Offset well evaluation data submitted with original Form 2 is in the well file. Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 36 feet.	11/23/2016
Permit	Passed completeness.	11/21/2016

Total: 4 comment(s)